



SECTION A-A



TYPICAL END TREATMENT AT SIDEWALK OR MEDIAN

Shorter plates with a single row of studs at 12" cts. may be necessary on medians which are shallower than 9". See manufacturer's recommendation.




<u>SECTION THRU</u> ROLLED RAIL JOINT

ILE NAME

#FILEL#

<u>SECTION THRU</u> WELDED RAIL JOINT

* Granular or solid flux filled headed studs conforming to Article 1006.32 of the Std. Specs., automatically end welded.



WELDED RAIL

LOCKING EDGE RAIL SPLICE

The inside of the locking edge rail groove shall be free of weld residue.

Rolled rail shown, welded rail similar.

LOCKING EDGE RAILS

Notes:

The strip seal shall be made continuous and shall have a minimum thickness of $\frac{1}{4}$ ". The configuration of the strip seal shall match the configuration of the Locking Edge Rails. Open or "webbed" strip seal gland configurations are not permitted. The gland shall be sized for a maximum rated movement of 4 inches.

The Locking Edge Rails depicted are conceptual only, except for the minimum dimensions shown. The actual configuration of the Locking Edge Rails and matching strip seal may vary from manufacturer to manufacturer. Flanged edge rails will not be allowed. Locking Edge Rails may be spliced at slope discontinuities.

The manufacturer's recommended installation methods shall be followed.

The joint opening and deck dimensions detailed on the superstructure are based on a rolled rail expansion joint. If the Contractor elects to use the welded rail expansion joint, the opening and deck dimensions shall be modified according to the dimensions detailed on this sheet. Required modifications shall be made at no additional cost to the State.

All steel components shall be galvanized after fabrication according to Article 520.03 of the Standard Specifications.

Maximum space between rail segments at stage lines shall be $^3{}_{16}$ ", sealed with a suitable sealant.

BILL OF MATERIAL

Item				Unit	Total
Preformed	Joint	Strip	Seal	Foot	190

FOR INFORMATION ONLY

MACTEC

COUNTY TOTAL SHEET NO.

 USER NAME =
 DESIGNED - JY
 REVISED

 CHECKED - RMK
 REVISED

 PLOT SCALE =
 DRAWN - JY
 REVISED

 PLOT DATE = 12/20/2010
 CHECKED - RMK
 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EXTRUDED RAIL

PREFORMED JOINT STRIP SEAL STRUCTURE NO. 049-0199 SHEET NO. 18 OF 43 SHEETS A.P. SECTION COUNTY TOTAL SHEETS NO. 330 128R-2-F LAKE 28 15

CONTRACT NO. 6OP54