

+1=16

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	VILLAGE OF ROUND LAKE PARK		VILLAGE OF ROUND LAKE
				80% FED. 20% LOCAL 0021	100% LOCAL 0021	80% FED. 20% LOCAL 0021
20200100	EARTH EXCAVATION	CU YD	252	236		16
20400800	FURNISHED EXCAVATION	CU YD	803	790		13
21101615	TOPSOIL FURNISH AND PLACE 4"	SQ YD	2377	2227		150
25000110	SEEDING CLASS 1A	ACRE	0.50	0.46		.04
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	41		4
25000500	PHOPHORUS FERTILIZER NUTRIENT	POUND	45	41		4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	41		4
25100630	EROSION CONTROL BLANKET	SQ YD	2387	2227		160
28000400	PERIMETER EROSION BARRIER	FOOT	2275	2100		175
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	11060	10310		750
42400400	PORTLAND CEMENT CONCRETE SIDEWALK 7 INCH	SQ FT	3200	3200		
42400800	DETECTABLE WARNINGS	SQ FT	22	12		10
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	457	457		
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1		
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTION 36"	EACH	3	3		
54216220	REINFORCED CONCRETE PIPE TEE, 36" PIPE WITH 12" RISER	EACH	2	2		
54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	3	3		
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	30	30		
550A0140	STORM SEWER, CLASS A, TYPE 1 30"	FOOT	30	30		
550A0160	STORM SEWER CLASS A TYPE 1 36"	FOOT	436	436		
55101600	STORM SEWER R. MOVAL 36"	FOOT	70	70		
60103500	PIPE DRAINS, CORRUGATED STEEL, 12"	FOOT	13			13
60207605	CATCH BASINS TYPE C, TYPE 8 GRATE	EACH	4	4		
60223700	MANHOLES, TYP A, 6'-DIAMETER TYPE 1 FRAME OPEN LID	EACH	4	4		
60500050	REMOVING CATCH BASINS	EACH	1	1		
66400305	CHAIN LINK FENCE 6'	FOOT	355	355		
67100100	MOBILIZATION	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12" (SPECIALTY ITEM)	FOOT	220	220		
Z0010555	DITCH CLEANING	FOOT	360		360	
Z0010600	CLEANING DRAINAGE SYSTEM	FOOT	540		540	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		

\* SPECIALTY ITEMS