

SUMMARY OF QUANTITIES

SPECIALTY ITEMS (Δ)	SPECIAL PROVISION (*)	PAYITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	ROADWAY 70% FEDERAL 30% LOCAL 0005
		20800150	TRENCH BACKFILL	CU YD	73	73
	*	21400100	GRADING AND SHAPING DITCHES	FOOT	250	250
		40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,455	3,455
		40600300	AGGREGATE (PRIME COAT)	TON	75	75
	*	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	640	640
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	4,380	4,380
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	3,135	3,135
		42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,195	1,195
	*	42400800	DETECTABLE WARNINGS	SQ FT	225	225
	*	44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	35,515	35,515
		44000600	SIDEWALK REMOVAL	SQ FT	1,195	1,195
		44201692	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	430	430
		44201694	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	430	430
		44201696	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	215	215
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	114	114
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	199	199
	*	60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	2,575	2,575
		60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1
		60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	6	6
		60204805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	1	1
		60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	8	8
		67100100	MOBILIZATION	L SUM	1	1
		70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	10,540	10,540
Δ		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	65	65
Δ		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,045	15,045
Δ		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,050	2,050
Δ		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	870	870
Δ		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	230	230
Δ		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	610	610
Δ		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	610	610
Δ	*	88600600	DETECTOR LOOP REPLACEMENT	FOOT	190	190
	*	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5,096	5,096
	*	Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	29	29
	*	Z0018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	8	8
	*	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
	*	X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	2,415	2,415
	*	X2520650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	2,018	2,018
	*	X5510100	STORM SEWER REMOVAL	FOOT	196	196
	*	XX000717	STORM SEWER CONNECTION, SPECIAL	EACH	3	3

COMPANY NAME: HRGreen.com
 PROJECT CONTACT: JStrozal
 DATE PLOTTED: 5/10/2011 9:18:13 AM
 FILE NAME: 86090304-sum-01.dgn
 PLOT DRIVER: McHenry-1050-plotter-AS.LS.DIF
 PEN TABLE: STANDARD-TRANS.TBL



USER NAME = JStrozal
 PLOT SCALE = N.T.S.
 PLOT DATE = 5/10/2011

DESIGNED - JJS
 DRAWN - JFA
 CHECKED - AC
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

VILLAGE OF BARTLETT

**SUMMARY OF QUANTITIES
 NEWPORT BOULEVARD**

SCALE: N.T.S. SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE. 3805	SECTION 11-00088-00-RS	COUNTY DUPAGE	TOTAL SHEETS 21	SHEET NO. 3
CONTRACT NO. 63604			ILLINOIS FED. AID PROJECT	