

## NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

## SEQUENCE OF CONSTRUCTION (PATCHING FIRST)

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE WITH CLASS C OR D PATCH.
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

## SEQUENCE OF CONSTRUCTION (MILLING FIRST)

- 1. MILL HMA FIRST IF THERE IS AT LEAST  $4\frac{1}{2}$  INCHES OR MORE OF HMA MATERIAL ON TOP OF THE EXISTING PAVEMENT OR IF THE PAVEMENT IS FULL DEPTH HMA. A MINIMUM OF 2 INCHES OF HMA MATERIAL SHALL BE IN PLACE AFTER MILLING.
- 2. REMOVE AND REPLACE WITH FULL DEPTH CLASS D PATCHES TO TOP OF MILLED SURFACE.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = bauerdl	DESIGNED - R. SHAH	REVISED - A. ABBAS 04-27-98			DAVENEST DATOURS COD	F.A. SECTION COUNTY TOTAL SHE
cs/projects/dsststd22x34/bd22.dgn		DRAWN -	REVISED - R. BORO 01-01-07	STATE OF ILLINOIS		PAVEMENT PATCHING FOR	RIE. SHEETS NO
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED - R. BORO 09-04-07	DEPARTMENT OF TRANSPORTATION		HMA SURFACED PAVEMENT	BD400-04 (BD-22) CONTRACT NO.
	PLOT DATE = 10/27/2008	DATE - 10-25-94	REVISED - K. ENG 10-27-08		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

FILE NAME =	USER NAME = ESIDORCZ	DESIGNED -	REVISED -			DISTRICT ONE DE	TAHC	F.A.U.	SECTION	COUNTY	TOTAL S	EET
N:\ELMW00DPARK\950253.00004\C1v11\DET.	950253_02.SHT	DRAWN -	REVISED -	STATE OF ILLINOIS		DISTRICT DIVE DE	IAILO	1774	10 00110 00 10	COOK	SHEETS	10.
	PLOT SCALE = 20'	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION SC					10-00112-00-LS	COOK	23	15
	PLOT DATE = 5/24/2011	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS STA.	TO STA.		ILI INOIS FED.	AID PROJECT	CONTRACT NO. 63608	