

SUMMARY OF QUANTITIES

SPECIALTY ITEM &/OR SPECIAL PROVISION	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
					0005		0021		0042	
					80% / 20% CASS	70% / 30% NON CASS	80% / 20% CASS	70% / 30% NON CASS	80% / 20% CASS	70% / 30% NON CASS
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	501	193	308				
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	606	299	307				
	20101000	TEMPORARY FENCE	FOOT	607	242	365				
	20101100	TREE TRUNK PROTECTION	EACH	4	1	3				
	20200100	EARTH EXCAVATION	CU YD	9395	1313	8082				
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	500		500				
	20700200	POROUS GRANULAR EMBANKMENT	CU YD	500		500				
	20800150	TRENCH BACKFILL	CU YD	1265	159	1106				
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	8905	1161	7744				
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	111	15	96				
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	111	15	96				
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	111	15	96				
	25200110	SODDING, SALT TOLERANT	SQ YD	8905	1161	7744				
	25200200	SUPPLEMENTAL WATERING	UNIT	107	14	93				
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	183	24	159				
SI	28000400	PERIMETER EROSION BARRIER	FOOT	3786	1051	2735				
SI	28000500	INLET AND PIPE PROTECTION	EACH	12	1	11				
SI	28000510	INLET FILTERS	EACH	60	22	38				
	31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	124		124				
	31101400	SUB BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1659	266	1393				
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	457		457				
	35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	2611	945	1666				
	35400200	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 7"	SQ YD	3260	2399	861				
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	2796		2796				
SP	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	667	269	398				
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4782	1331	3451				
	40600300	AGGREGATE (PRIME COAT)	TON	176	51	125				
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	692	262	430				
	40600895	CONSTRUCTING TEST STRIP	EACH	3	1	2				
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1313	592	721				
	40600990	TEMPORARY RAMP	SQ YD	209	82	127				
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	6795	1537	5258				
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	363	51	312				
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4741	1030	3711				
	42001300	PROTECTIVE COAT	SQ YD	3109	1281	1828				
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	352		352				
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	59722	14999	44723				

SP(CB) = SPECIAL PROVISION REQUIRED BY IDOT PAY CODE BOOK SP(OTHER) = SPECIAL PROVISION REQUIRED TO CLARIFY ITEM SI=SPECIALITY ITEM BDE=BUREAU OF DESIGN AND ENVIRONMENT GBSP=GUIDE BRIDGE SPECIAL PROVISION
 CASS = (CASS AVE. & STA. 32+06.35 TO STA. 42+53.50 ALONG C.H. 35 (55TH ST.)) / NON CASS = (ALL REMAINING AREAS)

FILE NAME =
 vs\2791\2791q001.dgn

USER NAME = bdecrsene
 PLOT SCALE = 1.000" / IN.
 PLOT DATE = 6/23/2011

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

C.H. 35 (55TH ST.)
 SUMMARY OF QUANTITIES
 SCALE: N/A SHEET NO. 1 OF 6 SHEETS STA. N/A TO STA. N/A

F.A.U. RTE. 1504	SECTION 94-00302-00-FP	COUNTY	TOTAL SHEETS 240	SHEET NO. 3
CONTRACT NO. 63609			ILLINOIS FED. AID PROJECT	