

PAVEMENT																						
LOCATION			BITUMINOUS MATERIALS (PRIME COAT) (0.08 GAL/SY)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	HOT-MIX ASPHALT SURFACE COURSE MIX "D", N70	PCC BASE COURSE WIDENING 7"	HOT-MIX ASPHALT BASE COURSE 8"	HOT-MIX ASPHALT BASE COURSE (VARIABLE DEPTH)	LEVELING BINDER (MACHINE METHOD), N70	AGGREGATE SUBGRADE, 16"	SUB-BASE GRANULAR MATERIAL TYPE B 6"	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SURFACE REMOVAL 1"	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL 3 3/4"	HOT-MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY PAVEMENT (10')	PAVEMENT REMOVAL	CONCRETE PAVEMENT SCARIFICATION	TEMPORARY RAMP
STATION	TO	STATION	GALLON	TON	TON	TON	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
C.H. 35 (55TH ST.)																						
9+50.00	TO	32+06.35	842.3	31.5	1326.7	884.4										10529.6						23.3
NON CASS SUB-TOTAL			842.3	31.5	1326.7	884.4										10529.6						23.3
C.H. 35 (55TH ST.)																						
32+06.35	TO	34+47.75	208.0	7.8	163.8	109.2	173.6				321.3					1126.5						
34+47.75	TO	38+38.66	382.2	14.3	300.9	200.6	564.6		27.5	554.1						1824.2						
38+38.66	TO	42+41.98	211.0	11.2	286.3	190.8	390.3			666.5						1881.7						
CASS AVE.																						
193+79.86	TO	199+72.50	287.1	10.7	452.2	301.5	744.7				1134.2					2845.0	97.7					24.4
200+27.50	TO	204+13.63	133.3	5.0	210.0	133.3	360.5		166.3	584.8						1307.0	337.7					21.1
LINDEN ST. (NORTH)			25.0	0.9	10.1	46.7	81.6					132.9	4.9		234.7					76.6		17.8
LINDEN ST. (SOUTH)			21.9	1.0	10.0	47.9	83.5		68.2			133.0	1.8		244.0					79.5		17.8
CASS SUB-TOTAL			1266.6	50.9	1433.3	1030.0	2398.8		262.0	3260.9	265.9	6.7		478.7	4832.4	4152.0	591.5					81.1
C.H. 35 (55TH ST.)																						
42+41.98	TO	83+40.00	1529.9	57.3	2409.6	1606.4										19124.4						23.3
83+40.00	TO	89+97.96	245.5	9.2	444.7	296.3			1740.8	746.6				3070.5								
84+00.00	TO	87+52.83																			193.2	
88+07.95	TO	96+62.03																			402.7	
89+97.96	TO	93+80.66			294.6	261.9			2338.7	2600.6											1785.9	
93+80.66	TO	96+26.67	120.3	4.5	187.3	124.9				425.4			1230.4									
96+26.67	TO	100+55.52	189.3	7.1	330.2	220.1	235.9		212.1	403.1												2384.9
100+55.52	TO	101+33.03	28.9	1.0	2.6	31.3				64.2										280.0		23.3
NON CASS SUB-TOTAL			2113.9	79.1	3669.0	2540.9	235.9	2338.7	2234.4	212.1	4239.9			4662.6		19124.4		280.0	595.9	1785.9	2384.9	46.6
CLARENDON HILLS RD.																						
196+18.00	TO	199+72.50	91.6	3.9	34.2	112.9	271.8		62.2		479.9									186.6		11.6
NON CASS SUB-TOTAL			91.6	3.9	34.2	112.9	271.8		62.2		479.9									186.6		11.6
ADDITIONAL SIDEROADS																						
LINCOLN ST.			12.3	0.5	8.0	30.2	63.4				98.6				111.8					46.4		12.2
ALABAMA AVE.			23.6	1.0	11.9	46.8	98.3		37.5		148.7	5.2			241.4					66.8		10.2
WALKER AVE.			24.1	1.0	11.6	47.7	96.4		48.5		147.8	3.9			254.9					70.5		11.5
PROSPECT AVE.			24.1	1.0	11.4	47.6	94.6		69.6		146.7	8.1			256.5					71.1		11.6
NON CASS SUB-TOTAL			84.1	3.5	42.9	172.3	352.7		155.6		541.8	17.2			864.6					254.8		45.5
SUB-TOTAL			4398.5	168.9	6506.1	4740.5	3259.2	2338.7	2234.4	691.9	7500.8	1287.6	23.9	4662.6	1343.3	34486.4	4152.0	1312.9	595.9	1785.9	2384.9	208.1
TOTAL			4399	169	6507	4741	3260	2339	2235	692	7501	1288	24	4663	1344	34487	4152	1313	596	1786	2385	209

VARIOUS SIDEROADS						
STATION	STREET	SIDE	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	HOT-MIX ASPHALT SURFACE COURSE, "MIX C", N50	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE PRIME COAT
			SQ YD	TON	GALLON	TON
10+00.00	WILLIAMS ST.	LT	97.2	8.1	7.7	0.3
13+61.20	PARK ST.	LT	71.8	6.0	5.7	0.2
15+00.00	PARK ST.	RT	96.1	8.0	7.6	0.3
17+33.00	HUDSON ST.	LT	81.3	6.8	6.5	0.2
18+29.70	LINDLEY RD.	RT	113.4	9.5	9.0	0.3
21+14.20	WASHINGTON ST.	LT	71.4	5.9	5.7	0.2
21+93.20	WASHINGTON ST.	RT	124.7	10.5	10.0	0.4
24+85.20	ADAMS ST.	LT	78.0	6.6	6.2	0.2
28+78.10	GRANT ST.	LT	77.0	6.5	9.2	0.2
42+88.80	WARWICK AVE.	RT	63.5	5.3	5.1	0.2
43+96.00	WARWICK AVE.	LT	110.0	9.2	8.8	0.3
49+61.80	WILMETTE AVE.	RT	141.9	11.9	11.3	0.4
49+65.30	WILMETTE AVE.	LT	111.2	9.3	8.8	0.3
56+29.70	OAK AVE.	LT	110.6	9.2	8.8	0.3
57+92.00	OAK AVE.	RT	85.2	7.2	6.8	0.3
62+86.90	RICHMOND AVE.	LT	125.0	10.5	10.0	0.4
69+51.80	WESTERN AVE.	RT	221.8	18.6	17.7	0.7
70+44.30	WESTERN AVE.	LT	140.1	11.7	11.2	0.4
76+26.50	BENTLEY AVE.	RT	106.8	8.9	8.5	0.3
79+40.50	VIRGINA AVE.	RT	103.3	8.6	8.2	0.3
82+74.90	TENNESSEE AVE.	RT	105.7	8.8	8.4	0.3
TOTAL			2236	187	182	7