

COMBINATION CONCRETE CURB AND GUTTER							
STATION / LOCATION	TO	STATION / LOCATION	SIDE	TYPE B-6.12	TYPE B-6.18	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	PROTECTIVE COAT
				FOOT		SQ YD	SQ YD
<b>CH 35 (55TH ST.)</b>							
9+67.00	TO	10+36.00	LT	12		2	2.7
13+28.00	TO	13+94.00	LT	45		7	9.9
14+27.00	TO	14+50.00	LT	23		4	5.1
14+61.00	TO	15+42.00	RT	51		8	11.3
16+98.00	TO	17+65.00	LT	43		7	9.6
17+85.00	TO	18+70.00	RT	52		9	11.6
20+81.00	TO	21+45.00	LT	41		7	9.1
21+55.00	TO	22+36.00	RT	48		8	10.8
24+61.00	TO	25+30.00	LT	43		7	9.4
28+48.00	TO	29+11.00	LT	43		7	9.6
30+33.00	TO	30+54.00	RT	21		3	4.6
31+01.00	TO	31+21.00	RT	19		3	4.3
NON CASS SUB-TOTAL				441		73	98
32+06.35	TO	CASS AVE.	LT	127	258		99.7
31+72.87	TO	CASS AVE.	RT		398		110.5
CASS AVE.	TO	LINDEN ST.	LT	62	268		88.0
CASS AVE.	TO	LINDEN ST.	RT	64	215		74.0
LINDEN ST.	TO	42+46.64	LT	53	185		63.1
LINDEN ST.	TO	42+53.50	RT	67	237		80.6
CASS SUB-TOTAL				372	1560		516
42+59.00	TO	43+23.00	RT	46		8	10.2
43+63.00	TO	44+26.00	LT	12		2	2.7
45+70.00	TO	45+80.00	LT	10		2	2.2
49+25.00	TO	49+98.00	RT	12		2	2.7
49+27.00	TO	50+02.00	LT	50		8	11.0
55+99.00	TO	56+59.00	LT	12		2	2.7
57+57.00	TO	58+27.00	RT	43		7	9.5
62+52.00	TO	63+23.00	LT	22		4	5.0
69+12.00	TO	69+86.00	RT	21		3	4.6
70+16.00	TO	70+72.00	LT	12		2	2.7
74+58.00	TO	74+91.00	RT	33		6	7.4
75+89.00	TO	76+57.00	RT	12		2	2.7
79+06.00	TO	79+77.00	RT	12		2	2.7
82+40.00	TO	83+10.00	RT	6		1	1.3
83+10.00	TO	ALABAMA AVE.	RT	56	253		82.5
83+40.00	TO	WALKER AVE.	LT	54	392		120.9
ALABAMA AVE.	TO	CLARENDON HILLS RD.	RT	52	240		78.1
WALKER AVE.	TO	PROSPECT AVE	LT	107	834		255.6
CLARENDON HILLS RD.	TO	101+33.03	RT	192	1164		365.9
PROSPECT AVE.	TO	101+33.03	LT	52	395		121.4
NON CASS SUB-TOTAL				815	3278	50	1092
<b>CASS AVE. (SOUTH LEG)</b>							
193+79.86	TO	W. 55th PLACE	LT	52	206		68.6
55th PLACE	TO	CH 35 / 55th ST	LT	51	328		102.4
193+79.86	TO	CH 35 / 55th ST	RT		616		171.1
<b>CASS AVE. (NORTH LEG)</b>							
55th ST	TO	203+29.07	LT	316			70.2
55th ST	TO	203+29.07	RT	318			70.7
CASS SUB-TOTAL				738	1149		483
<b>CLARENDON HILLS RD.</b>							
701+17.94	TO	C.H. 35 (55TH ST.)	LT	376			83.5
701+17.94	TO	C.H. 35 (55TH ST.)	RT	399			88.7
NON CASS SUB-TOTAL				775			172
NON CASS TOTAL				2030	3278	124	1362
CASS TOTAL				1110	2709		999
TOTAL				3140	5987	124	2361

SHORT-TERM PAVEMENT MARKING							
STATION	TO	STATION	LANE LINES	MEDIAN LINES	"ONLY"	ARROWS	STOP BARS
			SKIP DASH - WHITE 4"	SKIP DASH - YELLOW 4"	WHITE 4"	WHITE 3 - 4" STRIPES	WHITE 6 - 4" STRIPES
							FOOT
<b>C.H. 35 (55TH ST.)</b>							
9+50.0	TO	32+06.4	394	337			702
NON CASS SUB-TOTAL			394	337			702
32+06.4	TO	42+42.0	195	204	192	137	804
<b>CASS AVE.</b>							
193+79.9	TO	200+00.0	112	111	192	137	324
200+00.0	TO	203+29.1	40	52	64	46	240
CASS SUB-TOTAL			347	367	448	320	1368
42+42.0	TO	101+33.0	1068	1040	128	273	1770
<b>CLARENDON HILLS RD.</b>							
701+17.9	TO	705+00.0	13	95	64	46	198
NON CASS SUB-TOTAL			1081	1135	192	319	1968
NON CASS TOTAL			1475	1472	192	319	2670
CASS TOTAL			347	367	448	320	1368
TOTAL			1822	1839	640	639	4038
USE							8978

TEMPORARY PAVEMENT MARKING													
STATION	TO	STATION	LETTERS AND SYMBOLS		LINES								
			TURN	"ONLY"	4"		6"		12"	24"			
			SO FT		SOLID WHITE	SOLID YELLOW	DBL YELLOW	SKIP-DASH WHITE	SKIP-DASH YELLOW	DOTTED WHITE	SOLID WHITE	SOLID YELLOW	SOLID WHITE
					EDGE OF PAV'T.	LANE DIVISION	MEDIAN	CENTER LINE	CENTER LINE	TAPER	CROSSWALK	MEDIAN/DIAG.	STOP BAR
					FOOT								
<b>C.H. 35 (55TH ST.)</b>													
9+50.0	TO	32+06.4						3370	986				117
NON CASS SUB-TOTAL								3370	986				117
NON CASS TOTAL								4356					117
32+06.4	TO	42+42.0	46.8	62.4	125		2035	387		78	654	10	134
<b>CASS AVE.</b>													
193+79.9	TO	200+00.0	46.8	62.4			1111	179		74	548		54
200+00.0	TO	203+29.1	15.6	20.8			520	70		41	279		40
CASS SUB-TOTAL			109.2	145.6	125		3666	636		193	1481	10	228
CASS TOTAL			254.8				4427			1674		10	228
42+42.0	TO	101+33.0	93.6	41.6	301	642	9758	2595	161	116	423	152	295
<b>CLARENDON HILLS RD.</b>													
701+17.9	TO	705+00.0	15.6	20.8			945			39	263	8	33
NON CASS SUB-TOTAL			109.2	62.4	301	642	10703	2595	161	155	686	160	328
NON CASS TOTAL			171.6				14402			841		160	328
NON CASS TOTAL			171.6				18758			841		160	445
CASS TOTAL			254.8				4427			1674		10	228
TOTAL			427				23185			2515		170	673