THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" ADOPTED JANUARY 1, 2011; AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THIS PROJECT IS LOCATED AT THREE INTERSECTION ON FAP 322 (US 51) AROUND THE CITY OF MAROA, IN MACON COUNTY. THE WORK INCLUDED IN THIS SECTION CONSISTS OF THE INSTALLATION OF HIGHWAY LIGHTING AT THE THREE SEPARATE LOCATIONS AND ALL OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

THE LOCATION OF BURIED AND ABOVE GROUND UTILITIES SHOWN ARE APPROXIMATE, AND ARE SHOWN FOR THE CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTION PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVE GROUND UTILITY LOCATIONS, IDENTIFICATION, AND MARKINGS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REROUTING, DISCONNECTION, PROTECTION, ETC., OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVE GROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL VERIFY THE EXACT LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING CONSTRUCTION. CALL J.U.L.I.E. AT 1-800-892-0123.

THE CONTRACTOR IS RESPONSIBLE FOR UNCOVERING OR HAND DIGGING AROUND UTILITIES AS NECESSARY. THE COST OF THIS WORK IS TO BE INCLUDED WITH THE TRENCH AND BACKFILL FOR ELECTRICAL WORK PAY ITEM.

KNOWN UTILITIES LOCATED WITHIN THE LIMITS OF THIS IMPROVEMENT ARE:

AMEREN-IP
ROBERT J. ZUEGE
SUPERVISING ENGINEER
2400 NORTH JASPER STREET
DECATUR, IL 62526
PH: 217-424-7075

ALMEGA COMMUNICATIONS
PHIL CLARO
1204 S. SECOND ST.
GILLESPIE, IL 62033
CELL: 765-714-5328
Phillipc@almegaonline.com

VERIZON
CHARLES JENKINS
330 W. BEECHER
JACKSONVILLE, IL 62650
PH. 217-243-0211
charles.jenkins@verizon.com

CITY OF MAROA
BILL ZOMBRO
P. O. BOX 136
MAROA, IL 61756
PH: 217-794-2206

1	COVER SHEET
2	INDEX OF SHEETS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	LOCATION MAP
5	LIGHTING SCHEDULE
6	HIGHWAY LIGHTING LOCATION #1 (WOODS ST INTERSECTION)
7	HIGHWAY LIGHTING LOCATION #2 (W. WASHINGTON ST INTERSECTION)
8	HIGHWAY LIGHTING LOCATION #3 (LAKE FORK RD INTERSECTION)
9	POLE HANDHOLE WIRING DETAIL
10	POLE STANDARDS
11	DETAIL FOR NIGHTTIME LIGHTING INSPECTION

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 11:

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 15' AWAY
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701406-06	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701421-03	LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY, FOR SPEEDS >=45 MPH TO 55 MPH
701901-01	TRAFFIC CONTROL DEVICES
825001-01	LIGHTING CONTROLLER, POLE MOUNTED, 240V
836001	LIGHT POLE FOUNDATION