

ITEM NO	PAY ITEM #	DESCRIPTION	CONST. TYPE CODE 0005			
			UNIT	QTY	Sp Pr	SP
1	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50		
2	25200100	SODDING	SQ YD	611		
3	40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6		
4	40600300	AGGREGATE (PRIME COAT)	TON	4		
5	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	3		
6	40600525	LEVELING BINDER (HAND METHOD), N50	TON	25		
7	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	186		
8	40600990	TEMPORARY RAMP	SQ YD	58		
9	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	834		
10	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	74		
11	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,346		
12	42400800	DETECTABLE WARNINGS	SQ FT	88		
13	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	74		
14	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,672		
15	44000600	SIDEWALK REMOVAL	SQ FT	1,410		
16	44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	1,076		
17	44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	356		
18	44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	127		
19	44213200	SAW CUTS	FOOT	72		
20	50800105	REINFORCEMENT BARS	POUND	67		
21	60107600	PIPE UNDERDRAINS 4"	FOOT	40		
22	60251520	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11V FRAME AND GRATE	EACH	11		
23	60255500	MANHOLES TO BE ADJUSTED	EACH	11		
24	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2		
25	60266600	VALVE BOXES TO BE ADJUSTED	EACH	5		
26	60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1		
27	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,672		
28	70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,146		
29	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	223		
30	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	502		X

ITEM NO	PAY ITEM #	DESCRIPTION	CONST. TYPE CODE 0005			
			UNIT	QTY	Sp Pr	SP
31	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7,283		X
32	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	715		X
33	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	209		X
34	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	122		X
35	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20		
36	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20		
37	88600600	DETECTOR LOOP REPLACEMENT	FOOT	556	*	X
38	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	9,264	*	
39	X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1	*	
40	X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	*	
41	XX008348	MORTAR EXISTING STRUCTURE	EACH	2	*	
42	Z0001110	GAS VALVE TO BE ADJUSTED	EACH	1	*	
43	X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	3,310	*	

* DENOTES SPECIAL PROVISION PROVIDED

X DENOTES SPECIALTY ITEM

FILE NAME = *FILEL*	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = *SCALE*	DRAWN -	REVISED -			5352	09-00176-01-RS	DEKALB	15	3	
	PLGT DATE = *DATE*	CHECKED -	REVISED -			CONTRACT NO. 87492					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT NO. M-5017(047)					
						SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.