

HOT-MIX ASPHALT								
Location	Width	Length	HMA Surf.	HMA Surf.	*Bit. Prime	Agg. Prime	Mix. Crck./Jts./Flg.	Temp. Ramps
			Rem Sq Yd	N50 Tons	Tons	Tons	Tons	Sq Yds
North of Ridge	38	319	1346.89	121.22	0.87	0.64	0.40	
Ridge Dr to Laurel Lane	38	480	2026.67	182.40	1.31	0.96	0.61	14.00
Laurel Lane to Forsythe Lane	38	320	1351.11	121.60	0.88	0.64	0.41	14.00
Forsythe Lane to Windsor Drive	38	375	1583.33	142.50	1.03	0.75	0.48	14.00
Windsor Drive to Tilton Park Drive	38	350	1477.78	133.00	0.96	0.70	0.44	
Tilton Park Drive to Hillcrest Drive	38	350	1477.78	133.00	0.96	0.70	0.44	16.20
TOTAL		2194	9264	834	6	4	3	58

*Assume 2 Applications

THERMOPLASTIC PAVEMENT MARKING							
Location	Short-Term	4"	6"	12"	24"	L&S	Removal
	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)
North of Ridge	372	1076		40	25	74	27.00
Ridge Dr to Laurel Lane	360	1580	202	60	13	104	119.91
Laurel Lane to Forsythe Lane	271	1020	66		15	84	90.45
Forsythe Lane to Windsor Drive	328	1280	62		17	84	36.00
Windsor Drive to Tilton Park Drive	319	1148	66		18	104	35.00
Tilton Park Drive to Hillcrest Drive	497	1179	319	109	34	52	55.00
TOTAL	2146	7283	715	209	122	502	363

PAVEMENT REMOVAL AND REPLACEMENT			
Location	Width	Length	Sq Yd
North of Ridge	14.4	319	510.40
Ridge Dr to Laurel Lane	14.4	480	768.00
Laurel Lane to Forsythe Lane	14.4	320	512.00
Forsythe Lane to Windsor Drive	14.4	375	600.00
Windsor Drive to Tilton Park Drive	14.4	350	560.00
Tilton Park Drive to Hillcrest Drive	14.4	225	360.00
TOTAL		2069	3310

CLASS "D" PATCHING						
Location	Width	Length	Quantity	Type II	Type III	Type IV
Laurel Lane	8	13	2		23.11	
Laurel Lane	9	13.5	2			27.00
Windsor Drive	6	17	2		22.67	
*TBD	12	8	2	21.33		
*TBD	12	6	7	56.00		
*TBD	12	10	10	133.33		
*TBD	12	4	156	832.00		
*TBD	15	4	1	6.67		
*TBD	30	4	2	26.67		
*TBD	12	12	4		64.00	
*TBD	15	12	9		180.00	
*TBD	20	10	3		66.67	
*TBD	25	12	3			100.00
TOTAL			203	1076	356	127

*Locations measured in the field for quantity purposes only. Final patch locations to be determined in the field by the Engineer

PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH						
From Sta	To Sta	Ref	Width	Avg Length	Area	
241+33.00	241+63.00	RT	7	25	19	
246+19.00	246+49.00	LT	7	25	19	
246+70.00	247+00.00	LT	7	25	19	
255+32.00	255+47.00	RT	7	13	10	
255+53.00	255+70.00	RT	3	16	5	
TOTAL					74	