

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. II	10-00962-00-BR	CHAMPAIGN	40	4
STA.		TO STA.		
F.H.W.A. REG.		ILLINOIS PROJECT		

SCHEDULE OF QUANTITIES

60900140 TYPE B INLET BOX STANDARD 609006		
LOCATION		EACH
9+18.75	RT	1
9+18.75	LT	1
10+81.00	RT	1
10+81.00	LT	1
TOTAL		4

48101500 AGGREGATE SHOULDERS, TYPE B, 6"				
STATION TO STATION				SQ YD
8+37	9+03	LT		29.2
8+50	9+03	RT		23.4
10+97	12+18	LT		53.7
10+97	11+50	RT		23.4
TOTAL				129.8

78008210 POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"				
STATION TO STATION			FOOT	COLOR/TYPE
8+50	11+50	RT	300.0	WHITE/EDGE
8+50	11+50	LT	300.0	WHITE/EDGE
8+50	11+50	CL	75.0	YELLOW/CL
TOTAL				675

40600100 BITUMINOUS MATERIALS (PRIME COAT)	
ON THIS BASE	GALLON
MILLED SURFACE	27.0
LEVELING BINDER	27.0
TOTAL 54.0	
NOTE: CALCULATED @ 0.1 GAL/SY	

40600625 LEVELING BINDER (MACHINE METHOD), N50					
STATION TO STATION		LENGTH FOOT	WIDTH FOOT	THICK INCHES	TON
LT 8+50	9+03	53	11.5	3/4	2.8
RT 8+50	9+03	53	11.5	3/4	2.8
LT 10+97	11+50	53	11.5	3/4	2.8
RT 10+97	11+50	53	11.5	3/4	2.8
CONTINGENCY					0.8
TOTAL					12.0

60100945 PIPE DRAINS, 12"		
LOCATION		FOOT
9+18.75	RT	15
9+18.75	LT	15
10+81.00	RT	15
10+81.00	LT	15
TOTAL		60

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6			
STATION TO STATION			EACH
8+74.60	9+17.75	LT	1
10+82.25	11+25.40	LT	1
10+82.25	11+25.40	RT	1
TOTAL			3

63100070 TRAFFIC BARRIER TERMINAL, TYPE 5			
STATION TO STATION			EACH
9+18.08	9+32.75	RT	1
TOTAL			1

40600300 AGGREGATE (PRIME COAT)	
ON THIS BASE	TON
MILLED SURFACE	0.40
LEVELING BINDER	0.40
TOTAL 0.8	
NOTE: CALCULATED @ 3LB/SY	

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50					
STATION TO STATION		LENGTH FOOT	WIDTH FOOT	THICK INCHES	TON
LT 8+50	9+03	53	11.5	VARIES	9.1
RT 8+50	9+03	53	11.5	VARIES	9.1
LT 10+97	11+50	53	11.5	VARIES	9.9
RT 10+97	11+50	53	11.5	VARIES	9.9
CONTINGENCY					2.0
TOTAL					40.1
NOTE: CALCULATIONS USED 112 LB/SY/INCH					

60900515 CONCRETE THRUST BLOCKS		
LOCATION		EACH
9+18.75	RT	1
9+18.75	LT	1
10+81.00	RT	1
10+81.00	LT	1
TOTAL		4

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2			
STATION TO STATION			EACH
8+37.10	8+49.60	LT	1
11+37.90	11+50.40	RT	1
TOTAL			2

63300725 STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)			
STATION TO STATION			FOOT
8+97.93	9+18.08	RT	25
12+00.40	12+16.90	LT	25
TOTAL			50

44000157 HOT-MIX ASPHALT SURFACE REMOVAL, 2"				
STATION TO STATION		LENGTH FOOT	WIDTH FOOT	SQ YD
LT 8+50	9+03	53	11.5	67.0
RT 8+50	9+03	53	11.5	67.0
LT 10+97	11+50	53	11.5	67.0
RT 10+97	11+50	53	11.5	67.0
TOTAL				268.0

54213447 END SECTIONS 12"		
LOCATION		EACH
9+18.75	RT	1
9+18.75	LT	1
10+81.00	RT	1
10+81.00	LT	1
8+70.00	RT	1
TOTAL		5

63000001 STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS				
STATION TO STATION				FOOT
8+49.60	8+74.60	LT		25.0
11+25.40	12+00.40	LT		75.0
11+25.40	11+37.90	RT		12.5
TOTAL				112.5

SECTION: 10-00962-00-BR
CHAMPAIGN COUNTY
Q STATION 10+00