

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. II	10-00962-00-BR	CHAMPAIGN	40	12
STA.		TO STA.		
F.H.W.A. REG.		ILLINOIS PROJECT		

CL ROADWAY AND PGL

LOCATION	STATION	OFFSET	THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. Of W. Abut	9+32.75	0	690.76	690.76
Cl. W. Abut	9+34.00	0	690.76	690.76
A	9+44.00	0	690.79	690.81
B	9+54.00	0	690.82	690.84
C	9+64.00	0	690.84	690.85
Cl. Pier 1	9+74.00	0	690.85	690.85
D	9+84.00	0	690.86	690.88
E	9+94.00	0	690.87	690.91
F	10+04.00	0	690.87	690.91
G	10+14.00	0	690.87	690.89
Cl. Pier 2	10+26.00	0	690.85	690.85
H	10+36.00	0	690.84	690.85
I	10+46.00	0	690.82	690.84
J	10+56.00	0	690.79	690.81
Cl. E. Abut	10+66.00	0	690.76	690.76
Bk. Of E. Abut	10+67.25	0	690.76	690.76

BEAM 4

LOCATION	STATION	OFFSET		THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. Of W. Abut	9+32.75	2.75	Rt.	690.71	690.71
Cl. W. Abut	9+34.00	2.75	Rt.	690.72	690.72
A	9+44.00	2.75	Rt.	690.75	690.77
B	9+54.00	2.75	Rt.	690.77	690.80
C	9+64.00	2.75	Rt.	690.79	690.80
Cl. Pier 1	9+74.00	2.75	Rt.	690.81	690.81
D	9+84.00	2.75	Rt.	690.82	690.84
E	9+94.00	2.75	Rt.	690.83	690.86
F	10+04.00	2.75	Rt.	690.83	690.86
G	10+14.00	2.75	Rt.	690.82	690.84
Cl. Pier 2	10+26.00	2.75	Rt.	690.81	690.81
H	10+36.00	2.75	Rt.	690.79	690.80
I	10+46.00	2.75	Rt.	690.77	690.80
J	10+56.00	2.75	Rt.	690.75	690.77
Cl. E. Abut	10+66.00	2.75	Rt.	690.72	690.72
Bk. Of E. Abut	10+67.25	2.75	Rt.	690.71	690.71

BEAM 5

LOCATION	STATION	OFFSET		THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. Of W. Abut	9+32.75	8.25	Rt.	690.63	690.63
Cl. W. Abut	9+34.00	8.25	Rt.	690.63	690.63
A	9+44.00	8.25	Rt.	690.66	690.68
B	9+54.00	8.25	Rt.	690.69	690.71
C	9+64.00	8.25	Rt.	690.71	690.72
Cl. Pier 1	9+74.00	8.25	Rt.	690.72	690.72
D	9+84.00	8.25	Rt.	690.73	690.75
E	9+94.00	8.25	Rt.	690.74	690.78
F	10+04.00	8.25	Rt.	690.74	690.78
G	10+14.00	8.25	Rt.	690.74	690.76
Cl. Pier 2	10+26.00	8.25	Rt.	690.72	690.72
H	10+36.00	8.25	Rt.	690.71	690.72
I	10+46.00	8.25	Rt.	690.69	690.71
J	10+56.00	8.25	Rt.	690.66	690.68
Cl. E. Abut	10+66.00	8.25	Rt.	690.63	690.63
Bk. Of E. Abut	10+67.25	8.25	Rt.	690.63	690.63

BEAM 6

LOCATION	STATION	OFFSET		THEORETICAL GRADE ELEVATIONS	THEORETICAL GRADE ELEVATIONS ADJUSTED FOR DEAD LOAD DEFLECTION
Bk. Of W. Abut	9+32.75	13.75	Rt.	690.54	690.54
Cl. W. Abut	9+34.00	13.75	Rt.	690.55	690.55
A	9+44.00	13.75	Rt.	690.58	690.60
B	9+54.00	13.75	Rt.	690.60	690.62
C	9+64.00	13.75	Rt.	690.62	690.63
Cl. Pier 1	9+74.00	13.75	Rt.	690.64	690.64
D	9+84.00	13.75	Rt.	690.65	690.67
E	9+94.00	13.75	Rt.	690.65	690.69
F	10+04.00	13.75	Rt.	690.65	690.69
G	10+14.00	13.75	Rt.	690.65	690.67
Cl. Pier 2	10+26.00	13.75	Rt.	690.64	690.64
H	10+36.00	13.75	Rt.	690.62	690.63
I	10+46.00	13.75	Rt.	690.60	690.62
J	10+56.00	13.75	Rt.	690.58	690.60
Cl. E. Abut	10+66.00	13.75	Rt.	690.55	690.55
Bk. Of E. Abut	10+67.25	13.75	Rt.	690.54	690.54

TOP OF SLAB ELEVATIONS 2
SECTION: 10-00962-00-BR
CHAMPAIGN COUNTY
Q STATION 10+00