



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

July 25, 2022

SUBJECT: FAS 2735 (Renken Road)
Section 19-00077-03-RS
Madison County
Contract No. 97786
Item 043
August 5, 2022 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Fold Up Plan Sheet 3

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

COUNTY	TOTAL SHEETS	SHEET NO.
MADISON	15	3
CONTRACT NO. 97786		

INDEX OF SHEETS

1	COVER SHEET
2	LOCATION MAP
3	INDEX OF SHEETS, GENERAL NOTES, STANDARDS & COMMITMENTS
4	SUMMARY OF QUANTITIES
5 - 10	TYPICAL SECTIONS
11 - 12	SCHEDULE OF QUANTITIES
13 - 15	DETAILS

HIGHWAY STANDARDS

482001-02
701306-04
701311-03
701901-08
780001-05
781001-04

COMMITMENTS

1. NONE

GENERAL NOTES

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.39 OF THE STANDARD SPECIFICATIONS. THE J.U.L.I.E. NUMBER IS 1-800-892-0123.

UTILITY COMPANIES:

AMEREN ILLINOIS - 618-301-5327
SOUTHWESTERN ELECTRIC COOP - 800-637-8667
MARATHON - WOOD RIVER - 217-382-2234
FOSTERBURG WATER DISTRICT - 618-259-0935
CITY OF STAUNTON - 618-797-8366
MADISON TELEPHONE CO. - 618-635-5000

2. THE CONTRACTOR AND ENGINEER SHALL BE AWARE THAT A LIMITED SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING SHOWN IN THE PLANS WAS CREATED UTILIZING EXISTING PLANS AND FIELD MEASUREMENTS. THIS INFORMATION SHALL BE ASSUMED TO BE APPROXIMATE.

3. THE CONTRACTOR SHALL FERTILIZE, SEED AND MULCH ALL EARTH SURFACES DISTURBED OUTSIDE OF THE CONSTRUCTION LIMITS (EDGE OF PAVEMENT) DURING THE PROPOSED CONSTRUCTION. FERTILIZER, SEED AND MULCH SHALL BE APPLIED ACCORDING TO THE STANDARD SPECIFICATIONS, AS DIRECTED BY THE ENGINEER, AT THE CONTRACTOR'S EXPENSE AND NO ADDITIONAL COMPENSATION OR REMUNERATION WILL BE ALLOWED.

4. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

5. ANY REFERENCE WITHIN THESE PLANS TO A STANDARD SHALL BE INTERPRETED TO MEAN THE REVISION INDICATED BY THE SUB-NUMBER LISTED WITHIN OR THE COPY INCLUDED IN THIS PROPOSAL.

6. FACTORS USED FOR ESTIMATING PLAN QUANTITIES ARE AS FOLLOWS:

HMA MIXTURES	112 LBS/SQ YD/INCH
BITUMINOUS MATERIALS (TACK COAT)	0.05 LBS/SQ FT
AGGREGATE FOR SHOULDERS	2.05 TON/CY

7. PROPOSED PAVEMENT MARKING SHALL MATCH THE EXISTING OR AS DIRECTED BY THE ENGINEER.

8. THE EXISTING WATERPROOFING MEMBRANE SYSTEM, AS SHOWN ON THE TYPICAL SECTIONS, SHALL REMAIN IN PLACE. CARE SHALL BE TAKEN WHEN PERFORMING HOT-MIX ASPHALT SURFACE REMOVAL AS TO NOT DO ANY DAMAGE TO THE WATERPROOFING MEMBRANE SYSTEM.

HMA MIXTURE REQUIREMENTS

Location(s):	Renken Road - see Typical Sections	VFW Road Sta 485+90.68 LT	Renken Road - see Typical Sections
Mixture Use(s):	SURFACE	INCIDENTAL	SHOULDERS
PG:	PG 64-22	PG 64-22	PG 64-22
Design Air Voids:	4.0% @ Ndes=70	4.0% @ Ndes=70	4.0% @ Ndes=30
Mixture Composition:	IL- 9.5	IL- 9.5	IL- 9.5L
Friction Aggregate	MIXTURE "C"	MIXTURE "C"	-
Mixture Weight:	112 lb/sq yd/in	112 lb/sq yd/in	112 lb/sq yd/in
Quality Management Program:	QC/QA	QC/QA	QC/QA
Sublot Size:	N/A	N/A	N/A
Material Transfer Device (Required?)	No	No	No

Revised: 7/25/2022

INDEX/GENERAL NOTES/COMMITMENTS
FAS 2735
19-00077-03-RS
RENKEN ROAD OVERLAY