

02A

Letting August 5, 2022

Notice to Bidders, Specifications and Proposal



**Illinois Department
of Transportation**

Springfield, Illinois 62764

**Contract No. LW031
Lawrenceville-Vincennes International Airport
Lawrenceville, Illinois
Lawrence County
Illinois Project No. LWV-5003
SBG Project No. N/A**



NOTICE TO BIDDERS

1. **TIME AND PLACE OF OPENING BIDS.** Electronic bids are to be submitted to the electronic bidding system (iCX-Integrated Contractors Exchange). All bids must be submitted to the iCX system prior to 12:00 p.m. on August 5, 2022, at which time the bids will be publicly opened from the iCX SecureVault.

2. **DESCRIPTION OF WORK.** The proposed improvement is identified and advertised for bids in the Invitation for Bids as:

**Contract No. LW031
Lawrenceville-Vincennes International Airport
Lawrenceville, Illinois
Lawrence County
Illinois Project No. LWV-5003
SBG Project No. N/A**

Replace Omni-Directional Approach Lights (ODALs) on Runway 27

For engineering information, please contact Kevin N. Lightfoot, P.E. of Hanson Professional Services, Inc. at 217.747.9433.

3. **INSTRUCTIONS TO BIDDERS.**

(a) This Notice, the invitation for bids, proposal and letter of award shall, together with all other documents in accordance with Article 10-18 of the Illinois Standard Specifications for Construction of Airports (Adopted April 1, 2012), become part of the contract. Bidders are cautioned to read and examine carefully all documents, to make all required inspections, and to inquire or seek explanation of the same prior to submission of a bid.

(b) State law, and, if the work is to be paid wholly or in part with Federal-aid funds, Federal law requires the bidder to make various certifications as a part of the proposal and contract. By execution and submission of the proposal, the bidder makes the certification contained therein. A false or fraudulent certification shall, in addition to all other remedies provided by law, be a breach of contract and may result in termination of the contract.

4. **AWARD CRITERIA AND REJECTION OF BIDS.** This contract will be awarded within 90 calendar days to the lowest responsive and responsible bidder considering conformity with the terms and conditions established by the Department in the rules, Invitation for Bids and contract documents. The issuance of plans and proposal forms for bidding based upon a prequalification rating shall not be the sole determinant of responsibility. The Department reserves the right to determine responsibility at the time of award, to reject any or all proposals, to readvertise the proposed improvement, and to waive technicalities.

5. **PRE-BID CONFERENCE.** N/A

6. **DISADVANTAGED BUSINESS POLICY.** The DBE goal for this contract is 0.0%.

7. **SPECIFICATIONS AND DRAWINGS.** The work shall be done in accordance with the Illinois Standard Specifications for Construction of Airports (Adopted April 1, 2012), the Special Provisions dated June 10, 2022, and the Construction Plans dated June 10, 2022 as approved by the Illinois Department of Transportation, Division of Aeronautics.

- 8. BIDDING REQUIREMENTS AND BASIS OF AWARD.** When alternates are included in the proposal, the following shall apply:
- a. Additive Alternates
 - (1) Bidders must submit a bid for the Base Bid and for all Additive Alternates.
 - (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lowest aggregate amount of (i) the Base Bid plus (ii) any Additive Alternate(s) which the Department elects to award.

The Department may elect not to award any Additive Alternates. In that case, award will be to the lowest responsible qualified bidder of the Base Bid.
 - b. Optional Alternates
 - (1) Bidders must submit a bid for the Base Bid and for either Alternate A or Alternate B or for both Alternate A and Alternate B.
 - (2) Award of this contract will be made to the lowest responsible qualified bidder computed as follows:

The lower of the aggregate of either (i) the Base Bid plus Alternate A or (ii) the Base Bid plus Alternate B.
- 9. CONTRACT TIME.** The Contractor shall complete all work within the specified contract time. Any calendar day extension beyond the specified contract time must be fully justified, requested by the Contractor in writing, and approved by the Engineer, or be subject to liquidated damages.
- The contract time for this contract is 30 calendar days.
- 10. INDEPENDENT WEIGHT CHECKS.** The Department reserves the right to conduct random unannounced independent weight checks on any delivery for bituminous, aggregate or other pay item for which the method of measurement for payment is based on weight. The weight checks will be accomplished by selecting, at random, a loaded truck and obtaining a loaded and empty weight on an independent scale. In addition, the department may perform random weight checks by obtaining loaded and empty truck weights on portable scales operated by department personnel.
- 11. MATERIAL COST ADJUSTMENTS.** The Illinois Department of Transportation, Division of Aeronautics does not offer any material cost adjustment provisions.
- 12. GOOD FAITH COMPLIANCE.** The Illinois Department of Transportation has made a good faith effort to include all statements, requirements, and other language required by federal and state law and by various offices within federal and state governments whether that language is required by law or not. If anything of this nature has been left out or if additional language etc. is later required, the bidder/contractor shall cooperate fully with the Department to modify the contract or bid documents to correct the deficiency. If the change results in increased operational costs, the Department shall reimburse the contractor for such costs as it may find to be reasonable.

By Order of the
Illinois Department of Transportation

Omer Osman,
Secretary

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
EEO

Effective: July 21, 1978
Revised: November 18, 1980

The requirements of the following provisions written for federally-assisted construction contracts, including all goals and timetables and affirmative action steps, shall also apply to all State-funded construction contracts awarded by the Illinois Department of Transportation.

Notice of Requirement for Affirmative Action to Ensure
Equal Employment Opportunity (Executive Order 11246)

1. The offeror's or bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.
2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate workforce in each trade on all construction work in the covered area, are as follows:

APPENDIX A

The following goal for female utilization in each construction craft and trade shall apply to all Contractors holding Federal and federally assisted construction contracts and subcontracts in excess of \$10,000. The goal is applicable to the Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a federal, federally assisted or nonfederally related construction contract or subcontract.

Area Covered (Statewide)

Goals for Women apply nationwide.

GOAL	Goal (percent)
Female Utilization	6.9

APPENDIX B

Until further notice, the following goals for minority utilization in each construction craft and trade shall apply to all Contractors holding federal and federally-assisted construction contracts and subcontracts in excess of \$10,000 to be performed in the respective geographical areas. The goals are applicable to the Contractor's total on-site construction workforce, regardless of whether or not part of that workforce is performing work on a federal, federally-assisted or nonfederally related construction contract or subcontract.

	<u>Economic Area</u>	Goal (percent)
056	Paducah, KY: Non-SMSA Counties - IL - Hardin, Massac, Pope KY - Ballard, Caldwell, Calloway, Carlisle, Crittenden, Fulton, Graves, Hickman, Livingston, Lyon, McCracken, Marshall	5.2
080	Evansville, IN: Non-SMSA Counties - IL - Edwards, Gallatin, Hamilton, Lawrence, Saline, Wabash, White IN - Dubois, Knox, Perry, Pike, Spencer KY - Hancock, Hopkins, McLean, Mublenberg, Ohio, Union, Webster	3.5
081	Terre Haute, IN: Non-SMSA Counties - IL - Clark, Crawford IN - Parke	2.5

083	Chicago, IL: SMSA Counties: 1600 Chicago, IL -	19.6
	IL - Cook, DuPage, Kane, Lake, McHenry, Will 3740 Kankakee, IL -	9.1
	IL - Kankakee Non-SMSA Counties	18.4
	IL - Bureau, DeKalb, Grundy, Iroquois, Kendall, LaSalle, Livingston, Putnam	
	IN - Jasper, Laporte, Newton, Pulaski, Starke	
084	Champaign - Urbana, IL: SMSA Counties: 1400 Champaign - Urbana - Rantoul, IL -	7.8
	IL - Champaign Non-SMSA Counties -	4.8
	IL - Coles, Cumberland, Douglas, Edgar, Ford, Piatt, Vermilion	
085	Springfield - Decatur, IL: SMSA Counties: 2040 Decatur, IL -	7.6
	IL - Macon 7880 Springfield, IL -	4.5
	IL - Menard, Sangamon Non-SMSA Counties	4.0
	IL - Cass, Christian, Dewitt, Logan, Morgan, Moultrie, Scott, Shelby	
086	Quincy, IL: Non-SMSA Counties	3.1
	IL - Adams, Brown, Pike	
	MO - Lewis, Marion, Pike, Ralls	
087	Peoria, IL: SMSA Counties: 1040 Bloomington - Normal, IL -	2.5
	IL - McLean 6120 Peoria, IL -	4.4
	IL - Peoria, Tazewell, Woodford Non-SMSA Counties -	3.3
	IL - Fulton, Knox, McDonough, Marshall, Mason, Schuyler, Stark, Warren	
088	Rockford, IL: SMSA Counties: 6880 Rockford, IL -	6.3
	IL - Boone, Winnebago Non-SMSA Counties -	4.6
	IL - Lee, Ogle, Stephenson	
098	Dubuque, IA: Non-SMSA Counties -	0.5
	IL - JoDaviess	
	IA - Atlamakee, Clayton, Delaware, Jackson, Winnesheik	
	WI - Crawford, Grant, Lafayette	
099	Davenport, Rock Island, Moline, IA - IL: SMSA Counties: 1960 Davenport, Rock Island, Moline, IA - IL -	4.6
	IL - Henry, Rock Island IA - Scott Non-SMSA Counties -	3.4
	IL - Carroll, Hancock, Henderson, Mercer, Whiteside IA - Clinton, DesMoines, Henry, Lee, Louisa, Muscatine MO - Clark	

107	St. Louis, MO: SMSA Counties: 7040 St. Louis, MO - IL -	14.7
	IL - Clinton, Madison, Monroe, St. Clair MO - Franklin, Jefferson, St. Charles, St. Louis, St. Louis City	
	Non-SMSA Counties -	11.4
	IL - Alexander, Bond, Calhoun, Clay, Effingham, Fayette, Franklin, Greene, Jackson, Jasper, Jefferson, Jersey, Johnson, Macoupin, Marion, Montgomery, Perry, Pulaski, Randolph, Richland, Union, Washington, Wayne, Williamson	
	MO - Bollinger, Butler, Cape Girardeau, Carter, Crawford, Dent, Gasconade, Iron, Lincoln, Madison, Maries, Mississippi, Montgomery, Perry, Phelps, Reynolds, Ripley, St. Francois, St. Genevieve, Scott, Stoddard, Warren, Washington, Wayne	

These goals are applicable to all the Contractor's construction work (whether or not it is federal or federally assisted) performed in the covered area. If the Contractor performs construction work in a geographical area located outside of the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the Contractor also is subject to the goals for both its federally involved and nonfederally involved construction.

The Contractor's compliance with Executive Order 11246 and the regulations in 41 CFR Part 60-4 shall be based on its implementation of the Equal Opportunity Clause, specific affirmative action obligations required by the provisions and specifications set forth in its federally assisted contracts, and its efforts to meet the goals established for the geographical area where the contract resulting from this solicitation is to be performed. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order 11246 and the regulations in 41 CFR Part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The Illinois Department of Transportation will provide written notification to the Director of the Office of Federal Contract Compliance Programs within ten working days of award of any construction contract and/or subcontract in excess of \$10,000 at any tier for construction work under the contract resulting from this solicitation. This notification will list the name, address and telephone number of the subcontractor; employer identification number; estimated dollar amount of the subcontract; estimated starting and completion dates of the subcontract; and the geographical area in which the contract is to be performed.
4. As used in this Notice, and in the contract resulting from this solicitation, the "covered area" is the entire State of Illinois for the goal set forth in APPENDIX A and the county or counties in which the work is located for the goals set forth in APPENDIX B.

STANDARD FEDERAL EQUAL EMPLOYMENT
OPPORTUNITY CONSTRUCTION CONTRACT
SPECIFICATIONS (EXECUTIVE ORDER 11246)

1. As used in these specifications:
 - (a) "Covered area" means the geographical area described in the solicitation from which this contract resulted;
 - (b) "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority;
 - (c) "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941;
 - (d) "Minority" includes:
 - (i) Black (all persons having origins in any of the Black African racial groups not of Hispanic origin);
 - (ii) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American or other Spanish Culture or origin, regardless of race);
 - (iii) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
 - (iv) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation or community identification).
2. Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000. the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the solicitations from which this contract resulted.
3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.

4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. Covered Construction Contractors performing construction work in geographical areas where they do not have a Federal or federally assisted construction contract shall apply the minority and female goals established for the geographical area where the work is being performed. Goals are published periodically in the Federal Register in notice form, and such notices may be obtained from any Office of Federal Contract Compliance Programs office or from Federal procurement contracting officers. The Contractor is expected to make substantially uniform progress toward its goals in each craft during the period specified.
5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
6. In order for the nonworking training hours of apprentices and trainees to be counted in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor.
7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
 - (a) Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all foremen, superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working as such sites or in such facilities.
 - (b) Establish and maintain a current list of minority and female recruitment sources, provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its unions have employment opportunities available, and maintain a record of the organizations' responses.
 - (c) Maintain a current file of the names, addresses and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each such individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union or, if referred, not employed by the Contractor, this shall be documented in the file with the reason therefor, along with whatever additional actions the Contractors may have taken.
 - (d) Provide immediate written notification to the Director when the union or unions with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority person or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
 - (e) Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to the sources compiled under 7b above.
 - (f) Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreements; by publicizing it in the company newspaper, annual report, etc.; by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
 - (g) Review, at least annually, the company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination or other employment decisions including specific review of these items with onsite supervisory personnel such as Superintendents, General Foreman, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
 - (h) Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing the Contractor's EEO policy with other Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
 - (i) Direct its recruitment efforts, both oral and written, to minority, female and community organizations, to schools with minority and female students and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
 - (j) Encourage present minority and female employees to recruit other minority persons and women and, where reasonable, provide after school, summer and vacation employment to minority and female youth both on the site and in other areas of a Contractor's workforce.
 - (k) Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.

- (l) Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these employees to seek or to prepare for, through appropriate training, etc., such opportunities.
 - (m) Ensure that seniority practices, job classifications, work assignments and other personnel practices, do not have a discriminatory effect by continually monitoring all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
 - (n) Ensure that all facilities and company activities are nonsegregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
 - (o) Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction Contractors and suppliers, including circulation of solicitations to minority and female Contractor associations and other business associations.
 - (p) Conduct a review, at least annually, of all supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligations.
8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through p). The efforts of a Contractor association, joint Contractor-union, Contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through p of these Specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female workforce participation makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.
 9. A single goal for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minority groups, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specified minority group of women is underutilized).
 10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.
 11. The Contractor shall not enter into any Subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
 12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termination and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.
 13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
 14. The Contractor shall designate a responsible official to monitor all employment related activity to ensure that the company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form; however, to the degree that existing records satisfy his requirement, Contractors shall not be required to maintain separate records.
 15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon the application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
SPECIFIC EQUAL EMPLOYMENT OPPORTUNITY RESPONSIBILITIES
NONFEDERAL-AID CONTRACTS

Effective: March 20, 1969
Revised: January 1, 1994

1. General

- a. The requirements set forth herein shall constitute the specific affirmative action requirements under this contract and supplement the non-discrimination requirements contained elsewhere in this proposal.
- b. The Contractor shall work with the Illinois Department of Transportation (IDOT) in carrying out Equal Employment Opportunity (EEO) obligations and in reviews of activities under the contract.
- c. The Contractor, and all subcontractors holding subcontracts (not including material suppliers) of \$10,000 or more, shall comply with the following minimum specific requirement activities of EEO. The Contractor shall include these requirements in every subcontract of \$10,000 or more with such modification of language as is necessary to make them binding on the subcontractor.

2. Equal Employment Opportunity Policy

The Contractor shall accept as operating policy the following statement which is designed to further the provision of EEO to all persons, and to promote the full realization of equal employment opportunity through a positive continuing program: "It is the policy of this Company to ensure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age, or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

3. Equal Employment Opportunity Officer

The Contractor shall designate and make known to IDOT contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active Contractor program of EEO and who must be assigned adequate authority and responsibility to do so.

4. Dissemination of Policy

- a. All members of the Contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the Contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:
 - (1) Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the Contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.
 - (2) All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the Contractor's EEO obligations within thirty days following their reporting for duty with the Contractor.
 - (3) All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the Contractor's procedures for locating and hiring minority and female employees.
- b. In order to make the Contractor's EEO policy known to all employees, prospective employees, and potential sources of employees, i.e., schools, employment agencies, labor unions (where appropriate), college placement officers, etc., the Contractor shall take the following actions:
 - (1) Notices and posters setting forth the Contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.
 - (2) The Contractor's EEO policy and the procedures to implement such policy shall be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

5. Recruitment

- a. When advertising for employees, the Contractor shall include in all advertisements for employees the notation: "An Equal Opportunity Employer". All such advertisements shall be published in newspapers, or other publications, having a large circulation among minority groups in the area from which the project work force would normally be derived.
- b. The Contractor shall, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minority and female applicants, including, but not limited to, State employment

agencies, schools, colleges and minority and female organizations. To meet this requirement, the Contractor shall, identify sources of potential minority and female employees, and establish with such identified sources procedures whereby minority and female applicants may be referred to the Contractor for employment consideration. In the event the Contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, he/she is expected to observe the provisions of that agreement to the extent that the system permits the Contractor's compliance with EEO contract provisions.

- c. The Contractor shall encourage present employees to refer minority and female applicants for employment by posting appropriate notices or bulletins in areas accessible to all such employees. In addition, information and procedures with regard to referring minority and female applicants shall be discussed with employees.

6. Personnel Actions

Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, will be taken without regard to race, color, religion, sex, national origin, age, or disability. The following procedures shall be followed:

- a. The Contractor shall conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.
- b. The Contractor shall periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.
- c. The Contractor shall periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the Contractor shall promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.
- d. The Contractor shall promptly investigate all complaints of alleged discrimination made to the Contractor in connection with the obligations under this contract, shall attempt to resolve such complaints, and shall take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the Contractor shall inform every complainant of all of the avenues of appeal.

7. Training and Promotion

- a. The Contractor shall assist in locating, qualifying and increasing the skills of minority and female employees and applicants for employment.
- b. Consistent with the Contractor's work force requirements and as permissible under Federal and State regulations, the Contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance.
- c. The Contractor shall advise employees and applicants for employment of available training programs and entrance requirements for each.
- d. The Contractor shall periodically review the training and promotion potential of minority and female employees and shall encourage eligible employees to apply for such training and promotion.

8. Unions

If the Contractor relies in whole or in part upon unions as a source of employees, the Contractor shall use his/her best efforts to obtain the cooperation of such unions to increase opportunities for minorities and females within the unions, and to effect referrals by such unions of minority and female employees. Actions by the Contractor, either directly or through a Contractor's association acting as agent, shall include the procedures set forth below:

- a. The Contractor shall use best efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minority and female employees for membership in the unions and increasing the skills of minority and female employees so that they may qualify for higher paying employment.
- b. The Contractor shall use best efforts to incorporate an EEO clause into each union agreement to the end that such union shall be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age, or disability.
- c. The Contractor is to obtain information as to the referral practices and policies of the labor union, except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the Contractor, the Contractor shall so certify to IDOT and shall set forth what efforts have been made to obtain such information.
- d. In the event the union is unable to provide the Contractor with a reasonable flow of minority and female referrals within the time limit set forth in the collective bargaining agreement, the Contractor shall, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age, or disability; making full efforts to obtain qualified and/or qualifiable minorities and females. (The U.S. Department of Labor has held that it shall be no excuse that the union with which the Contractor has a collective bargaining agreement providing for exclusive referral failed to refer minorities or female employees). In the event the union referral practice prevents the Contractor from meeting the obligations pursuant to these Special Provisions, such Contractor shall immediately notify IDOT.

9. Selection of Subcontractors, Procurement of Materials, and Leasing of Equipment

The Contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age, or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment.

- a. The Contractor shall notify all potential subcontractors and suppliers of his/her EEO obligations under this contract.
- b. Disadvantaged business enterprises (DBE), as defined in 49 CFR Part 23, shall have equal opportunity to compete for and perform subcontracts which the Contractor enters into pursuant to this contract. The Contractor shall use best efforts to solicit bids from and to utilize DBE subcontractors or subcontractors with meaningful minority and female representation among their employees. Contractors shall obtain lists of DBE construction firms from IDOT personnel.
- c. The Contractor shall use his/her best efforts to ensure subcontractor compliance with their EEO obligations.

10. Records and Reports

The Contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following completion of the contract work and shall be available at reasonable times and places for inspection by authorized representatives of IDOT.

- a. The records kept by the Contractor shall document the following:
 - (1) the number of minorities, non-minorities and females employed in each work classification on the project;
 - (2) the progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and females;
 - (3) the progress and efforts being made in locating, hiring, training, qualifying, and upgrading minority and female employees; and
 - (4) the progress and efforts being made in securing the services of DBE subcontractors, or subcontractors with meaningful minority and female representation among their employees.
- b. The Contractor shall submit to IDOT a monthly report every month for the duration of the project, indicating the number of minority, non-minority and female employees currently engaged in each work classification required by contract work and the number of hours worked. This information is to be reported on Form SBE-956. If on-the-job training is being required by special provision, the Contractor will be required to collect and report training data.

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
REQUIRED PROVISIONS – STATE CONTRACTS

Effective: April 1 1965
Revised: January 1, 2017

I. SELECTION OF LABOR

The Contractor shall comply with all Illinois statutes pertaining to the selection of labor.

EMPLOYMENT OF ILLINOIS WORKERS DURING PERIODS OF
EXCESSIVE UNEMPLOYMENT

Whenever there is a period of excessive unemployment in Illinois, which is defined herein as any month immediately following two consecutive calendar months during which the level of unemployment in the State of Illinois has exceeded five percent as measured by the United States Bureau of Labor Statistics in its monthly publication of employment and unemployment figures, the Contractor shall employ at least 90 percent Illinois laborers. "Illinois laborer" means any person who has resided in Illinois for at least 30 days and intends to become or remain an Illinois resident.

Other laborers may be used when Illinois laborers as defined herein are not available, or are incapable of performing the particular type of work involved, if so certified by the Contractor and approved by the Engineer. The Contractor may place no more than three of his/her regularly employed non-resident executive and technical experts, who do not qualify as Illinois laborers, to do work encompassed by this Contract during period of excessive unemployment.

This provision applies to all labor, whether skilled, semi-skilled, or unskilled, whether manual or non-manual.

II. EQUAL EMPLOYMENT OPPORTUNITY

In the event of the Contractor's noncompliance with the provisions of this Equal Employment Opportunity Clause, the Illinois Human Rights Act or the Illinois Department of Human Rights Rules and Regulations, the Contractor may be declared ineligible for future contracts or subcontracts with the State of Illinois or any of its political sub-divisions or municipal corporations, and the contract may be cancelled or voided in whole or in part, and such other sanctions or penalties may be imposed or remedies invoked as provided by statute or regulation.

During the performance of this Contract, the Contractor agrees as follows:

1. That it will not discriminate against any employee or applicant for employment because of race, color, religion, sex, sexual orientation, marital status, order of protection status, national origin or ancestry, citizenship status, age, physical or mental disability unrelated to ability, military status, or an unfavorable discharge from military service; and further that it will examine all job classifications to determine if minority persons or women are underutilized and will take appropriate affirmative action to rectify any such underutilization.
2. That, if it hires additional employees in order to perform this contract or any portion hereof, it will determine the availability (in accordance with the Illinois Department of Human Rights Rules and Regulations) of minorities and women in the area(s) from which it may reasonably recruit and it will hire for each job classification for which employees are hired in such a way that minorities and women are not underutilized.
3. That, in all solicitations or advertisements for employees placed by it or on its behalf, it will state that all applicants will be afforded equal opportunity without discrimination because of race, color, religion, sex, sexual orientation, marital status, order of protection status, national origin or ancestry, citizenship status, age, physical or mental disability unrelated to ability, military status, or an unfavorable discharge from military service.
4. That it will send to each labor organization or representative of workers with which it has or is bound by a collective bargaining or other agreement or understanding, a notice advising such labor organization or representative of the Contractor's obligations under the Illinois Human Rights Act and the Illinois Department of Human Rights Rules and Regulations. If any labor organization or representative fails or refuses to cooperate with the Contractor in its efforts to comply with such Act and Rules and Regulations, the Contractor will promptly so notify the Illinois Department of Human Rights and IDOT and will recruit employees from other sources when necessary to fulfill its obligations thereunder.
5. That it will submit reports as required by the Illinois Department of Human Rights Rules and Regulations, furnish all relevant information as may from time to time be requested by the Illinois Department of Human Rights or IDOT, and in all respects comply with the Illinois Human Rights Act and the Illinois Department of Human Rights Rules and Regulations.
6. That it will permit access to all relevant books, records, accounts and work sites by personnel of IDOT and the Illinois Department of Human Rights for purposes of investigation to ascertain compliance with the Illinois Human Rights Act and the Illinois Department of Human Rights Rules and Regulations.
7. That it will include verbatim or by reference the provisions of this clause in every subcontract it awards under which any portion of the contract obligations are undertaken or assumed, so that the provisions will be binding upon the subcontractor. In the same manner as with other provisions of this contract, the Contractor will be liable for compliance with applicable provisions of this clause by subcontractors; and further it will promptly notify IDOT and the Illinois Department of Human Rights in the event any subcontractor fails or refuses to comply with these provisions. In addition, the Contractor will not utilize any subcontractor declared by the Illinois Human Rights Commission to be ineligible for contracts or subcontracts with the State of Illinois or any of its political subdivisions or municipal corporations.

III. SUBLETTING OR ASSIGNING THE CONTRACT

1. The Contractor shall perform with his/her own organization contract work amounting to not less than 51 percent of the original total contract price, except that any items designated by the State as "Specialty Items" may be performed by subcontract and the amount of any such "Specialty Items" so performed may be deducted from the original total contract price before computing the amount of work required to be performed by the Contractor with his/her own organization.
 - a. "His/her own organization" shall be construed to include only worker employed and paid directly by the Contractor and equipment owned or rented by him/her, with or without operators.
 - b. "Specialty Items" shall be construed to be limited to work that requires specialized knowledge, craftsmanship or equipment not ordinarily available in contracting organizations qualified to bid on the contract as a whole and in general are to be limited to minor components of the overall contract.
2. In addition to the 51 percent requirement set forth in paragraph 1 above, the Contractor shall furnish (a) a competent superintendent or foreman who is employed by him/her, who has full authority to direct performance of the work in accordance with the contract requirements, and who is in charge of all construction operations (regardless of who performs the work), and (b) such other of his/her own organizational capability and responsibility (supervision, management, and engineering services) as the State highway department contracting officer determines is necessary to assure the performance of the contract.
3. The Contractor shall not sublet, sell, transfer, assign or otherwise dispose of the contract or contracts or any portion thereof, or of his/her right, title or interest therein, without written consent of the Engineer. In case such consent is given, the Contractor will be permitted to sublet a portion thereof, but shall perform with the Contractor's own organization, work amounting to not less than 51 percent of the total contract cost, except that any items designated in the contract as "specialty items" may be performed by subcontract and the cost of any such specialty items so performed by subcontract may be deducted from the total cost before computing the amount of work required to be performed by the Contractor with his/her own organization. Materials purchased or produced by the Contractor must be incorporated into the project by the Contractor's own organization if their cost is to be applied to the 50 percent requirement.

No subcontracts, or transfer of contract, shall in any case release the Contractor of his/her liability under the contract and bonds. All transactions of the Engineer shall be with the Contractor. The Contractor shall have representative on the job at all times when either contract or subcontract work is being performed.

All requests to subcontract shall contain a certification that the subcontract agreement exists in writing and physically contains the required Federal and State Equal Employment Opportunity provisions and Labor compliance provisions, including the contract minimum wage requirements. The Contractor shall permit Department or Federal representatives to examine the subcontract agreements upon notice.

4. Any items that have been selected as "Specialty Items" for the contract are listed as such in the Special Provisions, bid schedule, or elsewhere in the contract documents.
5. No portion of the contract shall be sublet, assigned or otherwise disposed of, except with the written consent of the State highway department contracting officer, or his/her authorized representative, and such consent when given shall not be construed to relieve the Contractor of any responsibility for the fulfillment of the contract. Request for permission to sublet, assign or otherwise dispose of any portion of the contract shall be in writing and accompanied by (a) a showing that the organization which will perform the work is particularly experienced and equipped for such work, and (b) an assurance by the Contractor that the labor standards provisions set forth in this contract shall apply to labor performed on all work encompassed by the request.

IV. COMPLIANCE WITH THE PREVAILING WAGE ACT

1. **Prevailing Wages.** All wages paid by the Contractor and each subcontractor shall be in compliance with The Prevailing Wage Act (820 ILCS 130), as amended, except where a prevailing wage violates a federal law, order, or ruling, the rate conforming to the federal law, order, or ruling shall govern. The Contractor shall be responsible to notify each subcontractor of the wage rates set forth in this contract and any revisions thereto. If the Department of Labor revises the wage rates, the Contractor will not be allowed additional compensation on account of said revisions. Current wage rate information shall be obtained by visiting the Department of Labor website at <http://www.illinois.gov/idol/Pages/default.aspx>. It is the responsibility of the Contractor to review the rates applicable to the work of this contract at regular intervals in order to insure the timely payment of current rates. Provision of this information to the Contractor by means of the Department of Labor website satisfies the notification of revisions by the Department to the Contractor pursuant to the Act, and the Contractor agrees that no additional notice is required.
2. **Payroll Records.** The Contractor and each subcontractor shall make and keep, for a period of three years from the later of the date of final payment under the contract or completion of the contract, records of the wages paid to his/her workers. The payroll records shall include each worker's name, address, telephone number, social security number, classification, rate of pay, number of hours worked each day, starting and ending times of work each day, total hours worked each week, itemized deductions made, and actual wages paid. Upon seven business days' notice, these records shall be available at a location within the State, during reasonable hours, for inspection by the Department or the Department of Labor; and Federal, State, or local law enforcement agencies and prosecutors.
3. **Submission of Payroll Records.** The Contractor and each subcontractor shall submit payroll records to the Engineer each week from the start to the completion of their respective work, except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall include an identification number for each employee (e.g., the last four digits of the employee's social security number). In addition, starting and ending times of work each day may be omitted from the payroll records submitted to the Engineer. The submittals shall be on the Department's form SBE 48, or an approved facsimile. When there has been no activity during a work week, a payroll record shall still be submitted with the appropriate box ("No Work", "Suspended", or "Complete") checked on the form.

Each submittal shall be accompanied by a statement signed by the Contractor or subcontractor, or an officer, employee, or officer thereof, which avers that: (i) he or she has examined the records and such records are true and accurate; (ii) the hourly rate paid to each worker is not less than the general prevailing rate of hourly wages required by the Act; and (iii) the Contractor or subcontractor is aware that filing a payroll record that he/she knows to be false is a Class A misdemeanor.

4. Employee Interviews. The Contractor and each subcontractor shall permit his/her employees to be interviewed on the job, during working hours, by compliance investigators of the Department or the Department of Labor.

V. NONSEGREGATED FACILITIES

(Applicable to State Financed Construction Contracts and related subcontracts exceeding \$10,000 which are not exempt from the Equal Opportunity clause).

By submission of this bid, the execution of this contract or subcontract, or the consummation of this material supply agreement, as appropriate, the bidder, construction Contractor, subcontractor, or material supplier, as appropriate, certifies that (s)he does not maintain or provide for his/her employees any segregated facilities at any of his/her establishments, and that (s)he does not permit his/her employees to perform their services at any location, under his/her control, where segregated facilities are maintained. (S)He certifies further that (s)he will not maintain or provide for his/her employees any segregated facilities at any of his/her establishments, and that (s)he will not permit his/her employees to perform their services at any location, under his/her control, where segregated facilities are maintained. (S)He agrees that a breach of this certification is a violation of the Equal Opportunity clause in this contract. As used in this certification, the term "segregated facilities" means any waiting rooms, work areas, restrooms and washrooms, restaurants and other eating areas, time clocks, locker rooms and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing facilities provided for employees which are segregated by explicit directive or are in fact segregated on the basis of race, creed, color, or national origin, because of habit, local custom, or otherwise. (S)He agrees that (except where he/she has obtained identical certifications from proposed subcontractors and material suppliers for specific time periods), he/she will obtain identical certifications from proposed subcontractors or material suppliers prior to the award of subcontracts or the consummation of material supply agreements, exceeding \$10,000 which are not exempt from the provisions of the Equal Opportunity clause, and that (s)he will retain such certifications in his/her files.

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
SECTION 80 PROSECUTION AND PROGRESS

This Special Provision amends the provisions of the Standard Specifications for Construction of Airports, adopted April 1, 2012 and shall be construed to be a part thereof, superseding any conflicting provisions thereof applicable to the work under the contract.

80-09 FAILURE TO COMPLETE ON TIME.

DELETE: "See contract documents for current schedule of deductions."

ADD:

Schedule of Deductions for Each Day of Overrun in Contract Time			
Original Contract Amount		Daily Charges	
From More Than	To and Including	Calendar Day	Work Day
\$ 0	\$ 100,000	\$ 475	\$ 675
100,000	500,000	750	1,050
500,000	1,000,000	1,025	1,425
1,000,000	3,000,000	1,275	1,725
3,000,000	6,000,000	1,425	2,000
6,000,000	12,000,000	2,300	3,450
12,000,000	And over	6,775	9,525

State of Illinois
Department of Transportation

SPECIAL PROVISION
FOR
SECTION 90 MEASUREMENT AND PAYMENT

This Special Provision amends the provisions of the Standard Specifications for Construction of Airports, adopted April 1, 2012 and shall be construed to be a part thereof, superseding any conflicting provisions thereof applicable to the work under the contract.

90-07 PARTIAL PAYMENTS.

DELETE: The entire section.

ADD: Partial payments will be made to the Contractor at least once each month as the work progresses. The payments will be based upon estimates, prepared by the Resident Engineer, of the value of the work performed and materials complete and in place in accordance with the contract, plans, and specifications. Such partial payments may also include the delivered actual cost of those materials stockpiled and stored in accordance with the Section 90-08 PAYMENT FOR MATERIALS ON HAND. From the amount of partial payment so determined on Federal-Aid projects, there shall be deducted an amount up to ten percent of the cost of the completed work which shall be retained until all conditions necessary for financial closeout of the project are satisfied. The amount of the estimate approved as due for payment will be vouchered by the Department and presented to the State Comptroller for payment. No amount less than \$1,000.00 will be approved for payment other than the final payment. A final voucher for under \$5.00 shall not be paid except through electronic funds transfer. (15 ILCS 405/9(b-1))

It is understood and agreed that the Contractor shall not be entitled to demand or receive partial payment based on quantities of work in excess of those provided in the proposal or covered by approved change orders, except when such excess quantities have been determined by the Engineer to be a part of the final quantity for the item of work in question.

No partial payment shall bind the Department to the acceptance of any materials or work in place as to quality or quantity. All partial payments are subject to correction at the time of final payment as provided in Section 90-09 ACCEPTANCE AND FINAL PAYMENT.

Progress payments may be reduced by liens filed pursuant to Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c).

If a Contractor or subcontractor has defaulted on a loan issued under the Department's Disadvantaged Business Revolving Loan Program (20 ILCS 2705/2705-610) progress payments may be reduced pursuant to the terms of that loan agreement. In such cases, the amount of the estimate related to the work performed by the Contractor or subcontractor, in default of the loan agreement, will be offset, in whole or in part, and vouchered by the Department to the Working Capital Revolving Fund or designated escrow account. Payment for the work shall be considered as issued and received by the Contractor or subcontractor on the date of the offset voucher. Further, the amount of the offset voucher shall be a credit against the Department's obligation to pay the Contractor, the Contractor's obligation to pay the subcontractor, and the Contractor's or subcontractor's total loan indebtedness to the Department. The offset shall continue until such time as the entire loan indebtedness is satisfied. The Department will notify the Contractor and Fund Control Agent in a timely manner of such offset. The Contractor or subcontractor shall not be entitled to additional payment in consideration of the offset.

In accordance with 49 USC § 47111, the Department will not make payments totaling more than 90 percent of the contract until all conditions necessary for financial closeout of the project are satisfied.

The failure to perform any requirement, obligation, or term of the contract by the Contractor shall be reason for withholding any progress payments until the Department determines that compliance has been achieved.

90-10 TRUST AGREEMENT OPTION.

DELETE: The entire section.

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Construction of Airports," adopted April 1, 2012, and the Special Provisions included herein which apply to and govern the airport improvement of: Replace Omni-Directional Approach Lights (ODALs) on Runway 27 at Lawrenceville-Vincennes International, Contract LW031, and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

SPECIAL PROVISION FOR COMPLETION TIME VIA CALENDAR DAYS

It being understood and agreed that the completion within the time limit is an essential part of the contract, the bidder agrees to complete the work within **30 calendar days**, unless additional time is granted by the Engineer in accordance with the provisions of the specifications. In case of failure to complete the work on or before the time named herein, or within such extra time as may have been allowed by extensions, the bidder agrees that the Department of Transportation shall withhold from such sum as may be due him/her under the terms of this contract, the costs, as set forth in Section 80-09 Failure to Complete on Time of the Standard Specifications, which costs shall be considered and treated not as a penalty but as damages due to the State from the bidder by reason of the failure of the bidder to complete the work within the time specified in the contract.

CONSTRUCTION AIR QUALITY – DIESEL VEHICLE EMISSIONS CONTROL (BDE)

Effective: April 1, 2009

Revised: January 2, 2012

Diesel Vehicle Emissions Control. The reduction of construction air emissions shall be accomplished by using cleaner burning diesel fuel. The term "equipment" refers to any and all diesel fuel powered devices rated at 50 hp and above, to be used on the project site in excess of seven calendar days over the course of the construction period on the project site (including any "rental" equipment).

All equipment on the jobsite, with engine ratings of 50 hp and above, shall be required to: use Ultra Low Sulfur Diesel fuel (ULSD) exclusively (15 ppm sulfur content or less).

Diesel powered equipment in non-compliance will not be allowed to be used on the project site, and is also subject to a notice of non-compliance as outlined below.

The Contractor shall certify that only ULSD will be used in all jobsite equipment. The certification shall be presented to the Department prior to the commencement of the work.

If any diesel powered equipment is found to be in non-compliance with any portion of this specification, the Engineer will issue the Contractor a notice of non-compliance and identify an appropriate period of time, as outlined below under environmental deficiency deduction, in which to bring the equipment into compliance or remove it from the project site.

Any costs associated with bringing any diesel powered equipment into compliance with these diesel vehicle emissions controls shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed. The Contractor's compliance with this notice and any associated regulations shall also not be grounds for a claim.

Environmental Deficiency Deduction. When the Engineer is notified, or determines that an environmental control deficiency exists, he/she will notify the Contractor in writing, and direct the Contractor to correct the deficiency within a specified time period. The specified time-period, which begins upon Contractor notification, will be from 1/2 hour to 24 hours long, based on the urgency of the situation and the nature of the deficiency. The Engineer shall be the sole judge regarding the time period.

The deficiency will be based on lack of repair, maintenance and diesel vehicle emissions control.

If the Contractor fails to correct the deficiency within the specified time frame, a daily monetary deduction will be imposed for each calendar day or fraction thereof the deficiency continues to exist. The calendar day(s) will begin when the time period for correction is exceeded and end with the Engineer's written acceptance of the correction. The daily monetary deduction will be \$1,000.00 for each deficiency identified.

If a Contractor or subcontractor accumulates three environmental deficiency deductions in a contract period, the Contractor will be shutdown until the deficiency is corrected. Such a shutdown will not be grounds for any extension of contract time, waiver of penalties, or be grounds for any claim.

CONSTRUCTION AIR QUALITY – IDLING RESTRICTION (BDE)

Effective: April 1, 2009

Idling Restrictions. The Contractor shall establish truck-staging areas for all diesel powered vehicles that are waiting to load or unload material at the jobsite. Staging areas shall be located where the diesel emissions from the equipment will have a minimum impact on adjacent sensitive receptors. The Department will review the selection of staging areas, whether within or outside the existing highway right-of-way, to avoid locations near sensitive areas

or populations to the extent possible. Sensitive receptors include, but are not limited to, hospitals, schools, residences, motels, hotels, daycare facilities, elderly housing and convalescent facilities. Diesel powered engines shall also be located as far away as possible from fresh air intakes, air conditioners, and windows. The Engineer will approve staging areas before implementation.

Diesel powered vehicle operators may not cause or allow the motor vehicle, when it is not in motion, to idle for more than a total of 10 minutes within any 60 minute period, except under any of the following circumstances:

- 1) The motor vehicle has a gross vehicle weight rating of less than 8000 lb (3630 kg).
- 2) The motor vehicle idles while forced to remain motionless because of on-highway traffic, an official traffic control device or signal, or at the direction of a law enforcement official.
- 3) The motor vehicle idles when operating defrosters, heaters, air conditioners, or other equipment solely to prevent a safety or health emergency.
- 4) A police, fire, ambulance, public safety, other emergency or law enforcement motor vehicle, or any motor vehicle used in an emergency capacity, idles while in an emergency or training mode and not for the convenience of the vehicle operator.
- 5) The primary propulsion engine idles for maintenance, servicing, repairing, or diagnostic purposes if idling is necessary for such activity.
- 6) A motor vehicle idles as part of a government inspection to verify that all equipment is in good working order, provided idling is required as part of the inspection.
- 7) When idling of the motor vehicle is required to operate auxiliary equipment to accomplish the intended use of the vehicle (such as loading, unloading, mixing, or processing cargo; controlling cargo temperature; construction operations, lumbering operations; oil or gas well servicing; or farming operations), provided that this exemption does not apply when the vehicle is idling solely for cabin comfort or to operate non-essential equipment such as air conditioning, heating, microwave ovens, or televisions.
- 8) When the motor vehicle idles due to mechanical difficulties over which the operator has no control.
- 9) The outdoor temperature is less than 32 °F (0 °C) or greater than 80 °F (26 °C).

When the outdoor temperature is greater than or equal to 32 °F (0 °C) or less than or equal to 80 °F (26 °C), a person who operates a motor vehicle operating on diesel fuel shall not cause or allow the motor vehicle to idle for a period greater than 30 minutes in any 60 minute period while waiting to weigh, load, or unload cargo or freight, unless the vehicle is in a line of vehicles that regularly and periodically moves forward.

The above requirements do not prohibit the operation of an auxiliary power unit or generator set as an alternative to idling the main engine of a motor vehicle operating on diesel fuel.

Environmental Deficiency Deduction. When the Engineer is notified, or determines that an environmental control deficiency exists based on non-compliance with the idling restrictions, he/she will notify the Contractor, and direct the Contractor to correct the deficiency.

If the Contractor fails to correct the deficiency a monetary deduction will be imposed. The monetary deduction will be \$1,000.00 for each deficiency identified.

SPECIAL PROVISION FOR DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION

Effective: September 1, 2000

Revised: March 2, 2019

FEDERAL OBLIGATION. The Department of Transportation, as a recipient of federal financial assistance, is required to take all necessary and reasonable steps to ensure nondiscrimination in the award and administration of contracts. Consequently, the federal regulatory provisions of 49 CFR Part 26 apply to this contract concerning the utilization of disadvantaged business enterprises. For the purposes of this Special Provision, a disadvantaged business enterprise (DBE) means a business certified by the Department in accordance with the requirements of 49 CFR Part 26 and listed in the Illinois Unified Certification Program (IL UCP) DBE Directory.

STATE OBLIGATION. This Special Provision will also be used by the Department to satisfy the requirements of the Business Enterprise for Minorities, Females, and Persons with Disabilities Act, 30 ILCS 575. When this Special Provision is used to satisfy state law requirements on 100 percent state-funded contracts, the federal government has no involvement in such contracts (not a federal-aid contract) and no responsibility to oversee the implementation of this Special Provision by the Department on those contracts. DBE participation on 100 percent state-funded contracts will not be credited toward fulfilling the Department's annual overall DBE goal required by the US Department of Transportation to comply with the federal DBE program requirements.

CONTRACTOR ASSURANCE. The Contractor makes the following assurance and agrees to include the assurance in each subcontract the Contractor signs with a subcontractor.

The Contractor, subrecipient, or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The Contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of contracts funded in whole or in part with federal or state funds. Failure by the Contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the recipient deems appropriate, which may include, but is not limited to:

- (a) Withholding progress payments;
- (b) Assessing sanctions;
- (c) Liquidated damages; and/or
- (d) Disqualifying the Contractor from future bidding as non-responsible.

OVERALL GOAL SET FOR THE DEPARTMENT. As a requirement of compliance with 49 CFR Part 26, the Department has set an overall goal for DBE participation in its federally assisted contracts. That goal applies to all federal-aid funds the Department will expend in its federally assisted contracts for the subject reporting fiscal year. The Department is required to make a good faith effort to achieve the overall goal. The dollar amount paid to all approved DBE companies performing work called for in this contract is eligible to be credited toward fulfillment of the Department's overall goal.

CONTRACT GOAL TO BE ACHIEVED BY THE CONTRACTOR. This contract includes a specific DBE utilization goal established by the Department. The goal has been included because the Department has determined the work of this contract has subcontracting opportunities that may be suitable for performance by DBE companies. The determination is based on an assessment of the type of work, the location of the work, and the availability of DBE companies to do a part of the work. The assessment indicates, in the absence of unlawful discrimination and in an arena of fair and open competition, DBE companies can be expected to perform 0.0% of the work. This percentage is set as the DBE participation goal for this contract. Consequently, in addition to the other award criteria established for this contract, the Department will only award this contract to a bidder who makes a good faith effort to meet this goal of DBE participation in the performance of the work. A bidder makes a good faith effort for award consideration if either of the following is done in accordance with the procedures set for in this Special Provision:

- (a) The bidder documents enough DBE participation has been obtained to meet the goal or,
- (b) The bidder documents a good faith effort has been made to meet the goal, even though the effort did not succeed in obtaining enough DBE participation to meet the goal.

DBE LOCATOR REFERENCES. Bidders shall consult the IL UCP DBE Directory as a reference source for DBE-certified companies. In addition, the Department maintains a letting and item specific DBE locator information system whereby DBE companies can register their interest in providing quotes on particular bid items advertised for letting. Information concerning DBE companies willing to quote work for particular contracts may be obtained by contacting the Department's Bureau of Small Business Enterprises at telephone number (217) 785-4611, or by visiting the Department's website at: <http://www.idot.illinois.gov/doing-business/certifications/disadvantaged-business-enterprise-certification/il-ucp-directory/index>.

BIDDING PROCEDURES. Compliance with this Special Provision is a material bidding requirement and failure of the bidder to comply will render the bid not responsive.

The bidder shall submit a DBE Utilization Plan (form SBE 2026), and a DBE Participation Statement (form SBE 2025) for each DBE company proposed for the performance of work to achieve the contract goal, with the bid. If the Utilization Plan indicates the contract goal will not be met, documentation of good faith efforts shall also be submitted. The documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor is selected over a DBE for work on the contract. The required forms and documentation must be submitted as a single .pdf file using the "Integrated Contractor Exchange (iCX)" application within the Department's "EBids System".

The Department will not accept a Utilization Plan if it does not meet the bidding procedures set forth herein and the bid will be declared not responsive. In the event the bid is declared not responsive, the Department may elect to cause the forfeiture of the penal sum of the bidder's proposal guaranty and may deny authorization to bid the project if re-advertised for bids.

GOOD FAITH EFFORT PROCEDURES. The contract will not be awarded until the Utilization Plan is approved. All information submitted by the bidder must be complete, accurate and adequately document enough DBE participation has been obtained or document the good faith efforts of the bidder, in the event enough DBE participation has not been obtained, before the Department will commit to the performance of the contract by the bidder. The Utilization Plan will be approved by the Department if the Utilization Plan documents sufficient commercially useful DBE work to meet the contract goal or the bidder submits sufficient documentation of a good faith effort to meet the contract goal pursuant to 49 CFR Part 26, Appendix A. This means the bidder must show that all necessary and reasonable steps were taken to achieve the contract goal. Necessary and reasonable steps are those which, by their scope, intensity and appropriateness to the objective, could reasonably be expected to obtain sufficient DBE participation, even if they were not successful. The Department will consider the quality, quantity, and intensity of the kinds of efforts the bidder has made. Mere *pro forma* efforts, in other words efforts done as a matter of form, are not good faith efforts; rather, the bidder is expected to have taken genuine efforts that would be reasonably expected of a bidder actively and aggressively trying to obtain DBE participation sufficient to meet the contract goal.

(a) The following is a list of types of action that the Department will consider as part of the evaluation of the bidder's good faith efforts to obtain participation. These listed factors are not intended to be a mandatory checklist and are not intended to be exhaustive. Other factors or efforts brought to the attention of the Department may be relevant in appropriate cases and will be considered by the Department.

(1) Soliciting through all reasonable and available means (e.g. attendance at pre-bid meetings, advertising and/or written notices) the interest of all certified DBE companies that have the capability to perform the work of the contract. The bidder must solicit this interest within sufficient time to allow the DBE companies to respond to the solicitation. The bidder must determine with certainty if the DBE companies are interested by taking appropriate steps to follow up initial solicitations.

(2) Selecting portions of the work to be performed by DBE companies in order to increase the likelihood that the DBE goals will be achieved. This includes, where appropriate, breaking out contract work items into economically feasible units to facilitate DBE participation, even when the Contractor might otherwise prefer to perform these work items with its own forces.

(3) Providing interested DBE companies with adequate information about the plans, specifications, and requirements of the contract in a timely manner to assist them in responding to a solicitation.

(4) a. Negotiating in good faith with interested DBE companies. It is the bidder's responsibility to make a portion of the work available to DBE subcontractors and suppliers and to select those portions of the work or material needs consistent with the available DBE subcontractors and suppliers, so as to facilitate DBE participation. Evidence of such negotiation includes the names, addresses, and telephone numbers of DBE companies that were considered; a description of the information provided regarding the plans and specifications for the work selected for subcontracting; and evidence as to why additional agreements could not be reached for DBE companies to perform the work.

b. A bidder using good business judgment would consider a number of factors in negotiating with subcontractors, including DBE subcontractors, and would take a firm's price and capabilities as well as contract goals into consideration. However, the fact that there may be some additional costs involved in finding and using DBE companies is not in itself sufficient reason for a bidder's failure to meet the contract DBE goal, as long as such costs are reasonable. Also the ability or desire of a bidder to perform the work of a contract with its own organization does not relieve the bidder of the responsibility to make good faith efforts. Bidders are not, however, required to accept higher quotes from DBE companies if the price difference is excessive or unreasonable. In accordance with the above Bidding Procedures, the documentation of good faith efforts must include copies of each DBE and non-DBE subcontractor quote submitted to the bidder when a non-DBE subcontractor was selected over a DBE for work on the contract.

(5) Not rejecting DBE companies as being unqualified without sound reasons based on a thorough investigation of their capabilities. The bidder's standing within its industry, membership in specific groups, organizations, or associations and political or social affiliations (for example union vs. non-union employee status) are not legitimate causes for the rejection or non-solicitation of bids in the bidder's efforts to meet the project goal.

- (6) Making efforts to assist interested DBE companies in obtaining bonding, lines of credit, or insurance as required by the recipient or Contractor.
- (7) Making efforts to assist interested DBE companies in obtaining necessary equipment, supplies, materials, or related assistance or services.
- (8) Effectively using the services of available minority/women community organizations; minority/women contractors' groups; local, state, and federal minority/women business assistance offices; and other organizations as allowed on a case-by-case basis to provide assistance in the recruitment and placement of DBE companies.

(b) If the Department determines the bidder has made a good faith effort to secure the work commitment of DBE companies to meet the contract goal, the Department will award the contract provided it is otherwise eligible for award. If the Department determines the bidder has failed to meet the requirements of this Special Provision or that a good faith effort has not been made, the Department will notify the responsible company official designated in the Utilization Plan that the bid is not responsive. The notification will also include a statement of reasons for the adverse determination. If the Utilization Plan is not approved because it is deficient as a technical matter, unless waived by the Department, the bidder will be notified and will be allowed no more than a five calendar day period to cure the deficiency.

(c) The bidder may request administrative reconsideration of an adverse determination by emailing the Department at "DOT.DBE.UP@illinois.gov" within the five calendar days after the receipt of the notification of the determination. The determination shall become final if a request is not made on or before the fifth calendar day. A request may provide additional written documentation or argument concerning the issues raised in the determination statement of reasons, provided the documentation and arguments address efforts made prior to submitting the bid. The request will be reviewed by the Department's Reconsideration Officer. The Reconsideration Officer will extend an opportunity to the bidder to meet in person to consider all issues of documentation and whether the bidder made a good faith effort to meet the goal. After the review by the Reconsideration Officer, the bidder will be sent a written decision within ten working days after receipt of the request for reconsideration, explaining the basis for finding that the bidder did or did not meet the goal or make adequate good faith efforts to do so. A final decision by the Reconsideration Officer that a good faith effort was made shall approve the Utilization Plan submitted by the bidder and shall clear the contract for award. A final decision that a good faith effort was not made shall render the bid not responsive.

CALCULATING DBE PARTICIPATION. The Utilization Plan values represent work anticipated to be performed and paid for upon satisfactory completion. The Department is only able to count toward the achievement of the overall goal and the contract goal the value of payments made for the work actually performed by DBE companies. In addition, a DBE must perform a commercially useful function on the contract to be counted. A commercially useful function is generally performed when the DBE is responsible for the work and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. The Department and Contractor are governed by the provisions of 49 CFR Part 26.55(c) on questions of commercially useful functions as it affects the work. Specific counting guidelines are provided in 49 CFR Part 26.55, the provisions of which govern over the summary contained herein.

(a) DBE as the Contractor: 100 percent goal credit for that portion of the work performed by the DBE's own forces, including the cost of materials and supplies. Work that a DBE subcontracts to a non-DBE does not count toward the DBE goals.

(b) DBE as a joint venture Contractor: 100 percent goal credit for that portion of the total dollar value of the contract equal to the distinct, clearly defined portion of the work performed by the DBE's own forces.

(c) DBE as a subcontractor: 100 percent goal credit for the work of the subcontract performed by the DBE's own forces, including the cost of materials and supplies, excluding the purchase of materials and supplies or the lease of equipment by the DBE subcontractor from the Contractor or its affiliates. Work that a DBE subcontractor in turn subcontracts to a non-DBE does not count toward the DBE goal.

(d) DBE as a trucker: 100 percent goal credit for trucking participation provided the DBE is responsible for the management and supervision of the entire trucking operation for which it is responsible. At least one truck owned, operated, licensed, and insured by the DBE must be used on the contract. Credit will be given for the following:

(1) The DBE may lease trucks from another DBE firm, including an owner-operator who is certified as a DBE. The DBE who leases trucks from another DBE receives credit for the total value of the transportation services the lessee DBE provides on the contract.

(2) The DBE may also lease trucks from a non-DBE firm, including from an owner-operator. The DBE who leases trucks from a non-DBE is entitled to credit only for the fee or commission it receives as a result of the lease arrangement.

(e) DBE as a material supplier:

(1) 60 percent goal credit for the cost of the materials or supplies purchased from a DBE regular dealer.

(2) 100 percent goal credit for the cost of materials or supplies obtained from a DBE manufacturer.

(3) 100 percent credit for the value of reasonable fees and commissions for the procurement of materials and supplies if not a DBE regular dealer or DBE manufacturer.

CONTRACT COMPLIANCE. Compliance with this Special Provision is an essential part of the contract. The Department is prohibited by federal regulations from crediting the participation of a DBE included in the Utilization Plan toward either the contract goal or the Department's overall goal until the amount to be applied toward the goals has been paid to the DBE. The following administrative procedures and remedies govern the compliance by the Contractor with the contractual obligations established by the Utilization Plan. After approval of the Utilization Plan and award of the contract, the Utilization Plan and individual DBE Participation Statements become part of the contract. If the Contractor did not succeed in obtaining enough DBE participation to achieve the advertised contract goal, and the Utilization Plan was approved and contract awarded based upon a determination of good faith, the total dollar value of DBE work calculated in the approved Utilization Plan as a percentage of the awarded contract value shall become the amended contract goal. All work indicated for performance by an approved DBE shall be performed, managed, and supervised by the DBE executing the DBE Participation Commitment Statement.

(a) **NO AMENDMENT.** No amendment to the Utilization Plan may be made without prior written approval from the Department's Bureau of Small Business Enterprises. All requests for amendment to the Utilization Plan shall be emailed to the Department at DOT.DBE.UP@illinois.gov.

(b) CHANGES TO WORK. Any deviation from the DBE condition-of-award or contract plans, specifications, or special provisions must be approved, in writing, by the Department as provided elsewhere in the Contract. The Contractor shall notify affected DBEs in writing of any changes in the scope of work which result in a reduction in the dollar amount condition-of-award to the contract. Where the revision includes work committed to a new DBE subcontractor, not previously involved in the project, then a Request for Approval of Subcontractor, Department form BC 260A or AER 260A, must be signed and submitted. If the commitment of work is in the form of additional tasks assigned to an existing subcontract, a new Request for Approval of Subcontractor will not be required. However, the Contractor must document efforts to assure the existing DBE subcontractor is capable of performing the additional work and has agreed in writing to the change.

(c) SUBCONTRACT. The Contractor must provide copies of DBE subcontracts to the Department upon request. Subcontractors shall ensure that all lower tier subcontracts or agreements with DBEs to supply labor or materials be performed in accordance with this Special Provision.

(d) ALTERNATIVE WORK METHODS. In addition to the above requirements for reductions in the condition of award, additional requirements apply to the two cases of Contractor-initiated work substitution proposals. Where the contract allows alternate work methods which serve to delete or create underruns in condition of award DBE work, and the Contractor selects that alternate method or, where the Contractor proposes a substitute work method or material that serves to diminish or delete work committed to a DBE and replace it with other work, then the Contractor must demonstrate one of the following:

(1) The replacement work will be performed by the same DBE (as long as the DBE is certified in the respective item of work) in a modification of the condition of award; or

(2) The DBE is aware its work will be deleted or will experience underruns and has agreed in writing to the change. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so; or

(3) The DBE is not capable of performing the replacement work or has declined to perform the work at a reasonable competitive price. If this occurs, the Contractor shall substitute other work of equivalent value to a certified DBE or provide documentation of good faith efforts to do so.

(e) TERMINATION AND REPLACEMENT PROCEDURES. The Contractor shall not terminate or replace a DBE listed on the approved Utilization Plan, or perform with other forces work designated for a listed DBE except as provided in this Special Provision. The Contractor shall utilize the specific DBEs listed to perform the work and supply the materials for which each is listed unless the Contractor obtains the Department's written consent as provided in subsection (a) of this part. Unless Department consent is provided for termination of a DBE subcontractor, the Contractor shall not be entitled to any payment for work or material unless it is performed or supplied by the DBE in the Utilization Plan.

As stated above, the Contractor shall not terminate or replace a DBE subcontractor listed in the approved Utilization Plan without prior written consent. This includes, but is not limited to, instances in which the Contractor seeks to perform work originally designated for a DBE subcontractor with its own forces or those of an affiliate, a non-DBE firm, or with another DBE firm. Written consent will be granted only if the Bureau of Small Business Enterprises agrees, for reasons stated in its concurrence document, that the Contractor has good cause to terminate or replace the DBE firm. Before transmitting to the Bureau of Small Business Enterprises any request to terminate and/or substitute a DBE subcontractor, the Contractor shall give notice in writing to the DBE subcontractor, with a copy to the Bureau, of its intent to request to terminate and/or substitute, and the reason for the request. The Contractor shall give the DBE five days to respond to the Contractor's notice. The DBE so notified shall advise the Bureau and the Contractor of the reasons, if any, why it objects to the proposed termination of its subcontract and why the Bureau should not approve the Contractor's action. If required in a particular case as a matter of public necessity, the Bureau may provide a response period shorter than five days.

For purposes of this paragraph, good cause includes the following circumstances:

(1) The listed DBE subcontractor fails or refuses to execute a written contract;

(2) The listed DBE subcontractor fails or refuses to perform the work of its subcontract in a way consistent with normal industry standards. Provided, however, that good cause does not exist if the failure or refusal of the DBE subcontractor to perform its work on the subcontract results from the bad faith or discriminatory action of the Contractor;

(3) The listed DBE subcontractor fails or refuses to meet the Contractor's reasonable, nondiscriminatory bond requirements;

(4) The listed DBE subcontractor becomes bankrupt, insolvent, or exhibits credit unworthiness;

(5) The listed DBE subcontractor is ineligible to work on public works projects because of suspension and debarment proceedings pursuant 2 CFR Parts 180, 215 and 1200 or applicable state law.

(6) The Contractor has determined the listed DBE subcontractor is not a responsible contractor;

(7) The listed DBE subcontractor voluntarily withdraws from the projects and provides written notice to the Contractor of its withdrawal;

(8) The listed DBE is ineligible to receive DBE credit for the type of work required;

(9) A DBE owner dies or becomes disabled with the result that the listed DBE subcontractor is unable to complete its work on the contract;

(10) Other documented good cause that compels the termination of the DBE subcontractor. Provided, that good cause does not exist if the Contractor seeks to terminate a DBE it relied upon to obtain the contract so that the Contractor can self-perform the work for which the DBE contractor was engaged or so that the Contractor can substitute another DBE or non-DBE contractor after contract award.

When a DBE is terminated or fails to complete its work on the Contract for any reason, the Contractor shall make a good faith effort to find another DBE to substitute for the original DBE to perform at least the same amount of work under the contract as the terminated DBE to the extent needed to meet the established Contract goal. The good faith efforts shall be documented by the Contractor. If the Department requests documentation under this provision, the Contractor shall submit the documentation within seven days, which may be extended for an additional seven days if necessary at the request of the Contractor. The Department will provide a written determination to the Contractor stating whether or not good faith efforts have been demonstrated.

(f) **FINAL PAYMENT.** After the performance of the final item of work or delivery of material by a DBE and final payment therefore to the DBE by the Contractor, but not later than 30 calendar days after payment has been made by the Department to the Contractor for such work or material, the Contractor shall submit a DBE Payment Agreement on Department form SBE 2115 to the Resident Engineer. If full and final payment has not been made to the DBE, the DBE Payment Agreement shall indicate whether a disagreement as to the payment required exists between the Contractor and the DBE or if the Contractor believes the work has not been satisfactorily completed. If the Contractor does not have the full amount of work indicated in the Utilization Plan performed by the DBE companies indicated in the Utilization Plan and after good faith efforts are reviewed, the Department may deduct from contract payments to the Contractor the amount of the goal not achieved as liquidated and ascertained damages. The Contractor may request an administrative reconsideration of any amount deducted as damages pursuant to subsection (h) of this part.

(g) **ENFORCEMENT.** The Department reserves the right to withhold payment to the Contractor to enforce the provisions of this Special Provision. Final payment shall not be made on the contract until such time as the Contractor submits sufficient documentation demonstrating achievement of the goal in accordance with this Special Provision or after liquidated damages have been determined and collected.

(h) **RECONSIDERATION.** Notwithstanding any other provision of the contract, including but not limited to Article 109.09 of the Standard Specifications, the Contractor may request administrative reconsideration of a decision to deduct the amount of the goal not achieved as liquidated damages. A request to reconsider shall be delivered to the Contract Compliance Section and shall be handled and considered in the same manner as set forth in paragraph (c) of "Good Faith Effort Procedures" of this Special Provision, except a final decision that a good faith effort was not made during contract performance to achieve the goal agreed to in the Utilization Plan shall be the final administrative decision of the Department. The result of the reconsideration process is not administratively appealable to the U.S. Department of Transportation.

SPECIAL PROVISION FOR WEEKLY DBE TRUCKING REPORTS (BDE)

Effective: June 2, 2012
 Revised: November 1, 2021

The Contractor shall submit a weekly report of Disadvantaged Business Enterprise (DBE) trucks hired by the Contractor or subcontractors (i.e. not owned by the Contractor or subcontractors) that are used for DBE goal credit.

The report shall be submitted to the Resident Engineer on Division of Aeronautics Form "AER 723" within ten business days following the reporting period. The reporting period shall be Sunday through Saturday for each week reportable trucking activities occur.

Any costs associated with providing weekly DBE trucking reports shall be considered as included in the contract unit prices bid for the various items of work involved and no additional compensation will be allowed.

SPECIAL PROVISION FOR SUBCONTRACTOR MOBILIZATION PAYMENTS

Effective: November 2, 2017
 Revised: April 1, 2019

To account for the preparatory work and the operations necessary for the movement of subcontractor personnel, equipment, supplies, and incidentals to the project site and for all other work or operations that must be performed or costs incurred when beginning work approved for subcontracting according to Section 80-01 of the Standard Specifications, the Contractor shall make a mobilization payment to each subcontractor.

This mobilization payment shall be made at least seven days prior to the subcontractor starting work. The amount paid shall be at the following percentage of the amount of the subcontract reported on form AER 260A submitted for the approval of the subcontractor's work.

Value of Subcontract Reported on Form AER 260A	Mobilization Percentage
Less than \$10,000	25%
\$10,000 to less than \$20,000	20%
\$20,000 to less than \$40,000	18%
\$40,000 to less than \$60,000	16%
\$60,000 to less than \$80,000	14%
\$80,000 to less than \$100,000	12%
\$100,000 to less than \$250,000	10%
\$250,000 to less than \$500,000	9%
\$500,000 to \$750,000	8%
Over \$750,000	7%

The mobilization payment to the subcontractor is an advance payment of the reported amount of the subcontract and is not a payment in addition to the amount of the subcontract; therefore, the amount of the advance payment will be deducted from future progress payments.

This provision shall be incorporated directly or by reference into each subcontract approved by the Department.

SPECIAL PROVISION FOR PAYMENTS TO SUBCONTRACTORS

Effective: November 2, 2017

Federal regulations found at 49 CFR §26.29 mandate the Department to establish a contract clause to require Contractors to pay subcontractors for satisfactory performance of their subcontracts and to set the time for such payments.

State law also addresses the timing of payments to be made to subcontractors and material suppliers. Section 7 of the Prompt Payment Act, 30 ILCS 540/7, requires that when a Contractor receives any payment from the Department, the Contractor shall make corresponding, proportional payments to each subcontractor and material supplier performing work or supplying material within 15 calendar days after receipt of the Department payment. Section 7 of the Act further provides that interest in the amount of two percent per month, in addition to the payment due, shall be paid to any subcontractor or material supplier by the Contractor if the payment required by the Act is withheld or delayed without reasonable cause. The Act also

provides that the time for payment required and the calculation of any interest due applies to transactions between subcontractors and lower-tier subcontractors and material suppliers throughout the contracting chain.

This Special Provision establishes the required federal contract clause, and adopts the 15 calendar day requirement of the State Prompt Payment Act for purposes of compliance with the federal regulation regarding payments to subcontractors. This contract is subject to the following payment obligations.

When progress payments are made to the Contractor according to Article 90-07 of the Standard Specifications, the Contractor shall make a corresponding payment to each subcontractor and material supplier in proportion to the work satisfactorily completed by each subcontractor and for the material supplied to perform any work of the contract. The proportionate amount of partial payment due to each subcontractor and material supplier throughout the contracting chain shall be determined by the quantities measured or otherwise determined as eligible for payment by the Department and included in the progress payment to the Contractor. Subcontractors and material suppliers shall be paid by the Contractor within 15 calendar days after the receipt of payment from the Department. The Contractor shall not hold retainage from the subcontractors. These obligations shall also apply to any payments made by subcontractors and material suppliers to their subcontractors and material suppliers; and to all payments made to lower tier subcontractors and material suppliers throughout the contracting chain. Any payment or portion of a payment subject to this provision may only be withheld from the subcontractor or material supplier to whom it is due for reasonable cause. If reasonable cause is asserted, written notice shall be provided to the applicable subcontractor and/or material supplier and the Engineer within five days of the Contractor receiving payment. The written notice shall identify the contract number, the subcontract or material purchase agreement, a detailed reason for refusal, the value of payment being withheld, and the specific remedial actions required of the subcontractor and/or material supplier so that payment can be made.

This Special Provision does not create any rights in favor of any subcontractor or material supplier against the State or authorize any cause of action against the State on account of any payment, nonpayment, delayed payment, or interest claimed by application of the State Prompt Payment Act. The Department will not approve any delay or postponement of the 15 day requirement except for reasonable cause shown after notice and hearing pursuant to Section 7(b) of the State Prompt Payment Act. State law creates other and additional remedies available to any subcontractor or material supplier, regardless of tier, who has not been paid for work properly performed or material furnished. These remedies are a lien against public funds set forth in Section 23(c) of the Mechanics Lien Act, 770 ILCS 60/23(c), and a recovery on the Contractor's payment bond according to the Public Construction Bond Act, 30 ILCS 550.

SPECIAL PROVISION FOR SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)

Effective: April 2, 2018

Subcontractor and Disadvantaged Business Enterprise Payment Reporting

The Contractor shall report all payments made to the following parties:

- (a) first tier subcontractors;
- (b) lower tier subcontractors affecting disadvantaged business enterprise (DBE) goal credit;
- (c) material suppliers or trucking firms that are part of the Contractor's submitted DBE utilization plan.

The report shall be made through the Department's on-line subcontractor payment reporting system within 21 days of making the payment.

SPECIAL PROVISION FOR NPDES CERTIFICATION

In accordance with the provisions of the Illinois Environmental Protection Act, the Illinois Pollution Control Board Rules and Regulations (35 Ill. Adm. Code, Subtitle C, Chapter I), and the Clean Water Act, and the regulations thereunder, this certification is required for all construction contracts that will result in the disturbance of one or more acres total land area.

The bidder certifies under penalty of law that he/she understands the terms and conditions of the general National Pollutant Discharge Elimination System (NPDES) permit (ILR100000) that authorizes the storm water discharges associated with industrial activity from the construction site identified as part of this certification.

The Airport Owner or its Agent will:

- 1) prepare, sign and submit the Notice of Intent (NOI)
- 2) conduct site inspections and complete and file the inspection reports
- 3) submit Incidence of Non-Compliance (ION) forms
- 4) submit Notice of Termination (NOT) form

Prior to the issuance of the Notice-to-Proceed, for each erosion control measure identified in the Storm Water Pollution Prevention Plan, the contractor or subcontractor responsible for the control measure(s) must sign the above certification (forms to be provided by the Department).

ILLINOIS WORKS APPRENTICESHIP INITIATIVE – STATE FUNDED CONTRACTS (BDE)

Effective: June 2, 2021

Revised: September 2, 2021

Illinois Works Jobs Program Act (30 ILCS 559/20-1 et seq.). For contracts having an awarded contract value of \$500,000 or more, the Contractor shall comply with the Illinois Works Apprenticeship Initiative (30 ILCS 559/20-20 to 20-25) and all applicable administrative rules. The goal of the Illinois Apprenticeship Works Initiative is that apprentices will perform either 10% of the total labor hours actually worked in each prevailing wage classification or 10% of the estimated labor hours in each prevailing wage classification, whichever is less. The Contractor may seek from the Department of

Commerce and Economic Opportunity (DCEO) a waiver or reduction of this goal in certain circumstances pursuant to 30 ILCS 559/20-20(b). The Contractor shall ensure compliance during the term of the contract and will be required to report on and certify its compliance. An apprentice use plan, apprentice hours, and a compliance certification shall be submitted to the Engineer on forms provided by the Department and/or DCEO.

REVISIONS TO THE ILLINOIS PREVAILING WAGE RATES

The Prevailing rates of wages are included in this Contract proposal. The rates have been ascertained and certified by the Illinois Department of Labor for the locality in which the work is to be performed and for each craft or type of work or mechanic needed to execute the work of the Contract. As required by Prevailing Wage Act ([820 ILCS](#) 130/0.01, et seq.) and this Proposal, not less than the rates of wages ascertained by the Illinois Department of Labor and as revised during the performance of a Contract shall be paid to all laborers, workers and mechanics performing work under the Contract. Post the scale of wages in a prominent and easily accessible place at the site of work.

If the Illinois Department of Labor revises the prevailing rates of wages to be paid as listed in the specification of rates, the contractor shall post the revised rates of wages and shall pay not less than the revised rates of wages. Current wage rate information shall be obtained by visiting the Illinois Department of Labor web site at <https://www2.illinois.gov/idol/Laws-Rules/CONMED/Pages/Rates.aspx> or by calling 312-793-2814. It is the responsibility of the contractor to review the rates applicable to the work of the contract at regular intervals in order to insure the timely payment of current rates. Provision of this information to the contractor by means of the Illinois Department of Labor web site satisfies the notification of revisions by the Department to the contractor pursuant to the Act, and the contractor agrees that no additional notice is required. The contractor shall notify each of its subcontractors of the revised rates of wages.

SECTION III

Lawrenceville-Vincennes International Airport (LWV) Lawrenceville, Illinois

Replace Omni-Directional Approach Lights (ODALs) on Runway 27

Illinois Project No.: LWV-5003

Prepared By:




6/10/22
Exp. 11/30/23



Engineering | Planning | Allied Services

Hanson Professional Services Inc.

1525 S. Sixth St.
Springfield, IL 62703



Kevin N. Lightfoot
COVERING ELECTRICAL
DESIGN 6/6/2022
EXPIRES: 11/30/2023

June 10, 2022

INDEX

Item No.	Description	Page No.
	Foreword	2
DIVISION I – GENERAL PROVISIONS		
50	Control of Work	3
70	Legal Regulations and Responsibility to the Public	4
80	Prosecution and Progress	7
DIVISION II – PAVING CONSTRUCTION DETAILS		
150510	Engineer’s Field Office	8
150520	Mobilization	9
DIVISION VI – LIGHTING INSTALLATION		
108	Underground Power Cable for Airports	10
109	Airport Transformer Vault and Vault Equipment.....	20
110	Airport Underground Electrical Duct Banks and Conduits.....	40
115	Electrical Manholes and Junction Structures	47
125	Installation of Airport Lighting Systems	55
AR800476	Remove Airfield Lighting	65

APPENDIX A – Constant Current Regulator and Cable Testing Forms

APPENDIX B – ODALS Ground Check Forms

Refer to IDOT Division of Aeronautics Policy Memorandums (as applicable):

96-1, “Item 610, Structural Portland Cement Concrete: Job Mix Formula Approval & Production Testing.

FOREWORD

These Special Provisions, together with applicable Standard Specifications, Rules and Regulations, Contract Requirements for Airport Improvement Projects, Payroll Requirements and Minimum Wage Rates, which are hereto attached or which by reference are herein incorporated, cover the requirements of the State of Illinois, Department of Transportation (IDOT), Division of Aeronautics (IDA) for the following improvement project at the **Lawrenceville-Vincennes International Airport, Lawrenceville, Illinois** including the following:

SCOPE OF WORK

This project will include removal and replacement of the existing Omni-Directional Approach Lights (ODALS) on Runway 27. This will include the associated cabling, conduits, duct work and vault work. This will also include training of the Airport staff by the respective ODALS manufacturer technical support staff.

GOVERNING SPECIFICATIONS AND RULES AND REGULATIONS

The State of Illinois Department of Transportation, Division of Aeronautics, Standard Specifications for Construction of Airports, **adopted April 1, 2012**, shall govern the project, except as otherwise revised or noted in these Special Provisions. All references to IDOT Specifications refer to Standard Specifications for Road and Bridge Construction, Illinois Department of Transportation, adopted January 1, 2022. In the event of inconsistencies between the Standard Specifications and the Special Provisions, the Special Provisions shall govern. The Contractor shall maintain a minimum of one printed copy of the relevant sections of the Standard Specifications for Construction of Airports on the project site at all times. The Standard Specifications for Construction of Airports is available on line at the following address link:

<http://www.idot.illinois.gov/>

RESOURCES
Manuals & Guides

REFERENCES

The following Federal Aviation Administration Advisory Circulars are referenced on the Plans and/or Special Provision Specifications in regard to safety on airports. These Advisory Circulars are available on the FAA web site at http://www.faa.gov/regulations_policies/advisory_circulars

- A. FAA AC No. 70/7460-1L (or most current issue) "Obstruction Marking and Lighting."
- B. FAA AC No. 150/5210-5D (or most current issue) "Painting, Marking, and Lighting of Vehicles Used on an Airport."
- C. FAA AC No. 150/5300-13B "AIRPORT DESIGN."
- D. FAA AC No. 150/5370-2G (or most current issue) "Operational Safety on Airports During Construction."

DIVISION I – GENERAL PROVISIONS

SECTION 50. CONTROL OF WORK

50-06 CONSTRUCTION LAYOUT STAKES

Revise the first paragraph to read:

“The Contractor shall be responsible for all construction layout and any extension of the control network provided in the plans necessary to properly complete the work.”

Under the heading RESPONSIBILITY OF THE RESIDENT ENGINEER, delete paragraphs A, B, and C.

50-16 FINAL INSPECTION

Revise the first sentence of the first paragraph to read:

“Upon due notice to the Resident Engineer/Technician by the Contractor of presumptive completion of the entire project, the charging of Contract Time shall be suspended and the Engineer will make an inspection.”

Add after the first sentence of the second paragraph:

“The charging of Contract Time shall resume upon receipt of the punch list from the Engineer and continue until the remaining work, including work as required in Section 40-08 Final Clean Up, is completed to the satisfaction of the Engineer.”

END OF SECTION 50

SECTION 70. LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC

70-10 BARRICADES, WARNING SIGNS, AND HAZARD MARKINGS. Add the following paragraphs to this section:

“The Lawrenceville-Vincennes International Airport has two paved runways. This project will require the temporary closure of Runway 9-27 and Runway 18-36. The project will also require the temporary closure of taxiways. Refer to the Construction Safety Plan Sheets for information regarding the temporary closures during construction.

Runway 9-27 will be closed any time the Contractor is working within existing runway safety area as depicted on the Proposed Safety Plan. Runway 18-36 will be closed any time the Contractor is working within the existing runway safety area as depicted on the Proposed Safety Plan. Runway closures shall be completed in accordance with the details shown in the Construction Plans. Prior to opening the respective runway, a Representative of the Airport, the Contractor, and the Resident Engineer/Resident Technician will inspect the respective runway to be sure the pavement is clean, all holes and trenches have been backfilled, and all equipment and materials are at least 400 feet from the Runway centerline. Any deficiencies noticed will be corrected before the Contractor will be allowed to re-open the runway.

When a runway is closed the runway lighting system shall be shut off and the associated Nav aids for that runway shall also be shut off. The Contractor shall coordinate with the Airport and the Resident Engineer/Technician to turn off the runway and taxiway lighting circuits as well as the Nav aids. When the runway is re-opened these circuits must be re-activated. All existing lighting and Nav aids associated with the respective runway that is closed, will be inactive during runway closures.

Except where shown otherwise on the plans, work within 79 feet of an active taxiway centerline shall require closure of that taxiway using barricades in accordance with the Construction Safety Plan.

Except where shown otherwise on the plans, work within 85.5 feet of an active taxiway centerline shall require closure of that taxiway using barricades in accordance with the Construction Safety Plan.

All work included in opening and closing the airfield pavements will be considered incidental to the Project and no additional compensation will be allowed.

The Airport Manager shall be notified a minimum of **72 hours** in advance of any work that would require the closure of the runway, and a minimum of **48 hours** notice before the closure of any taxiway. It will be the responsibility of the Contractor to properly mark the closed runway, and when the runway is re-opened, to remove the marking. The appropriate marking for a closed runway is a cross at both ends of the runway. The legs of the cross will be 60 ft. in length and 10 ft. in width. The crosses will be constructed of any suitable, locally available materials, such as fabric, plywood, or other similar material. They will be held in place in a manner locally determined to be suitable. The crosses must be properly lighted during darkness and periods of reduced visibility. The Contractor will be responsible for placing and removing the crosses as the runways are closed and opened. The Contractor will provide the Engineer with a proposed schedule of when and length of time for all closures. The Project Engineer must review and approve this schedule before any construction begins. The placement, maintenance and

removal of the crosses will be considered as an incidental item to the contract and no additional compensation will be allowed.

Extreme care will be taken not to impose on the operations of any open runway or taxiway. The proposed Safety Plan Sheets, as outlined on the Construction Plans and in the Special Provisions, will maximize safety and attempt to minimize disruption to Airport daily operations.

When the Contractor's vehicles are on Airport property, they shall be properly marked. The markings shall consist of a 3-ft sq. flag consisting of a checkered pattern of international orange and white squares of not less than 1 ft on each side displayed in full view above the vehicle. Contractor vehicles engaged in continuous hauling operations will not be required to display a flag.

The Contractor will be responsible for placing barricades and/or traffic cones at the locations shown on the Construction Plans, or as directed by the Airport Director/Manager. It will be the Contractor's responsibility to furnish and maintain the barricades equipped with red flashing or red, steady-burn lights and 20-in. sq. orange flags throughout the duration of this project.

The barricades and their maintenance will be considered as an incidental item to the contract, and no additional compensation will be allowed. Any cost of labor and equipment, which is necessary to insure safety at the Airport during the duration of the project, will be considered incidental to the contract, and no additional reimbursement for these items of work will be received.

All runway closures will be coordinated with the Airport Director/Manager. The runway will be closed in accordance with the procedures set forth on the Proposed Safety Plan Sheets. Prior to re-opening the runway the Contractor will insure the following:

1. All holes/trenches have been backfilled.
2. All equipment has been moved outside the Runway Safety Area.
3. All trucks have their beds lowered and all cranes have their booms lowered.
4. There is no material stockpiled within the Runway Object Free Area.
5. All active pavements have been swept of foreign material.
6. All lighting circuits associated with the pavement being re-opened are active and functioning correctly.
7. Representatives of the Contractor, Airport Manager and Resident Engineer/ Technician shall inspect the pavement prior to re-opening. Anything noted will be corrected prior to re-opening."

Add the following:

70-27 AIRPORT SECURITY NOTES. Airport security will be maintained at all times. The Contractor will monitor the site access to the proposed job site to insure no one will enter the access gate that is not authorized to be on the construction site or on the air side of the airport.

70-28 MAINTAINING OPERATION OF AIRFIELD LIGHTING AND NAVAIDS. Shut down of airfield lighting and/or Navaids shall only be permitted during day light hours and must be coordinated with and approved by the Airport Manager. All airfield lighting and navaid circuits shall be operational at night fall. The Contractor shall not leave the runway lighting, taxiway lighting, or any other airfield lighting circuit inoperable overnight. The Contractor shall provide temporary cable connections (in unit duct) and any manual operations of airfield lighting to keep them in operation overnight. The Contractor shall secure, identify, and place temporary exposed wiring in conduit, duct, or unit duct to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2G "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".

70-29 SITE INSPECTION. The Contractor shall be responsible for an on-site inspection prior to submitting a bid on this project. Upon receipt of a bid, it shall be assumed that the Contractor is fully familiar with the construction site.

70-30 SAFETY PLAN COMPLIANCE DOCUMENT. Prior to the issuance of a construction Notice-to-Proceed (NTP), the Contractor shall be responsible for preparing and submitting a Safety Plan Compliance Document in accordance with FAA Advisory Circular 150/5370-2G, paragraph 2.4.2, or equivalent section in subsequent/current issue. The Airport Manager shall approve this document and submit to the Division of Aeronautics for approval prior to the NTP issuance.

END OF SECTION 70

SECTION 80. PROSECUTION AND PROGRESS

80-13 CONTRACTOR'S ACCESS TO AIRFIELD. Add the following to this section:

The Contractor's personnel and equipment shall not traverse outside the designated work areas to other locations on the Airport. The designated haul route will be the only vehicular access to the construction site. It will be the responsibility of the Contractor to maintain the proposed haul route and equipment parking area for the duration of the project.

The Contractor will be responsible for obtaining any permits necessary to use the State/County/Township/City roads. All work required in complying with the above requirement will be considered incidental to the Contract, and no additional compensation will be allowed.

Failure to use the prescribed haul routes and equipment parking area or adhere to the safety requirements will result in the suspension of work.

Add the following:

80-14 EMPLOYEE PARKING. The Contractor's employees shall park their personal vehicles in the designated Equipment Parking Area as shown on the Proposed Safety and Phasing Plan Sheets. The Contractor will transport the workers from the parking area to the work area. Only Contractor vehicles needed for construction will be allowed outside of the proposed equipment parking area. No employee vehicle will be allowed onto the proposed construction site.

80-15 EQUIPMENT PARKING AND MATERIAL STORAGE. The Contractor will be allowed to park equipment and store material in the Proposed Equipment Parking Area shown on the Safety and Phasing Plan Sheets. The Contractor will maintain this area throughout the duration of the project and restore it to its original condition upon completion of the project. This work will be considered incidental to the Contract and no additional compensation will be allowed.

END OF SECTION 80

DIVISION II PAVING CONSTRUCTION DETAILS

ITEM 150510 ENGINEER'S FIELD OFFICE

CONSTRUCTION METHODS

150-2.1 Revise the following in the list of equipment and furniture required in the office:

- "B. Delete this item
- C. One two-drawer legal letter size filing cabinet with lock and an Underwriter's Laboratories insulated file device 350 degrees one hour rating.
- H. A functional internet Wi-Fi device such as a mobile hot spot providing hi-speed broadband internet access to the field office. Dial up, or equivalent, internet service will not be acceptable.
- J. Delete this item.

Add the following to the list of equipment and furniture required in the office:

- (N) One lockable cabinet or closet that is large enough in which a nuclear density machine may be stored.
- (O) High-speed internet access shall be provided to the field office by the Contractor via modem, if phone or cable connections are available. If they are not, the contractor shall provide a wireless Aircard, or similar; internet access method which shall be approved by the Resident Engineer/Technician. Dial up, or equivalent, internet service will not be acceptable.

BASIS OF PAYMENT

150-3.1 Add the following to this section:

"The mobile hot spot, wireless Aircard, internet access and associated charges will be included in the contract unit price per lump sum for Engineer's Field Office. This price shall include all utility costs and shall reflect the salvage value of the building or buildings, equipment, and furniture which remain the property of the Contractor after release by the Engineer.

Payment will be made under:

Item AR150510 Engineer's Field Office - per lump sum."

END OF ITEM 150510

ITEM 150520 MOBILIZATION

BASIS OF PAYMENT

150-3.1 Add the following to this section:

“Payment will be made under:

Item AR150520 Mobilization - per lump sum.”

END OF ITEM 150520

DIVISION VI – LIGHTING INSTALLATION

ITEM 108 UNDERGROUND POWER CABLE FOR AIRPORTS

DESCRIPTION

108-1.1. Add the following to this section:

“This Item of work shall consist of the installation (plowing, trenching, directional-boring, or installing in ducts or raceways) of cable for airfield lighting circuits and/or Navaid circuits on the runways, taxiways, aprons, and the associated homeruns at the locations shown on the Plans and in accordance with these Specifications.

In areas where there is a congestion of buried cable or where the proposed cable crosses an existing cable, the Contractor will be required to trench the proposed cable into place. In all other areas, the Contractor has the option to either trench or plow the proposed cable in unit duct into place.

When crossing existing circuits, the Contractor will be required to hand dig the trenches for the proposed cable.”

Add the following:

108-1.2 REFERENCES. The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. ASTM Specification B3 – Standard Specification for Soft or Annealed Copper Wire.
- B. ASTM Specification B8 – Standard Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard, or Soft.
- C. FAA AC 150/5340-30, “DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS”.
- D. FAA AC 150/5345-7, "SPECIFICATIONS FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS”.
- E. FAA AC 150/5345-26, “FAA SPECIFICATIONS FOR L-823 PLUG AND RECEPTACLE CABLE CONNECTORS”.
- F. FAA AC 150/5345-53 “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM” and FAA AC 150/5345-53D, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum”.
- G. FAA AC 150/5370-2, “OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION”.

- H. FAA Standard-019f; Lightning and Surge Protection, Grounding Bonding and Shielding Requirements for Facilities and Electronic Equipment.
- I. Federal Specification A-A-59544 Cable and Wire, Electrical (Power, Fixed Installation).
- J. Federal Specification A-A-55809 Insulation Tape, Electrical, Pressure-Sensitive Adhesive, Plastic.
- K. NFPA 70 – National Electrical Code (most current issue in force).
- L. NFPA 70E – Standard for Electrical Safety in the Workplace.
- M. NFPA 2638645-1 National Fire Protection Association.
- N. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.
- O. UL Standard 44 – Thermoset-Insulated Wires and Cables.
- P. UL Standard 83 – Thermoplastic-Insulated Wires and Cables.
- Q. UL Standard 854 – Service Entrance Cables.

108-1.3 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each wire, conductor, and/or cable type to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Shop drawings shall include the following information:

- A. **Certification of compliance with the AIP (Airport Improvement Program) Buy American Preferences for all materials and equipment. Do not submit ARRA (American Recovery and Reinvestment Act) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Do not submit NAFTA (North American Free Trade Agreement) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Shop drawings submitted without certification of compliance with the Airport Improvement Program Buy American Preferences or without certification of manufacture in the United States of America in accordance with the AIP Buy American Requirements will be rejected. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for more information on the AIP Buy American Preferences requirements. FAA approved equipment that is on the FAA Buy American Conformance List or the list of Nationwide Buy American Waivers Issued by the FAA complies with the AIP Buy American Preferences and will not require additional waiver paperwork for AIP projects. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for a list of Nationwide Buy American Waivers Issued by the FAA.**
- B. In order to expedite the shop drawing review, inspection and/or testing of materials, the Contractor shall furnish complete statements to the Project Engineer as to the origin, composition, and manufacturer of all material to be used in the work. Such statements shall

be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials.

- C. Illinois Department of Transportation Division of Aeronautics requires the following: ***“Under the FAA Buy American Preference, the contractor is required to submit certification that assures only domestic steel, domestic materials and domestic manufactured products are used. The Buy American statement must come from the producer, not the supplier. Producer verification must state that the items are produced in the United States and are made from 100% domestic materials. Statements that solely refer to the “Buy American Act” or “ARRA” or any federal purchasing act other than Title 49 United States Code (USC), Section 50101 will be rejected. Producers may use the Illinois Department of Transportation Domestic Material Compliance Certification Form AER 25 to satisfy this requirement.”***
- D. Indicate the pay item number for each respective cable and/or cable in unit duct.
- E. Shop drawings shall include wire/conductor/cable cut sheets with type, size, specifications, Intertek Testing Services verification/ETL listing or UL listing, manufacturer, and catalog or part number.
- F. Where cable is required to have colored coded insulation, provide information on the color coding for the respective conductors.

EQUIPMENT AND MATERIALS

108-2.1 GENERAL. Add the following:

“All cable shall be FAA approved or UL-listed as suitable for installed application. Cable furnished on this project shall comply with the requirements of the “Airport Improvement Program Buy American Preference requirements. All conductors shall be Copper.”

108-2.2 CABLE. Revise this section to read as follows:

L-824 Cable – L-824 cable shall be FAA L-824, Type C and shall conform to the requirements of FAA Advisory Circular 150/5345-7 (current edition in effect) "SPECIFICATIONS FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS". L-824 cable shall be FAA approved and listed in the current AC 150/5345-53D, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum. Circuits for use with constant current regulator outputs (runway or taxiway lighting circuits) shall use 5000-Volt rated cable. Circuits for use with low voltage applications (600 Volts or below) shall use either 5000-Volt rated cable or 600-Volt rated cable and shall have colored insulation corresponding to the respective voltage system. Cable shall be manufactured in the United States of America to comply with the Airport Improvement Program Buy American Requirement or be on the Federal Aviation Administration list of Nationwide Buy American Waivers.

Cable for use with airfield lighting series circuits (including runway lighting, taxiway lighting and taxi guidance signs) shall be one conductor No. 8, 5,000-Volt, FAA L-824, Type C, stranded.”

XLP-USE Wire. Cable shall comply with UL Standard 44, UL Standard 854, and Federal Specification A-A-59544. Conductor shall be concentric-strand, soft Copper, conforming to ASTM B8 and Underwriters' Laboratories Standard UL44 for Rubber Insulated Wires. Insulation shall be rated for 600-Volt. Insulation shall be cross-linked polyethylene conforming to Underwriters Laboratories Requirements for Type USE-2 insulation. Cable shall be UL-listed and marked USE-2. Cable shall be manufactured in the United States of America to comply with the Airport Improvement Program Buy American Requirement. Conductor insulation for 120/240 VAC, single phase, 3-wire with ground circuits shall be color-coded: Phase A – Black, Phase B – Red, Neutral – White and Ground – Green. Conductor insulation for 240 VAC, single phase, 2-wire with ground circuits shall be color-coded: Phase A – Black, Phase B – Red, and Ground – Green.

108-2.4 CABLE CONNECTIONS. Add the following to this section:

“The Contractor will use a cable stripper/penciller whenever cable connections are made.

All below grade splices shall be installed in splice cans, handholes, or manholes. Splice cans shall be L-867, Class IA, Size B (12 in. diameter), 24 in. deep, with ½ in. thick, galvanized steel cover and stainless-steel bolts. Larger size splice cans shall be provided, as applicable, for specific equipment applications or manufacturer's recommendations, and/or where detailed on the Plans. Splice cans located in areas subject to heavy aircraft or vehicle loading shall be L-868 type. The Engineer shall approve all splice locations before work commences. The furnishing and installing of splice cans for new homerun cables shall be incidental to the respective cable pay item, and no additional compensation will be allowed.”

108-2.5 RESERVED. Revise 108-2.5 as follows to comply with the requirements of FAA Advisory Circular Number 150/5370-10H Standards for Specifying Construction of Airports, Item L-108 Underground Power Cable for Airports:

“**108-2.5 SPLICER QUALIFICATIONS.** Every airfield lighting cable splicer shall be qualified in making cable splices and terminations on cables rated at and/or above 5000 Volts AC. The Contractor shall submit to the Project Engineer proof of the qualifications of each proposed cable splicer for the cable type and voltage level to be worked on. Cable splicing/terminating personnel shall have a minimum of three (3) years continuous experience in terminating/splicing medium voltage cable.”

CONSTRUCTION METHODS

108-3.1 GENERAL. Add the following to this section:

“Keep all work, power outages, and/or shut down of existing systems coordinated with the Airport Director/Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Director/Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).

Examine the site to determine the extent of the work. Contractor shall field verify existing site conditions.

Verify respective circuits and power sources prior to removing, disconnecting, relocating, installing, connecting, or working on the respective airfield lighting, taxi sign, NAVAID, or other device. Identify each respective circuit prior to performing work on that circuit.

If the Contractor wishes to lay cable on a line other than that shown on the Plans, he shall obtain approval of the Project Engineer of record before doing so and coordinate with the Resident Engineer. Any additional cable needed because of such change will be at the Contractor's expense.

New airfield lighting series circuit cables shall be installed a minimum of 18 inches below grade to comply with NEC 300.5 Underground Installations. Deeper depths might be required to avoid obstructions, or where detailed herein.

Locate and identify all existing underground utilities located within the area where the proposed cables are being installed and take all precautions to protect these utilities from damage. Care shall be taken so as not to damage any existing circuits. Any existing circuits damaged shall be immediately repaired to the satisfaction of the Engineer and/or the respective utility or owner where applicable. Any underground utility damaged will be repaired or replaced at the Contractor's own expense. Any repairs of existing cables will be considered incidental to the contract, and no additional compensation will be allowed.

In areas where there is a congestion of buried cables or where the proposed cable crosses an existing cable, the Contractor will be required to hand dig and/or carefully excavate the trench necessary for the proposed cable. At other locations, the proposed cable in unit duct, or conduit may be trenched or plowed into place. Hand digging, trenching, and/or plowing will be considered incidental to the proposed cables and no additional compensation will be allowed.

Grounding work and modifications shall not be performed during a thunderstorm or when a thunderstorm is predicted in the area. Grounding for airfield lights and taxi signs shall be as detailed on the Plans and as specified herein.

Homerun cables for a respective circuit that are installed in conduit or duct shall be run together in the same raceway or duct.

The respective personnel performing airfield lighting work, vault work, and/or test shall be familiar with, and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators and associated airport electrical vault equipment.

FAA requires that every airfield lighting cable splicer shall be qualified in making cable splices and terminations on cables rated at and/or above 5000 Volts AC and shall have a minimum of three (3) years continuous experience in terminating/splicing medium voltage cable.

Only cable in unit duct may be plowed or directional-bored.

Obey and comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.

The Contractor shall comply with the requirements of FAA AC No. 150/5370-2 (current issue in effect) “OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION”.

In the event a conflict is determined with respect to manufacturer installation instructions, National Electrical Code, and/or the Contract Documents, contact the Project Engineer for further direction.

Secure, identify and place any above ground temporary wiring in conduit to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2G, Part 2.18.3 “Lighting and Visual NAVAIDS”. All temporary installations shall comply with National Electrical Code Article 590 – “Temporary Installations.”

Existing ducts and cables associated with removal work shall be abandoned in place unless it conflicts with the installation of the airfield light, sign, duct, cable, handhole, manhole, site work, pavement or other work, then it shall be disconnected, removed, and disposed of off the site at no additional cost to the Contract. Contractor may remove abandoned cables at no additional cost to the Contract and shall have the salvage rights to abandoned cables.

Other construction projects might be in progress on the Airport at the same time as this project. The Contractor will be required to cooperate with all other contractors and the Airport Director/Manager in the coordination of the work.

Relocation of existing cables and/or cable in unit duct will require careful excavation of the cables to prevent damage to them. The cables and/or cable in unit duct shall be excavated and exposed and then relocated to a different depth and/or route to accommodate the respective site work.

The cable quantities as shown on the Construction plans are based on straight-line measurement. All other cable lengths, such as slack or waste, will not be measured for payment.

All cables installed by the Contractor shall be properly labeled and tagged at all points of access (handholes, manholes, terminal panels, control panels, and the respective wireway in the vault).

All changes to the airfield lighting system shall be documented by the Contractor and provided to the Resident Engineer.”

108-3.3 TRENCHING. Add the following to this section:

- “F. Cable installed in cultivated fields shall be installed a minimum of 42 in. below grade.
- G. Any and all trenches will be backfilled to a smooth grade to the satisfaction of the Engineer. All trench settlement shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed cable will be incidental to the respective 108 Pay Item.”

108-3.5 SPLICING. Add the following:

“In-line connections for existing 600 Volt cables cut during construction shall be repaired with a cast splice kit. cast splice kit. The Contractor shall have a minimum of ten splice kits for each type of splice, on the job site at all times for emergency repairs. Cast splice kits shall be as specified in paragraph (a) of Item 108-2.4.

In-line connections for existing 5,000 Volt series circuit cables cut during construction shall be repaired with an FAA approved L-823 connector kit properly sized for the respective cables. The Contractor shall have a minimum of ten splice kits for each type of splice, on the job site at all times for emergency repairs. FAA approved L-823 connector kits shall be as specified in paragraph (b) of Item 108-2.4.

Splice cans shall be provided for existing cables cut and repaired for each splice in cables not to be abandoned. Where a splice can is not readily available at the time of the cable damage, splice markers shall be temporarily installed over each splice in cables not to be abandoned, then these splices shall later be replaced with new splices in an L-867 splice can. Costs associated with splice cans for accidental cable cuts caused by the Contractor, repairs and/or shortages of cables will be the responsibility of the Contractor and no additional compensation will be allowed.

There shall be no splices between series lighting circuit isolation transformers. In the event that a series lighting circuit cable is cut between isolation transformers, the entire length of cable between these isolation transformers shall be replaced, at the Contractor's own expense.

The Contractor shall use a cable stripper/penciller whenever cable connections are made.

All splices and connections will be considered incidental to the respective cable.”

108-3.8 TESTING. Add the following.

- K. Prior to beginning airfield lighting modifications, cable installation, and/or any other work that might possibly affect airfield lighting circuits, all existing series circuit cables shall be Megger tested and recorded at the vault. All existing series circuit cable loops shall have the resistance tested and recorded for each circuit at the vault. Each constant current regulator shall be tested with results recorded. Copies of test results shall be provided to the Resident Engineer and the respective Project Engineer within 5 business days of conducting the respective set of tests. See the testing forms in Appendix A.
- L. After airfield lighting modifications, additions, and/or upgrades have been completed, series circuit cables shall be Megger tested and recorded at the vault. All series circuit cable loops shall have the resistance tested and recorded for each circuit at the vault. Each constant current regulator shall be tested with results recorded. Copies of test results shall be provided to the Resident Engineer and the respective Project Engineer within 5 business days of conducting the respective set of tests. See the testing forms in Appendix A.

- M. Insulation resistance testing equipment for use with 5,000 Volt series circuit cables shall use an insulation resistance tester capable of testing the cables at 5,000 Volts. Older series circuit cables and/or cables in poor condition may require the test voltage to be performed at a voltage lower than 5,000 Volts (Example 1,000 Volts, 500 Volts, or less than 500 Volts). The respective test voltage shall be recorded for each cable insulation resistance test result.
- N. Insulation resistance testing equipment for use with 600 Volt rated cables shall use a 500 Volt insulation resistance tester. The respective test voltage shall be recorded for each cable insulation resistance test result.
- O. It is recommended to use the same insulation resistance test equipment throughout the project to ensure reliable comparative readings at the beginning of the project and at the completion of the project.
- P. Disconnect the airfield lighting series circuit cables from the constant current regulator when performing cable insulation resistance tests (Megger Tests). Test the cables that go to the airfield for the respective airfield lighting series circuit. Connect the cable insulation resistance tester to one of the airfield lighting series circuit cables and to a good ground in the airport electrical vault such as the airport vault ground bus. Conduct the cable insulation resistance test on each respective cable for not less than 90 seconds. Record the test results at the end of the time duration for the test.
- Q. FAA Advisory Circular 150/5340-26C Maintenance of Airport Visual Aid Facilities provides guidance on Insulation Resistance Tests. Also refer to the user manual for the respective cable insulation resistance tester. Reasonably new series circuit cables and transformers with good connections should read 500 Mega-Ohms to 1,000 Mega-Ohms or higher. The readings should decrease with age. The resistance value declines over the service life of the circuit; a 10-20 percent decline per year may be considered normal. A yearly decline of 50 percent (4 percent monthly) or greater indicates the existence of a problem, such as a high resistance ground, serious deterioration of the circuit insulation, lightning damage, bad connections, bad splices, cable insulation damage, or other failure. FAA Advisory Circular 150/5340-26C notes *“Generally speaking, any circuit that measures less than 1 megohm is certainly destined for rapid failure.”* Airfield lighting series circuits with cable insulation readings of less than 1 megohm are not uncommon for older circuits that are 20 years or more of age.
- R. Based on information in FAA AC No. 150/5340-26C Maintenance of Airport Visual Aid Facilities, the cable insulation resistance value inevitably declines of the service life of the circuit; a 10-20 percent decline per year may be considered normal. In the event that the cable insulation resistance readings have declined more than 2 percent per month it might indicate cable damage due to lightning or damage as a result of Contractor operations. Where the cable insulation resistance readings have declined more than 2 percent per month over the project construction duration as a result of Contractor operations, Contractor will need to investigate, address, and repair the respective cable circuits.
- S. All existing series circuit cable loops shall also have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. The resistance of the series circuit loop with connections using #8 AWG copper conductor should be approximately 0.8 to 1 Ohm per thousand feet of cable length. The resistance of the series circuit loop with

connections using #6 AWG copper conductor should be approximately 0.5 to 0.7 Ohm per thousand feet of cable length. The number of series circuit transformers and connections will affect the overall resistance of the series circuit loop and therefore the measurements might be slightly higher than the calculated resistance for the respective length of cable.

- T. The Contractor is responsible to employ qualified personnel that are capable of properly conducting the required tests to the satisfaction of the Project Engineer. Tests that provide unsatisfactory results shall be reviewed to determine the possible cause of unsatisfactory results, corrections shall be made, and the tests shall be conducted again.”

Add the following:

108-3.12 LOCATING OF EXISTING UNDERGROUND UTILITIES AND CABLES. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatsoever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain, from the respective utility companies, detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer/Technician shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract.

All utility cables and lines shall be located by the respective utility. **Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123.** Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

Payment for locating and marking underground utilities and cables will not be paid for separately, but shall be considered incidental to the plowing/trenching/boring of cable and cable in unit duct.

108-3.13 SEPARATION OF HIGH-VOLTAGE AND LOW-VOLTAGE WIRING. High-voltage circuit wiring (airfield lighting 5000 Volt series circuits and/or other circuits rated above 600 Volts) and low-voltage circuit wiring (rated 600 Volts and below) shall maintain separation from each other. High-voltage wiring and low-voltage wiring shall not be installed in the same wireway, conduit, duct, raceway, handhole, or junction box. Where necessary provide split flexible duct around low voltage cables located in a handhole with high voltage cables, to isolate the cables from possible contact with each other.

108-3.14 IDENTIFICATION OF CABLES. At electrical handholes and manholes, identify and label each cable originating in the vault with respect to the system or device served. Provide identification tags rated suitable for the respective locations with permanent markings.

METHOD OF MEASUREMENT

108-4.1. Add the following:

“The footage of cable and/or cable in unit duct installed in duct, conduit, or raceway to be paid for shall be the number of linear feet of cable installed in duct, conduit, or raceway measured in place by direct measurement, completed, ready for operation and accepted as satisfactory with no allowance being made for overrun due to slack, turns, splices, etc. Slack cable required to perform cable splices outside of the respective splice cans, handholes, or manholes, shall be incidental to the respective cable pay item and no additional measurement for payment will be made. Coring and interface to handholes, manholes, or junction structures shall be incidental to the respective cable pay item and no additional measurement for payment will be made. The relocation, interface, and/or adjustment of existing cable and/or cable in unit duct will be considered incidental to the work for which it is required, and no additional compensation will be allowed. Cable will be measured for payment from the respective termination or splice point in the field up to the vault or respective termination point.

Trenching including the excavation, backfill, dewatering and restoration shall not be measured for payment, but shall be considered incidental to the respective cable pay item for which it is required.

Power and control cables installed between the ODALS units will be considered incidental to the item for which they are required, and no additional compensation will be allowed. Airfield lighting series circuit wiring associated with the interface between the ODALS and the runway lighting system will be considered incidental to the item for which they are required, and no additional compensation will be allowed.

BASIS OF PAYMENT

108-5.1. Add the following:

“Payment will be made at the contract unit price per lin. ft. of cable completed and accepted by the Resident Engineer. This price shall be full compensation for furnishing all materials, and for all preparation, assembly, and installation of these materials; for all plowing, trenching, directional-boring, coring of manholes or handholes, installation in ducts, raceways, conduits, splice cans, handholes, or manholes, and for all excavation and backfilling; for all site restoration (topsoiling, grading, seeding, mulching) and pavement restoration; and for all labor, equipment, tools, testing, and incidentals necessary to complete this Item.

Payment will be made under:

Item AR108084 1/C #4 XLP-USE - per linear foot”

END OF ITEM 108

ITEM 109 AIRPORT TRANSFORMER VAULT AND VAULT EQUIPMENT

DESCRIPTION

Add the following

109-1.2. Item AR109200 "Install Electrical Equipment" shall consist of furnishing and installing electrical equipment and materials inside the vault as detailed on the Plans and specified herein. This item shall include all labor, materials, transportation, equipment, wiring, raceways, grounding, warranties, tools, coordination, removals, relocations, operational instructions, labeling, testing, and all incidentals required to place the vault and associated equipment into proper working order as a completed unit to the satisfaction of the Owner and Resident Engineer.

Included under this item shall be the following:

- A. Field verification of existing site conditions to determine the complexity of the proposed work.
- B. Coordinating all work with the Airport Manager and/or designated Airport Maintenance Staff, the respective FAA personnel and the Resident Engineer.
- C. Furnishing and installing all associated electrical equipment, materials, and support hardware in the vault as detailed on the Plans and specified herein.
- D. Furnishing and installing all raceways, conduits, pull boxes, and ducts in, beneath, and adjacent to the vault. Conduits and ducts from the vault to handholes or junction structures near the vault will be included with this item.
- E. Furnishing and installing all necessary cable and wiring at the vault as detailed on the Plans and specified herein.
- F. Furnishing and installing all grounding and surge protection as detailed on the Plans and specified herein.
- G. Locating, identifying, relocating, and/or replacing existing airfield lighting cables, power cables, and/or control wiring, as necessary to disconnect these respective cables and wiring from the existing equipment and reconnect, replace and/or interface these respective cables to the new or relocated equipment. All work shall be coordinated with the Airport Director/Manager and shall be coordinated to minimize down time to the respective airfield systems.
- H. Removal and/or relocation of existing equipment and/or materials.
- I. Furnishing and installing lockout/tagout kits and following lockout/tagout procedures for safety of personnel.
- J. Furnishing shop drawings for new equipment and materials.
- K. Testing, adjusting, and retesting, where applicable, respective equipment and modifications to existing systems for proper operation.

- L. Submitting test reports to the Resident Engineer and the Project Engineer.
- M. Labeling all electrical equipment and incidentals necessary to place all of the equipment in operation as a complete unit acceptable to the Owner and Resident Engineer.
- N. Furnishing operation, maintenance, and installation manuals for all new equipment.”

109-1.3 REFERENCES. The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. ASTM A706, Standard Specification for Deformed and Plain Low-Alloy Steel Bars for Concrete Reinforcement.
- B. ANSI/ICEA S-85-625, Standard for Telecommunications Cable Aircore, Polyolefin Insulated, Copper Conductor Technical Requirements.
- C. FAA AC 150/5340-26, “MAINTENANCE OF AIRPORT VISUAL AID FACILITIES”.
- D. FAA AC 150/5340-30, “DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS”.
- E. FAA AC 150/5345-7, “SPECIFICATION FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS”.
- F. FAA AC 150/5345-53, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM”.
- G. FAA AC 150/5370-2, “OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION”.
- H. FAA STD-019f, Lightning and Surge Protection, Grounding Bonding and Shielding Requirements for Facilities and Electronic Equipment.
- I. Federal Specification A-A-59544, Cable and Wire, Electrical (Power, Fixed Installation).
- J. Federal Specification A-A-55809, Insulation Tape, Electrical, Pressure-Sensitive Adhesive, Plastic.
- K. IEEE 1584, Guide for Performing Arc-Flash Hazard Calculations.
- L. NFPA 70 – National Electrical Code (most current issue in force).
- M. NFPA 70E – Standard for Electrical Safety in the Workplace.
- N. NFPA 780 – Standard for the Installation of Lightning Protection Systems.
- O. OSHA 29 CFR Part 1910, Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.

- P. UL Standard 6, Electrical Rigid Metal Conduit – Steel.
- Q. UL Standard 514B, Conduit, Tubing, and Cable Fittings.
- R. UL Standard 44, Thermoset-Insulated Wires and Cables.
- S. UL Standard 83, Thermoplastic-Insulated Wires and Cables.
- T. UL Standard 467, Grounding and Bonding Equipment.
- U. UL Standard 486A-486B, Wire Connectors.
- V. UL Standard 514C, Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers.
- W. UL Standard 651, Schedule 40, 80, Type EB and A Rigid PVC Conduit and Fittings.
- X. UL Standard 651A, Type EB and A Rigid PVC Conduit and HDPE Conduit.
- Y. UL Standard 854, Service Entrance Cables.

109-1.4 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for vault equipment and materials to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** The preferred shop drawing submittal format shall be electronic (PDF) copies. Shop Drawings shall clearly indicate proposed items, capacities, characteristics, and details in conformance with the Plans and Specifications. The respective manufacturer shall certify capacities, dimensions, special features, etc. When a submittal is marked “Revise and Resubmit”, “Rejected”, and/or “Not Approved”, do not proceed with that part of the work covered by the submittal, including purchasing, fabrication, delivery, or other activity. Revise or prepare a new submittal in accordance with the notations, resubmit, and repeat if necessary to obtain a different action mark such as “No Exceptions Taken” or “Furnish as Corrected”. Contractor is responsible for compliance with the specified characteristics. Contractor’s responsibility for error and omissions in submittals is not relieved by the Project Engineer’s review of submittals. Accompany each submittal with a transmittal letter that includes the date, project title and number, Contractor’s name and address, the number of Shop Drawings, product data and/or samples submitted, notification of any deviations from the Contract, and any other pertinent information. Shop drawings shall include the following information:

- A. **Certification of compliance with the AIP (Airport Improvement Program) Buy American Preferences for all materials and equipment. Do not submit ARRA (American Recovery and Reinvestment Act) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Do not submit NAFTA (North American Free Trade Agreement) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Shop drawings submitted without certification of compliance with the Airport Improvement Program Buy American Preferences or without certification of manufacture in the United States of America in accordance with the AIP Buy American Requirements will be rejected. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for more information on the AIP Buy American Preferences requirements. FAA approved equipment that is on the FAA Buy American Conformance List or the list of Nationwide Buy American Waivers Issued by the FAA complies with the AIP Buy**

American Preferences and will not require additional waiver paperwork for AIP projects.

- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Furnish shop drawings for equipment and materials.
- D. Provide shop drawings for lockout/tagout kits.
- E. Provide cut sheets for all types of conduit used in the vault (for example galvanized rigid steel conduit and UL listed liquid tight flexible metal conduit). Include certification that steel conduits are made with 100 percent domestic steel.
- F. Provide cut sheets for the power and control circuit conductors.

EQUIPMENT AND MATERIALS

VAULT OR PREFABRICATED METAL HOUSING

109-2.5 RIGID STEEL CONDUIT. Add the following:

“GRSC shall be heavy wall, hot-dipped, galvanized steel pipe bearing the UL label and conforming to UL-6 and ANSI Specification C80.1. Couplings, connectors, and fittings for rigid steel conduit shall be threaded, galvanized steel, or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 and UL-514B. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.”

109-2.19 OTHER ELECTRICAL EQUIPMENT. Add the following:

“Proposed electrical equipment and materials for the vault shall be as follows:

- A. Circuit Breakers. Circuit breakers, to be installed in the existing vault panelboard, shall be compatible with the existing panelboard. Circuit breakers shall be bolt-on type with an amp interrupting capacity of 22,000 Amps minimum at 120/240 VAC. Circuit breaker amperage trip settings and number of poles shall be as detailed on the Plans.
- B. Safety Switches. Safety switches shall be heavy duty, UL-listed, with amperage, voltage, number of poles, and type (fusible or not fusible), and accessories as detailed on the Plans. Safety switches shall be pad lockable in the off position. Include ground lugs or grounding kits with all safety switches. Safety switches located outdoors, or in damp areas shall be in NEMA 4X stainless steel enclosures. Safety switches located in

hazardous classified areas shall be UL-listed or FM approved as suitable for the respective location. Safety switches shall be as manufactured by Square D, Eaton Cutler-Hammer, or equivalent. Safety switches shall be manufactured in the United States to comply with the Airport Improvement Program Buy American Preferences requirements.

- C. Junction and Pull Boxes. Junction and pull boxes shall be sized, as required for conductors and splices and per 2017 NEC Article 314. Boxes shall be UL-listed. Special boxes made to suit conditions shall be used to accommodate the respective application, or where required by the NEC, even though they might not be indicated on the Drawings. Surface-mounted exterior junction and pull boxes located in non-hazardous, non-classified areas shall be NEMA 4X stainless steel or aluminum, with hinged cover as manufactured by Hoffman, E-Box, Saginaw Control & Engineering, or approved equal. All junction and pull boxes installed in classified hazardous areas (Class 1, Division 1 or 2, Group D) shall be NEMA 7 and NEMA 4 and shall comply with applicable provisions of the NEC, including, but not limited to, Articles 500 and 501.
- D. Liquid-Tight Flexible Metal Conduit. Liquid-tight, flexible metal conduit shall consist of polyvinyl jacket over flexible hot dip galvanized steel tubing. The flexible conduit shall be completely sealed from liquids, dust, dirt, and fumes and be resistant to oil, gasoline, grease, and abrasion. Jacket shall also be sunlight-resistant. Liquid-tight flexible metal conduit shall be UL-listed, suitable for use as a grounding conductor, and comply with Article 350 of the NEC. **Liquid-tight flexible metal conduit and associated fittings shall be UL-listed to meet the requirements of NEC 350.6.** Liquid-tight flexible metal conduit shall be Anaconda Sealtite Type UA as manufactured by Anamet Electrical Inc., Licutite Type LA as manufactured by Electri-Flex Company, Liquid-Tuff Type LFMC as manufactured by Atkore International AFC Cable Systems, or approved equal. Do not install liquid-tight, flexible metal conduit that is not UL listed. Confirm liquid-tight, flexible metal conduit bears the UL label prior to installation. Provide certification that liquid-tight flexible metal conduit is produced from domestic steel.
- E. Step-Up Transformer. Step-up transformer for use with the Runway 27 ODALS power feeder shall have KVA rating as detailed on the Plans, 208 VAC to 120/240 VAC, single phase with 180 degree C insulation class and 115 degree C temperature rise rating. Transformer shall be resin-filled suitable for use indoors or outdoors. Transformer shall be UL listed and shall include electrostatic shielding. Step-up transformer shall be suitable for wiring as 208 VAC, single phase, 2-wire, 60 Hz primary and 120/240 VAC, single phase, 3-wire secondary in accordance with the manufacturer's recommendations without affecting the warranty or causing excessive heating of the transformer.
- F. Boost Transformers. Boost transformer for use with the power feeder circuit for the ODALS shall be 240 VAC primary, 12/24 VAC, secondary or 240 VAC primary, 16/32 VAC secondary sized and rated to handle the respective equipment loads. Boost transformer shall be suitable for connection as 240 VAC, 60 Hz, 1-phase, 2-wire input, and output connections as 252 VAC, 264 VAC, 256 VAC, or 272 VAC (as applicable for the respective load, cable size, and voltage drop), 60 Hz, 1-phase, 2-wire output. Boost transformer shall be UL-listed and designed, manufactured, and tested in accordance with ANSI Standard Z535.3 and NEMA ST20, where applicable. Transformer shall be suitable for indoor/outdoor installation with a NEMA 3R weatherproof enclosure. Boost transformers for ODALS shall be properly sized for the respective equipment load, cable, and voltage drop application to meet the requirements of the ODALS manufacturer.

- G. Lockout/Tagout Kit. Provide a Lockout Station suitable for wall mounting, with 10 lockout padlocks each with a different key, 5 lockout hasps to accommodate multiple padlocks, and 100 lockout tags. Lockout station and components shall comply with OSHA Standard 1910.147. Include hardware to mount on the vault interior wall.”

109-2.20 WIRE. Add the following to Section A. Control Circuits:

“THWN Wire. Cable shall comply with Underwriters’ Laboratories Standard UL-83 and Federal Specification A-A-59544. Conductor shall be soft-annealed, uncoated Copper and shall comply with ASTM B3 and B8. Insulation shall be rated for 600-Volt. Insulation shall be polyvinyl-chloride conforming to Underwriters’ Laboratories requirements for Type THW. The outer covering shall be nylon-conforming to Underwriters’ Laboratories for type THHN or THWN. Cable shall be UL-listed and marked THWN.”

Delete paragraphs 1, 2, and 3 under Section B. Power Circuits.

Add the following:

“Power Cable (600-Volt and Below). All power wiring, 600-Volt and below, shall be the type, size, and number of conductors as noted on the Plans.

THWN Wire. Cable shall comply with Underwriters’ Laboratories Standard UL-83 and Federal Specification A-A-59544. Conductor shall be soft-annealed, uncoated Copper and shall comply with ASTM B3 and B8. Insulation shall be rated for 600-Volt. Insulation shall be polyvinyl-chloride conforming to Underwriters’ Laboratories requirements for Type THW. The outer covering shall be nylon-conforming to Underwriters’ Laboratories for type THHN or THWN. Cable shall be UL-listed and marked THWN-2. Power and control wiring shall be Type THWN-2, or approved equal.
Note where THWN wiring is referenced on the Plans, it shall be THWN-2.

XHHW Wire. Cable shall be UL-listed as Type XHHW-2 per UL Standard 44. Cable shall also conform to ICEA S-95-658/NEMA WC70 and Federal Specification A-A-59544. Conductors shall be Class B stranded, annealed, uncoated Copper per UL Standard 44. Insulation shall be rated for 600-Volt. Insulation shall be cross-linked polyethylene complying with the physical and electrical requirements of UL Standard 44 for Type XHHW-2. XHHW wire may be used in place of THWN wire for all applications.

XLP-USE Wire. Cable shall comply with UL Standard 44, UL Standard 854, and Federal Specification A-A-59544. Conductor shall be concentric-strand, soft Copper, conforming to ASTM B8 and Underwriters’ Laboratories Standard UL44 for Rubber-Insulated Wires. Insulation shall be rated for 600-Volts. Insulation shall be cross-linked polyethylene conforming to Underwriter’s Laboratories Requirements for Type USE-2 insulation. Cable shall be UL-listed and marked USE-2.

Series Circuit 5000-Volt Cable. Cable for use with series circuit airfield lighting shall be FAA-L-824, Type C cable complying with Item 108. L-824 cable shall be FAA approved and listed in the current AC150/5345-53D, AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum. Cable furnished on this project shall comply with the requirements of the Airport Improvement Program Buy American

Requirement and the “Buy American Act”. Circuits for use with constant current regulator outputs (runway or taxiway lighting circuits) shall use 5000-Volt rated cable.

Grounding electrode conductors and/or bonding jumpers shall be the size and type, as detailed on the Plans. Ground wire for bonding constant current regulator housings, cutout enclosures, and other vault equipment frames to the vault ground bus shall be #6 AWG stranded Copper.”

CONSTRUCTION METHODS

INSTALLATION OF EQUIPMENT IN VAULT OR PREFABRICATED METAL HOUSING

109-3.10 GENERAL. Add the following:

“The Contractor shall furnish and install all equipment and materials necessary for complete and operational installation of all vault equipment, as specified herein and as shown on the Plans. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of NFPA 70 - National Electrical Code (NEC) most current issue in force, and all other applicable local codes, laws, ordinances, and requirements in force. Electrical equipment shall be installed in conformance with the respective manufacturer’s directions and recommendations for the respective application. Any installations, which void the UL listing, Intertek Testing Services verification/ETL listing, (or other third-party listing) and/or the manufacturer’s warranty of a device, will not be permitted.

- A. Keep a copy of the latest NEC in force on site, at all times during construction for use as a reference. Contractor shall keep a copy of the Plans, Special Provision Specifications including any addenda, and copies of any change orders on site at all times during construction.
- B. Examine the site to determine the extent of the work. Contractor shall field verify existing site conditions.
- C. Verify respective circuits and power sources prior to removing, disconnecting, relocating, installing, connecting, or working on the respective service, feeder, branch circuit, airfield lighting system, Navaid, or other device.
- D. Identify each respective circuit prior to performing work on that circuit.
- E. New work shall be coordinated with the Airport Director/Manager and to minimize downtime to existing systems. Contractor shall coordinate work and any power outages with the Airport Director/Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Director/Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).

- F. Locate Existing Underground Utilities and Cables. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatsoever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain, from the respective utility companies, detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract. All utility cables and lines shall be located by the respective utility. **Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123.** Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.
- G. In areas where there is a congestion of buried cables or where the proposed duct, cable, or work crosses an existing cable, the Contractor will be required to hand dig and/or carefully excavate the trench necessary for the proposed duct, cable, or other work.
- H. Grounding work and modifications shall not be performed during a thunderstorm or when a thunderstorm is predicted in the area.
- I. Homerun cables for a respective circuit that are installed in conduit, duct, or raceway shall be run together in the same conduit, duct or raceway.
- J. The respective personnel performing airfield lighting work, vault work, and/or tests shall be familiar with and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.
- K. Feeder circuit conductors, branch circuit conductors, power wiring, control wiring, airfield lighting series circuit conductors, and other wiring at the Vault shall be installed in conduit, duct, wireways, pull boxes, junction boxes, or raceways. No exposed power or control wiring will be permitted.
- L. Obey and comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.

- M. Other construction projects might be in progress on the Airport at the same time as this project. The Contractor will be required to cooperate with all other contractors and the Airport Director/Manager in the coordination of the work.
- N. The Contractor shall comply with the requirements of FAA AC No. 150/5370-2G (or most current issue) "OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION".
- O. In the event a conflict is determined with respect to manufacturer installation instructions, National Electrical Code, and/or the Contract Documents, contact the Project Engineer for further direction.
- P. Secure, identify, and place temporary exposed wiring in conduit, duct, or unit duct to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2G, Part 2.18.3 "Lighting and Visual NAVAIDS". All temporary installations shall comply with National Electrical Code Article 590 – "Temporary Installations".
- Q. Equipment installed by the Contractor shall be properly labeled, and all cables must be tagged.
- R. Obtain approval from the Airport Director/Manager prior to shutting down a runway or taxiway. When a respective Runway is closed the respective runway lighting and NAVAIDS for the runway shall be shut off. Keep respective Nav aids active during times when the runway is open. Nav aids receiving maintenance shall be shut off until operating properly. When a respective taxiway is closed the respective taxiway lighting for that taxiway shall be shut off.
- S. Record and document all changes to the airfield lighting system and provide this information to the Resident Engineer."

109-3.12 SWITCHGEAR AND PANELS. Add the following to this section:

- A. Installation of Control Panels. Install control panels, as detailed on the Plans and in conformance with the respective panel manufacturer's requirements and/or recommendations.
- B. Installation of Circuit Breakers in Panelboards. Install circuit breakers in panelboards in conformance with the respective manufacturer's directions. Connect only one wire/cable to each breaker terminal. Update circuit directory to identify the respective device fed by each new circuit breaker.
- C. Installation of Safety Switches. Safety switches shall be provided with appropriate mounting hardware and strut support. Strut support shall be hot-dipped, galvanized steel strut support, manufactured by Unistrut, B-Line, or approved equal. Provide zinc rich paint applied to field cuts of strut support to minimize the potential for corrosion per the respective strut support manufacturer's recommendation. All hardware shall be corrosion-resistant. Mount safety switches securely in accordance with the manufacturer's recommendations/instructions and as required for the respective application. Inspect all safety switches for proper operation, tight and

secure connections, and correctness. All safety switch enclosures shall be bonded to ground with a ground lug or bar and ground wire. Field cut holes in safety switch enclosures to accommodate conduit entrances. Where safety switch enclosures are provided with concentric knockouts, and the respective conduit does not use the largest knockout, install a grounding bushing with ground wire connections between the bushing and the ground bus. Where safety switches enclosures are used for service entrance applications provide a grounding bushing with ground wire connections between the bushing and the ground bus at each metal conduit entry. Do not use safety switch enclosures for a splice box or for a pull box. Do not route control wires or other circuit wiring through a safety switch enclosure. Where splices are required or other control circuit wires are installed in the respective conduit to a safety switch, provide a separate junction box to accommodate the splices and/or other circuit conductors. Provide weatherproof, abrasion-resistant, engraved legend plates for each safety switch noting the device served, the power source, and the voltage system.”

Add the following:

109-3.13 DUCT AND CONDUIT. Add the following to this section:

- “A. Conduit shall be installed in accordance with the following:
1. All service, feeder, branch circuit, and control circuit conduits associated with the vault shall be galvanized rigid steel conduit as detailed on the Plans.
 2. Schedule 80 PVC conduits shall be used for individual grounding electrode conductors and/or bonding jumpers.
 3. Liquid-tight, flexible metal conduit shall be used as specified herein.
- B. Conduit Runs:
1. All conduits shall be sized, as indicated on the Drawings, or if conduit sizes not shown shall be in accordance with the NEC. All conduit systems shall be mechanically and electrically continuous from source of current to all outlets and grounded in accordance with the NEC.
 2. Run all exposed conduit parallel to building walls using right angle bends. Exposed diagonal runs of conduit will not be permitted. Do not install conduit on roof surfaces unless specifically indicated on the Drawings.
 3. Ream conduit after threads are cut. Cut ends square and butt solidly into couplings.
 4. Prevent the accumulation of water, foreign matter, or concrete in the conduits during the execution of the work. Temporarily plug conduit, blowout, and swab before wires are pulled.
 5. Fasten conduits to all sheet metal boxes and cabinets with two locknuts in accord with the NEC where insulated bushings are used and where

bushings cannot be brought into firm contact with the metal enclosures; otherwise, use at least a single locknut and bushing.

6. Seal each underground joint and make water-tight.
7. Where building construction or other conditions make it impossible to use standard threaded couplings, install water-tight, threaded unions.
8. Make changes in direction of runs with symmetrical bends or cast-metal fittings. Make field-made bends and offsets with conduit bending machine to avoid changing the internal diameter of the conduit and not damage its protective coating either inside or outside. Individual bends shall not exceed 90 degrees, and not more than 270 degrees total bends will be allowed in any one conduit run. Where more bends are necessary, and conduit runs exceed 150 lin. ft., install a suitable pull box or junction box.
9. Provide empty conduits installed with a pull wire. Pull wire shall be No. 14 AWG, zinc-coated steel or of plastic having not less than 200 lb. tensile strength. Leave not less than 12 in. of slack at each end of the pull wire.
10. Use liquid-tight, flexible metal conduit for final connection to motors, constant current regulators, transformers, portable equipment, and for equipment subject to vibration and noise transmission. For each conduit size up to 1-in. trade size, flexible conduit shall be minimum length of 12 in. and a maximum length of 36 in. and for conduit sizes above 1-in. trade size, flexible conduit shall be minimum length of 20 in. and maximum length of 48 in. Liquid-tight flexible metal conduit and associated fitting shall be UL listed to meet the requirements of NEC 350.6. Liquid-tight flexible metal conduit that is used for flexibility (including connections to motors, constant current regulators, and transformers) shall require an external bonding jumper or internal equipment grounding conductor per NEC 350.60. Do not install liquid-tight flexible metal conduit that is not UL listed. Confirm liquid-tight flexible metal conduit bears the UL label prior to installation
11. Provide duct seal at conduit terminations inside enclosures where the respective conduit is from below grade.
12. All enclosures rated NEMA 4, 4X shall have watertight hubs at conduit entrances UL listed NEMA 4, 4X for the respective enclosure to maintain the NEMA 4, 4X rating. Provide NEMA 4 hubs at conduit entrances for equipment rated NEMA 3R to maintain a watertight seal.

C. Raceway Support and Hangers:

1. Securely fasten raceways in-place and support from ceiling or walls at spacing not exceeding:

<u>Material</u>	<u>Maximum Spacing of Supports</u>
a. ½-in. through 1-in. trade size conduit	6 ft.
b. 1¼-in. through 1½-in. trade size conduit	8 ft.
c. 2-in. to 4-in. trade size conduit	10 ft.
d. Liquid-tight, flexible metal conduit	4½ ft.
e. Metal wireway	10 ft.
2. Support rigid conduits within 3 ft. of every outlet box, junction box, pull box, cabinet, or termination. Support flexible conduit within 12 in. on each side of every outlet box or fitting.	
3. Support conduits by pipe straps, wall brackets, hangers, or ceiling trapeze. The use of perforated iron or wire for supporting conduits is prohibited. Fasten with wood screws or screw nails to wood; by toggle bolts on hollow masonry units, by concrete inserts, or expansion bolts on concrete or spring-tension or threaded C-clamps for rigid steel conduits on steel. Do not weld conduits or pipe straps to steel structures unless specifically indicated.	
4. The load applied to fasteners shall not exceed one-third the proof test load of the fasteners.	
5. Fasteners attached to concrete shall be vibration and shock-resistant.	
6. All screws, bolts, washers, and miscellaneous hardware used for conduit supports shall be fabricated from rust-resisting metal. Trapeze hangers shall have hanger assemblies protected with galvanized finish.”	

109-3.15 WIRING AND CONNECTIONS. Add the following to this section.

”High-voltage circuit wiring (airfield lighting 5000 Volt series circuits and/or other circuits rated above 600 Volts) and low-voltage circuit wiring (rated 600 Volts and below) shall maintain separation from each other. High-voltage wiring and low-voltage wiring shall not be installed in the same wireway, conduit, duct, raceway, junction box, handhole, or manhole. Where necessary provide split flexible duct around low voltage cables located in a handhole with high voltage cables, to isolate the cables from possible contact with each other.”

109-3.16 MARKING AND LABELING. Add the following to this section:

“C. Legend plates shall be provided for all equipment. Legend plates shall be provided to identify the equipment controlled, the power source, and the function of each device. Legend plates shall be weatherproof and abrasion-resistant phenolic/plastic engraved material and fastened with contact type permanent adhesive, screws, or rivets. Installation shall not break, crack, or deform the legend plate. Lettering shall be ¼ in. high, black on a white background, unless noted otherwise.

- D. Identify control wiring at each termination point and in junction/terminal boxes with wire number corresponding to the respective control wiring diagram or respective terminal numbering arrangement. Each individual control wire shall have unique identification and shall maintain that same identification from its point of origin to its final termination point. Wire markers shall be permanent pressure sensitive label with suitable numbers or letters for easy recognition. Where new control wiring is interfaced to existing control wiring it shall also match the color coding of the existing control wiring.”
- E. Each individual circuit breaker, control panel, terminal panel, safety switch, etc. shall be furnished with a phenolic-engraved legend plate that identifies the respective device, the power source, and the respective voltage, phase, and wire. Furnish additional phenolic-engraved legend plates as detailed on the Plans and/or where required by code.
- F. At electrical handholes, identify each cable originating in the vault with respect to the system or device served.
- G. Color-code phase and neutral conductor insulation for No. 6 AWG or smaller. Provide colored marking tape for phase and neutral conductors for No. 4 AWG and larger. **Insulated ground conductors shall have green colored insulation for all conductor sizes (AWG and/or KCMIL) to comply with NEC 250.119. Neutral conductors shall have white colored insulation for No. 6 AWG and smaller to meet the requirements of NEC 200.6.** Standard colors for power wiring and branch circuits shall be as follows:

208/120 VAC, 3-Phase, 4-Wire System	
Phase A	Black
Phase B	Red
Phase C	Blue
Neutral	White
Ground	Green

- J. Furnish and install weatherproof warning label for each meter socket, enclosed circuit breaker, disconnect switch, switchboard, cutout, panelboard, load center, motor control center, and control panel to warn persons of potential electric arc flash hazards, per the requirements of NEC 110.16 “Flash Protection”. Labels shall also conform to ANSI Z535.4-2002 “American National Standard for Product Safety Signs and Labels”. NEC 110.16 requires that switchboards, panelboards, industrial control panels, meter socket enclosures, and motor control centers that are likely to require examination, adjustment, servicing, or maintenance while energized shall be field marked to warn qualified persons of potential arc flash hazards. The markings shall be located so as to be clearly visible to qualified persons before examination, adjustment, servicing, or maintenance of the equipment. This new requirement is intended to help reduce the occurrence of serious injury or death due to arcing faults to those working on or near energized electrical equipment. The warning labels are to indicate to a qualified worker who intends to open the equipment for analysis of work that a serious hazard exists and that the worker should follow appropriate work practices and wear appropriate personal protective equipment (PPE) for the

specific hazard. Labels shall be as detailed on the Plans or shall include at least the following information: "Warning - Potential Arc-Flash Hazards exist while working on this energized equipment. Appropriate PPE Required.

- K. Furnish and install "DANGER – HIGH VOLTAGE" signs or labels on all fixed electrical equipment where potentials of 500 Volts or more terminal-to-ground are exposed (including, but not limited to, constant current regulators, series circuit cutout enclosures, high voltage junction boxes, and high voltage wireways) in accordance with FAA AC No. 150/5340-26C "Maintenance of Airport Visual Aid Facilities" and National Electrical Code Article 300.45 "Warning Signs". Place signs in a conspicuous location, usually on the outside of equipment."

Add the following:

109-3.19 TESTING AIRFIELD LIGHTING SYSTEMS. Cable and/or constant current regulator testing and calibration shall include the following:

- A. Follow safety procedures for all tests. Make sure each constant current regulator has a good and secured frame ground connection from the regulator housing to the respective vault ground bus and grounding electrode system, prior to operation and testing of each regulator.
- B. Prior to beginning excavations, airfield lighting modifications, cable installation, and/or any other work that might possibly affect airfield lighting circuits, all existing series circuit cables in the respective work area shall be Megger tested with an insulation resistance tester and recorded at the respective vault. All existing series circuit cable loops shall have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. Each constant current regulator shall be tested with results recorded. Contractor shall provide a True RMS Ammeter for current measurements. Copies of test results shall be provided to the Resident Engineer and the respective Project Engineer within five business days of conducting the respective set of tests. See the testing forms included in the Appendix. These tests are required to protect the Owner and the Contractor and to identify existing conditions and any defective cables, circuits, and/or constant current regulators. Failure to comply with this requirement might result in the Contractor being responsible for defective cable and circuit conditions (where previously not identified) and the associated corrective work at no additional cost to the Contract.
- C. After airfield lighting modifications, additions, and/or upgrades have been completed, series circuit cables shall be Megger tested with an insulation resistance tester and recorded at the respective vault. All series circuit cable loops shall have the resistance measured with an Ohmmeter and recorded for each circuit at the respective vault. Each constant current regulator shall be tested with results recorded. Contractor shall provide a True RMS Ammeter for current measurements. Copies of test results shall be provided to the Resident Engineer and the respective Project Engineer within five business days of conducting the respective set of tests. See the testing forms included in Appendix A.
- D. Insulation resistance testing equipment for use with 5,000 Volt series circuit cables shall use an insulation resistance tester capable of testing the cables at 5,000 Volts. Older series circuit cables and/or cables in poor condition may require the test

- voltage to be performed at a voltage lower than 5,000 Volts (Example 1,000 Volts, 500 Volts, or less than 500 Volts). The respective test voltage shall be recorded for each cable insulation resistance test result.
- E. Insulation resistance testing equipment for use with 600 Volt rated cables shall use a 500 Volt insulation resistance tester. The respective test voltage shall be recorded for each cable insulation resistance test result.
 - F. It is recommended to use the same insulation resistance test equipment throughout the project to ensure reliable comparative readings at the beginning of the project and at the completion of the project.
 - G. Disconnect the airfield lighting series circuit cables from the constant current regulator when performing cable insulation resistance tests (Megger Tests). Test the cables that go to the airfield for the respective airfield lighting series circuit. Connect the cable insulation resistance tester to one of the airfield lighting series circuit cables and to a good ground in the airport electrical vault such as the airport vault ground bus. Conduct the cable insulation resistance test on each respective cable for not less than 90 seconds. Record the test results at the end of the time duration for the test.
 - H. FAA Advisory Circular 150/5340-26C Maintenance of Airport Visual Aid Facilities provides guidance on Insulation Resistance Tests. Also refer to the user manual for the respective cable insulation resistance tester. Reasonably new series circuit cables and transformers with good connections should read 500 Mega-Ohms to 1,000 Mega-Ohms or higher. The readings should decrease with age. The resistance value declines over the service life of the circuit; a 10-20 percent decline per year may be considered normal. A yearly decline of 50 percent (4 percent monthly) or greater indicates the existence of a problem, such as a high resistance ground, serious deterioration of the circuit insulation, lightning damage, bad connections, bad splices, cable insulation damage, or other failure. FAA Advisory Circular 150/5340-26C notes "*Generally speaking, any circuit that measures less than 1 megohm is certainly destined for rapid failure.*" Airfield lighting series circuits with cable insulation readings of less than 1 megohm are not uncommon for older circuits that are 20 years or more of age.
 - I. Based on information in FAA AC No. 150/5340-26C MAINTENANCE OF AIRPORT VISUAL AID FACILITIES, the cable insulation resistance value inevitably declines over the service life of the circuit; a 10-20 percent decline per year may be considered normal. In the event that the cable insulation resistance readings have declined more than 2 percent per month it might indicate cable damage due to lightning or damage as a result of Contractor operations. Where the cable insulation resistance readings have declined more than 2 percent per month over the project construction duration as a result of Contractor operations, Contractor will need to investigate, address, and repair the respective cable circuits.
 - J. All existing series circuit cable loops shall also have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. The resistance of the series circuit loop with connections using #8 AWG copper conductor should be approximately 0.8 to 1 Ohm per thousand feet of cable length. The resistance of the series circuit loop with connections using #6 AWG copper conductor should be

approximately 0.5 to 0.7 Ohm per thousand feet of cable length. The number of series circuit transformers and connections will affect the overall resistance of the series circuit loop and therefore the measurements might be slightly higher than the calculated resistance for the respective length of cable.

- K. When test results for constant current regulators indicate readings that are outside the acceptable tolerances calibrate and adjust the regulator to be within acceptable output current levels. Adjustments and calibrations shall be in accordance with the respective regulator manufacturer recommendations and instructions. Provide a true RMS Ammeter for measuring input and output currents on constant current regulators.
- L. The respective personnel performing tests shall be familiar with the respective test equipment and the use and operation of the test equipment. The Contractor is responsible to employ the services of personnel qualified to perform the respective tests and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment. The Contractor is required to employ qualified personnel that are familiar with and capable of properly conducting the required tests and calibrations for the respective cables and equipment.
- M. See Appendix A – “Constant Current Regulator and Cable Testing Forms” for additional information on testing requirements for airfield lighting systems. All testing will be considered incidental to the respective work items and no additional compensation will be allowed.

109-3.20 GROUNDING REQUIREMENTS. Grounding shall conform to the following as applicable: The Contractor shall furnish and install all grounding shown on the Plans and/or as may be necessary or required to make a complete grounding system, as required by the latest NFPA 70 – National Electrical Code (NEC) in force. The reliability of the grounding system is dependent on careful, proper installation, and choice of materials. Improper preparation of surfaces to be joined to make an electrical path, loose joints, or corrosion can introduce impedance that will seriously impair the ability of the ground path to protect personnel and equipment and to absorb transients that can cause noise in communications circuits. The following functions are particularly important to ensure a reliable ground system:

- A. All products associated with the grounding system shall be UL-listed and labeled.
- B. All bolted or mechanical connections shall be coated with a corrosion preventative compound before joining, Sanchem Inc. “NO-OX-ID “A-Special” compound, Burndy Penetrox E, or equal.
- C. Metallic surfaces to be joined shall be prepared by the removal of all non-conductive material, per 2020 NEC Article 250-12. All copper bus bars must be cleaned prior to making connections to remove surface oxidation.
- D. Metallic raceway fittings shall be made up tight to provide a permanent low impedance path for all circuits. Metal conduit terminations in enclosures shall be bonded to the enclosure with UL-listed fittings suitable for grounding. Provide grounding bushings with bonding jumpers for all metal conduits entering service

- equipment (meter base, CT cabinet, main service breaker enclosure, etc.), generator breaker enclosures, and automatic transfer switch enclosures. Provide grounding bushings with bonding jumpers for all metal conduits entering an enclosure through concentric or eccentric knockouts that are punched or otherwise formed so as to impair the electrical connection to ground. Standard locknuts or bushings shall not be the sole means for bonding where a conduit enters an enclosure through a concentric or eccentric knockout.
- E. Furnish and install ground rods and ground rings at all locations where shown on the Plans or specified herein. Ground rods shall be 3/4-in. diameter, 10 ft. long, UL-listed, stainless steel, unless detailed otherwise on the Plans. Longer ground rods shall be required where detailed on the Plans and/or as specified herein to accommodate respective soil conditions or respective applications. Ground rods shall have 10 mil minimum copper coating. Top of ground rods shall be a minimum of 12 inches below finish grade unless otherwise noted on the Plans. Ground rods shall be spaced, as detailed on the Plans, and in no case spaced less than one-rod length apart. All connections to ground rods and/or ground rings shall be made with exothermic weld type connectors, Cadweld by Erico Products, Inc., Thermoweld by Continental Industries, Inc., Ultraweld by Harger, or approved equal. Exothermic weld connections shall be installed in conformance with the respective manufacturer's directions using molds as required for each respective application. Bolted connections will not be permitted at ground rods or at buried grounding electrode conductors. Grounding electrode conductors shall be bare copper (stranded or solid) sized, as detailed on the Plans. In addition to the grounding work described herein and shown on the Plans, the Contractor shall test the made electrode ground system with an instrument specifically designed for testing ground systems. If ground resistance exceeds **25 Ohms**, contact the Resident Engineer and the Project Engineer for further direction. Copies of ground system test results shall be furnished to the Resident Engineer and the Project Engineer.
- F. All connections located above grade, between the different types of grounding conductors shall be made using UL-listed, double-compression, crimp-type connectors or UL-listed, bolted ground connectors. For ground connections to enclosures, cases, and frames of electrical equipment not supplied with ground lugs, the Contractor shall drill required holes for mounting a bolted, ground connector. All bolted, ground connectors shall be Burndy, Dossert Corporation, ILSCO Corporation, Penn-Union Corporation, Thomas and Betts, or approved equal. Tighten connections to comply with tightening torques in UL Standard 486A to assure permanent and effective grounding.
- G. All metal equipment enclosures, conduits, cabinets, boxes, receptacles, etc. shall be bonded to the respective grounding system. Provide grounding bushings at all conduits entering service entrance equipment (meter bases, service disconnects, service panelboards, etc.) and distribution panels or load centers and ground wire from bushing to ground bus in the respective service entrance equipment or distribution panel.
- H. Each feeder circuit and/or branch circuit shall include an equipment ground wire. Metal raceway or conduit shall not meet this requirement. The equipment ground wire from equipment shall not be smaller than allowed by 2020 NEC Table 250-122 "Minimum Size Conductors or Grounding Raceway and Equipment." When conductors are adjusted in size to compensate for voltage drop, equipment-

- grounding conductors shall be adjusted proportionately according to circular mil area. All equipment ground wires shall be copper, either bare or insulated green in color. Where the equipment grounding conductors are insulated, they shall be identified by the color green, and shall be the same insulation type as the phase conductors.
- I. All utility transformer bank grounds shall be installed in accordance with the serving utility company's recommendation and in accordance with the NEC.
 - J. Bond the main electrical service neutral to ground at the main service disconnect. Bond the service neutral to ground at one location only per the NEC. A grounding connection shall not be made to any neutral circuit conductor on the load side of the service disconnecting means, except as permitted by 2020 NEC 250-24.
 - K. The secondary neutral of all transformers (separately derived system transformers) shall be grounded in accordance with the NEC. The respective grounding electrode conductor shall be connected to the neutral point of the transformer between the transformer and the output disconnecting means. Size of the grounding electrode conductor shall be in accordance with 2020 NEC Article 250-66 and Table 250-66 unless shown larger on the Drawings. A bond shall be provided between the neutral and transformer case, or other metal that is part of the AC equipment grounding system, so as to complete a circuit for fault current to the transformer winding from the AC equipment grounding system. Size of the neutral bonding conductor shall be in accordance with 2020 NEC Article 250-102.
 - L. All exterior metal conduit, where not electrically continuous because of manholes, handholes, non-metallic junction boxes, etc., shall be bonded to all other metal conduit in the respective duct run, and at each end, with a copper-bonding jumper sized in conformance with 2020 NEC 250-102. Where metal conduits terminate in an enclosure (such as a motor control center, switchboard, etc.) where there is not electrical continuity with the conduit and the respective enclosure, provide a bonding jumper from the respective enclosure ground bus to the conduit sized per 2020 NEC 250-102.
 - M. Where acceptable to the Authority of Jurisdiction, install grounding electrode conductors and/or individual ground conductors in Schedule 40 or Schedule 80 PVC conduit. Where grounding electrode conductors or individual ground conductors are run in PVC conduit, do not completely encircle conduit with ferrous and/or magnetic materials. Use non-metallic, reinforced fiberglass strut support. Where metal conduit clamps are installed, use nylon bolts, nuts, washers, and spacers to interrupt a complete metallic path from encircling the conduit.
 - N. If local codes dictate that individual grounding conductors must be run in metal conduit or raceway, then the conduit or raceway must be bonded at each end of the run with a bonding jumper sized equal to the individual grounding conductor or as required by 2020 NEC 250-102. Note: this does not apply to AC equipment ground conductors run with AC circuits. Confirm requirements with the Authority of Jurisdiction.

109-3.21 LOCKOUT/TAGOUT PROCEDURES. Lockout/Tagout Procedures shall include the following:

- A. The Contractor shall provide a copy of their electrical energy source Lockout/Tagout Procedures document to the Airport Director/Manager, Resident Engineer and the Project Engineer. The Lockout/Tagout Procedures document shall include the contact information with 24-hour phone numbers for the Contractor and the Electrical Contractor Superintendent and/or the respective licensed Journeyman Electricians on the project site.
- B. Contractor shall coordinate work and any power outages with the Airport Director/Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Director/Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- C. Where existing electrical equipment does not have features for lockout/tagout the Contractor will be responsible to provide the appropriate lockout/tagout equipment and measures to ensure the safety of personnel.
- D. Contractor shall provide a Lockout Stations suitable for wall mounting, each with 10 lockout padlocks each with a different key, 5 lockout hasps to accommodate multiple padlocks, and 100 lockout tags. Lockout station and components shall comply with OSHA Standard 1910.147. Include hardware to mount on each vault interior wall.
- E. Contractor shall comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.
- F. Compliance with Lockout/Tagout Procedures and all other safety procedures and requirements are the responsibility of the Contractor.

109-3.22 RESTORATION. Any and all trenches and disturbed areas will be backfilled and restored to a smooth grade and seeded to the satisfaction of the Resident Engineer. All trench settlement or disturbed areas shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed vault work and/or vault removal work will be incidental to the respective 109 Pay Item. The vault interior shall be cleaned to remove dust, dirt, debris, metal shavings, scrap materials, and waste materials. The Vault floor shall be swept and/or vacuumed to clean. The vault interior shall be cleaned and disinfected.

METHOD OF MEASUREMENT

109-4.3. Add the following:

“The quantity of vault equipment to be paid for under Item AR109200 “Install Electrical Equipment” shall be made on a lump sum basis wherein no measurement will be made and shall consist of furnishing and installing all electrical equipment and materials at the

vault, as detailed on the Plans and specified herein. This item shall include all labor, materials, transportation, equipment, wiring, raceways, grounding, warranties, tools, coordination, relocations, lockout/tagout procedures, operational instructions, labeling, testing, cleaning, and all incidentals required to place the vault and associated equipment into proper working order.

Cables inside or at the Airport Electrical Vault Building will be considered incidental to this item, and no additional compensation will be allowed. Conduits inside, adjacent to, interfacing to, or at the Airport Electrical Vault Building will be considered incidental to this item, and no additional compensation will be allowed. Disconnecting and removing existing designated equipment and materials will be considered incidental to this item, and no additional compensation will be allowed. Relocation of existing equipment to storage will be considered incidental to this item, and no additional compensation will be allowed.

Cleaning the vault interior will be considered incidental to this item and no additional compensation will be made.

Testing the airfield lighting systems and the associated cable tests, constant current regulator tests and calibration will be considered incidental to AR109200 "Install Electrical Equipment" and no additional compensation will be allowed. This shall include all testing prior to beginning excavations, airfield lighting modifications, cable installation, and/or any other work that might possibly affect airfield lighting circuits and all testing after airfield lighting modifications, additions, and/or upgrades have been completed. Testing of the airfield lighting systems and the associated cable tests and constant current regulator tests and calibration shall include all labor, transportation, equipment, tools, and measuring devices; all coordination with the Airport Director/Manager, Airport Staff, FAA personnel, Contractor staff, and the Resident Engineer; all recording of the test results and submission of the test results to the Resident Engineer and the Project Engineer; all calibration and adjusting of constant current regulators where test results indicate regulator output currents that are not within accepted tolerances; all retesting where test results indicate unsatisfactory conditions or incorrect testing procedures; and all other incidentals necessary to complete this item."

BASIS OF PAYMENT

Add the following:

"Payment will be made under:

Item AR109200 Install Electrical Equipment per lump sum."

END OF ITEM 109

ITEM 110 AIRPORT UNDERGROUND ELECTRICAL DUCT BANKS AND CONDUITS

DESCRIPTION

110-1.1 Add the following:

“This item of work shall consist of the installation of all proposed conduits and ducts as shown on the Construction Plans.”

110-1.2 REFERENCES. The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. ANSI C80.1 – Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 – Fittings Rigid Metal Conduit and EMT.
- C. ASTM A706 – Standard Specification for Deformed and Plain Low-Alloy Steel Bars for Concrete Reinforcement
- D. ASTM D3350 – Specification of Polyethylene Plastics Pipe and Fittings Materials.
- E. ASTM F2160 – Standard Specification for Solid Wall, High-Density Polyethylene Conduit Based on Controlled Outside Diameter.
- F. FAA AC 150/5340-30, “DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS”.
- G. FAA AC 150/5345-53, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM”.
- H. FAA STD-019f, Lightning and Surge Protection, Grounding Bonding and Shielding Requirements for Facilities and Electronic Equipment.
- I. NEMA TC-2 – Electrical Plastic Tubing and Conduit.
- J. NEMA TC-3 – Fittings Rigid PVC Conduit and Tubing.
- K. NEMA TC-7 – Smooth-Wall Coilable Polyethylene Electrical Plastic Conduit.
- L. NFPA 70 – National Electrical Code (NEC), most current issue in force.
- M. NFPA 2638645-1, National Fire Protection Association.
- N. OSHA 29 CFR Part 1910, Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.
- O. UL Standard 6 – Electrical Rigid Metal Conduit – Steel.
- P. UL Standard 514B – Conduit, Tubing and Cable Fittings.

- Q. UL Standard 514C – Nonmetallic Outlet Boxes, Flush-Device Boxes, and Covers.
- R. UL Standard 1242 – Electrical Intermediate Metal Conduit Steel.
- S. UL Standard 651 – Schedule 40 and 80 Rigid PVC Conduit.
- T. UL Standard 651A – Type EB and A Rigid PVC Conduit and HDPE Conduit.
- U. UL Standard 651B – Standard for Continuous Length High-Density Polyethylene (HDPE) Conduit.

110-1.3 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each type of conduit or duct to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** Shop drawings shall include the following information:

- A. Certification of compliance with the AIP (Airport Improvement Program) Buy American Preferences for all materials and equipment. Do not submit ARRA (American Recovery and Reinvestment Act) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Do not submit NAFTA (North American Free Trade Agreement) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Shop drawings submitted without certification of compliance with the Airport Improvement Program Buy American Preferences or without certification of manufacture in the United States of America from Domestic materials in accordance with the AIP Buy American Requirements will be rejected. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for more information on the Airport Improvement Program Buy American Preferences requirements.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. Illinois Department of Transportation Division of Aeronautics requires the following: ***“Under the FAA Buy American Preference, the contractor is required to submit certification that assures only domestic steel, domestic materials and domestic manufactured products are used. The Buy American statement must come from the producer, not the supplier. Producer verification must state that the items are produced in the United States and are made from 100% domestic materials. Statements that solely refer to the “Buy American Act” or “ARRA” or any federal purchasing act other than Title 49 United States Code (USC), Section 50101 will be rejected. Producers may use the Illinois Department of Transportation Domestic Material Compliance Certification Form AER 25 to satisfy this requirement.”***
- D. Indicate the pay item number for each respective conduit or duct.
- E. Shop drawings shall include conduit and/or duct cut sheets with type, size, specifications, UL listing, manufacturer, and catalog or part number.

- F. Provide manufacturer's literature confirming the respective duct to be bored is suitable for directional boring with the respective Shop Drawing submittal.
- G. Provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.
- H. Provide certification that the respective plastic conduits used on this project are manufactured from domestic materials.

EQUIPMENT AND MATERIALS

110-2.1 GENERAL. Add the following:

"All materials for these items shall be in accordance with the FAA Standard Specification 110 Equipment and Materials, as detailed on the Plans, and as specified herein."

110-2.2 STEEL CONDUIT. Replace this section with the following:

"Rigid Steel Conduit and fittings shall be hot-dipped, galvanized, UL-listed, and produced in accordance with UL Standard 6 – Rigid Metal Conduit and ANSI C80.1 – Rigid Steel Conduit, Zinc Coated. Couplings, connectors, and fittings for rigid steel conduit shall be threaded, galvanized steel or galvanized, malleable iron, specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 – Fittings Rigid Metal Conduit and EMT and UL 514B – Conduit, Tubing, and Cable Fittings. Set screw type fittings are not acceptable. Steel used to manufacture conduits shall be 100 percent domestic steel to comply with the Airport Improvement Program Buy American Preference Requirements and the Steel Products Procurement Act. Contractor shall provide certification that the respective steel conduits used on this project are manufactured from 100 percent domestic steel.

Miscellaneous Fittings. Fittings shall be suitable for use with conduits and ducts supplied. All fittings for use with rigid metal conduit shall be threaded. Set screw-type fittings are not acceptable. All conduit bodies, fittings, and boxes installed in classified hazardous locations (Class I, Division 1 or 2, Group D) shall be suitable for use in Class I, Division 1, and Group D locations. Fittings shall be as manufactured by Appleton, Crouse-Hinds, Hubbell-Killark, O-Z/Gedney, or approved equal.

Provide NEMA 4, 4X hubs for all conduit entries into NEMA 4, 4X equipment enclosures to maintain the NEMA 4, 4X rating of the respective enclosure. Hubs for use with NEMA 4X stainless steel enclosures shall be NEMA 4X stainless steel hubs."

110-2.3 PLASTIC CONDUIT. Add the following to the end of this section:

"Conduits shall be suitable for underground applications encased in concrete or direct burial, and suitable for exposed applications aboveground.

- C. Conduits for concrete encasement shall be Schedule 40 PVC, UL-listed, rated for 90°C cable, conforming to NEMA Standard TC-2 and UL 651, listed suitable for concrete encasement or Schedule 40 (minimum) HDPE conduit, UL-listed or ETL listed, conforming to NEMA Standard TC-7 and UL 651B and listed suitable for concrete

encasement. Conduits shall be suitable for underground applications encased in concrete or direct burial, and suitable for exposed applications aboveground.

- D. Conduits for directional boring shall be Schedule 40 PVC or Schedule 80 PVC conduit, UL-listed or ETL listed, rated for 90°C cable-conforming to NEMA Standard TC-2 and UL 651 and suitable for directional boring installation, Schedule 40 HDPE or Schedule 80 HDPE conduit, UL-listed, conforming to NEMA Standard TC-7 and UL 651B and suitable for directional boring installation, or Wall Type SDR 11 (minimum) HDPE conduit manufactured in accordance with ASTM D-3350 (Specification of Polyethylene Plastics Pipe and Fittings Materials) and ASTM F2160 (Standard Specification for Solid Wall, High-Density Polyethylene Conduit Based on Controlled Outside Diameter), and suitable for directional boring installation. **Per NEC 300.5 (K), raceways installed using directional boring equipment shall be approved for the purpose. Provide manufacturer's literature confirming the respective duct is suitable for directional boring with the respective Shop Drawing submittal.**
- E. Conduits for direct burial in earth shall be PVC Schedule 40 (minimum wall thickness), UL-listed, rated for 90°C cable-conforming to NEMA Standard TC-2 and UL 651, listed suitable for direct burial in earth, or HDPE Schedule 40 (minimum wall thickness), conforming to NEMA Standard TC-7 and UL 651B, or HDPE SDR 13.5 (minimum wall thickness) manufactured in accordance with ASTM D-3350 (Specification of Polyethylene Plastics Pipe and Fittings Materials) and ASTM F2160 (Standard Specification for Solid Wall, High-Density Polyethylene Conduit Based on Controlled Outside Diameter). Conduits shall be suitable for direct burial in earth and/or concrete encasement.
- F. Conduit for Item AR110202; 2" PVC Conduit, Direct Bury shall be Schedule 40 PVC (minimum), UL-listed or ETL listed, rated for 90°C cable, conforming to NEMA Standard TC-2 and UL 651 or Schedule 40 (minimum) HDPE, UL-listed, conforming to NEMA Standard TC-7 and UL 651B. Conduits shall be suitable for underground applications direct burial in earth or concrete."

CONSTRUCTION METHODS

110-3.1 GENERAL. Add to this section:

"The proposed conduits and ducts shall be constructed at the locations and in accordance with the details shown on the Construction Plans. Ducts shall be installed 18 in. minimum below grade. Ducts located in area subject to farming shall be 42 in minimum below grade. Where detailed on the Plans or where required to avoid obstructions, ducts shall be buried deeper. Where concrete-encased duct interfaces to directional-bored duct at a pavement crossing, the concrete encasement shall be installed up to the respective pavement edge. Where concrete-encased duct interfaces to an electrical handhole or manhole, the concrete encasement shall be installed up to the respective handhole or manhole. Provide bushings or bells at conduit terminations in electrical handholes or manholes.

Underground ducts installed by directional-boring method shall be installed in a manner that will not damage any existing underground utilities, and shall not disturb or damage

the respective pavement or roadway surface. Ducts shall be directional bored at the locations shown on the Construction Plans. The ducts will be bored at a minimum depth of 24 in. below the bottom of the pavement it is being bored under. Ducts installed under paved areas and roadways shall extend a minimum of 10 feet beyond the respective pavement or roadway surface, unless detailed otherwise on the Plans. A pull wire will be left in the conduit if it is to be left vacant. The ends of the conduit will be sealed with approved plugs.

The Contractor will determine if there is a conflict between the installation of the proposed electrical ducts and any existing/proposed utilities. He will make all necessary adjustments in depth of installation to avoid any and all existing/proposed underground improvements.

Provide conduit bushings or bells at duct terminations in handholes and manholes.”

110-3.7 RESTORATION. Add to this section:

“Any and all trenches and disturbed areas will be backfilled and restored to a smooth grade and seeded to the satisfaction of the Resident Engineer/Resident Technician. All trench settlement shall be corrected for a period of one year. Restoration, grading, and seeding of areas disturbed during the installation of the proposed ducts will be incidental to the respective pay item for which the duct is installed and shall be in accordance with Item 901 Seeding and Item 908 Mulching.

Any and all disturbed pavement areas will be restored to original or better condition. Restoration of pavement areas disturbed during the installation of the proposed ducts will be incidental to the respective pay item for which the duct is installed. The restoration of concrete pavement will be completed in accordance with Item 610 for sidewalks and concrete pavement but will be incidental to the respective pay item for which the duct is installed.”

Add the following:

110-3.8 LOCATING OF EXISTING UNDERGROUND UTILITIES AND CABLES. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatsoever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor’s responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain from the respective utility companies detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner’s Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract.

All utility cables and lines shall be located by the respective utility. **Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123.** Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

Contractor shall locate and mark all existing cables within ten (10) feet of proposed excavating/trenching area. Any cables found interfering with proposed excavation or cable/trenching shall be hand dug and exposed. Any damaged cables shall be immediately repaired to the satisfaction of the Resident Engineer at the Contractor's expense. The Resident Engineer and Owner shall be notified immediately if any cables are damaged.

Due to the quantities of existing utilities and lines in the proposed areas of work, the Contractor will need to carefully excavate to expose and protect these utilities and lines prior to installing manholes, handholes, and/or junction structures and the associated trenches for the proposed conduits, ducts, and raceway system.

Payment for locating and marking underground utilities and cables will not be paid for separately but shall be considered incidental to the respective duct installation.

110-3.9 SEPARATION OF HIGH-VOLTAGE AND LOW-VOLTAGE WIRING. High-voltage circuit wiring (airfield lighting 5000 Volt series circuits and/or other circuits rated above 600 Volts) and low-voltage circuit wiring (rated 600 Volts and below) shall maintain separation from each other. High-voltage wiring and low-voltage wiring shall not be installed in the same wireway, conduit, duct, raceway, handhole, or junction box.

METHOD OF MEASUREMENT

110-4.1 Add the following:

"All restoration work associated with installation of ducts and conduits will be considered incidental to the respective item for which they are installed, and no additional measurement will be made. Removal and replacement of bituminous pavement or concrete pavement will be considered incidental to the respective pay item for which the duct is installed. All duct and conduit interface to manholes, handholes, junction structures, or pull boxes including coring of manholes, handholes, junction structures, or pull boxes will be considered incidental to the respective item for which they are installed, and no additional measurement will be made. Conduits, conduit nipples, conduit couplings, and other conduit fittings included with splice cans, junction structures, Navaid installations, base mounted airfield light fixtures, airfield signs, and/or taxi signs, will be considered incidental to the respective item for which they are installed, and no additional measurement will be made."

110-4.2 Delete this section.

BASIS OF PAYMENT

110-5.1. Add the following:

“Payment will be made at the contract unit price per each type and size of conduit, completed and accepted. This price shall be full compensation for furnishing all materials and for all preparation, assembly, and installation of these materials; for all sawing and pavement removal; for all duct interface work to handholes/manholes including coring of handholes/manholes; for all excavation and backfilling with aggregate backfill, earth backfill, and concrete; and for all labor, coordination, equipment, tools, and incidentals necessary to complete this Item. Removal and replacement of bituminous pavement or concrete pavement will be considered incidental to the respective pay item for which the duct is installed.

Payment will be made under:

Item AR110012	2” Directional Bore - per linear foot
Item AR110202	2” PVC Duct, Direct Bury - per linear foot”

END OF ITEM 110

ITEM 115 ELECTRICAL MANHOLES AND JUNCTION STRUCTURES

DESCRIPTION

115-1.1. This item of work shall consist of electrical manholes and junction structures (handholes and splice cans) in accordance with this Specification and as detailed on the Construction Plans. This item shall include the installation of each electrical manhole and/or junction structures with all associated excavation, backfilling, sheeting and bracing, concrete, reinforcing steel, ladders, appurtenances, testing, dewatering and restoration of surfaces to the satisfaction of the Resident Engineer/Resident Technician.

115-1.2 REFERENCES. The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. ASTM A123, Standard Specification for Zinc (Hot Dip Galvanized) Coatings on Iron and Steel Products.
- B. ASTM A283, Standard Specification for Low and Intermediate Tensile Strength Carbon Steel Plates.
- C. ASTM A615, Standard Specification for Deformed and Plain Carbon-Steel Bars for Concrete Reinforcement.
- D. AASHTO M 85, Standard Specification for Portland Cement.
- E. ANSI/IEEE STD 81, IEEE Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System.
- F. Federal Specification A-A 59544, Cable and Wire, Electrical (Power, Fixed Installation).
- G. FAA AC 150/5345-7, "SPECIFICATION FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS".
- H. FAA AC 150/5345-26, "SPECIFICATION FOR L-823 PLUG AND RECEPTACLE, CABLE CONNECTORS".
- I. FAA AC 150/5345-42, "SPECIFICATION FOR AIRPORT LIGHT BASES, TRANSFORMER HOUSINGS, JUNCTION BOXES, AND ACCESSORIES".
- J. FAA AC 150/5340-30, "DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS".
- K. FAA AC 150/5345-53, "AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM".
- L. MIL-P-21035, Paint High Zinc Dust Content, Galvanizing Repair.
- M. NFPA-70, National Electrical Code (NEC), most current issue in force.

115-1.3 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each type of electrical handhole/manhole and junction structure to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** The preferred shop drawing submittal format shall be electronic (PDF) copies. Shop drawings shall include the following information:

- A. Certification of compliance with the AIP (Airport Improvement Program) Buy American Preferences for all materials and equipment. Do not submit ARRA (American Recovery and Reinvestment Act) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Do not submit NAFTA (North American Free Trade Agreement) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Shop drawings submitted without certification of compliance with the Airport Improvement Program Buy American Preferences or without certification of manufacture in the United States of America in accordance with the AIP Buy American Requirements will be rejected. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for more information on the AIP Buy American Preferences requirements.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.
- C. The data submitted shall be sufficient, in the opinion of the Engineer, to determine compliance with the plans and specifications. The Engineer reserves the right to reject any and all equipment, materials or procedures that do not meet the system design and the standards and codes, specified in this document.
- D. Precast concrete handholes and manholes must be on IDOT (Illinois Department of Transportation) List of Certified Precast Concrete Producers. Provide information on respective precast concrete producer for precast manholes and drawings for respective handholes.
- E. Provide cut sheets with part number and specifications for each FAA L-867 junction structure/splice can.
- F. Provide certification that the respective pre-cast handholes and manholes are manufactured in the United States of America.

MATERIALS

115-2.1. GENERAL

- A. All equipment and materials covered by referenced specifications shall be subject to acceptance through manufacturer's certification of compliance with the applicable specification when so requested by the Engineer.
- B. Manufacturer's certifications shall not relieve the Contractor of the Contractor's responsibility to provide materials in accordance with these specifications and acceptable to the Engineer.

Materials supplied and/or installed that do not materially comply with these specifications shall be removed, when directed by the Engineer and replaced with materials, which do comply with these specifications, at the sole cost of the Contractor.

- C. All equipment and materials furnished and installed under this section shall be guaranteed against defects in materials and workmanship for a period of at least twelve (12) months from the date of final acceptance by the Owner. The defective materials and/or equipment shall be repaired or replaced, at the Owner's discretion, with no additional cost to the Owner.

115-2.2 CONCRETE STRUCTURES. Provide precast concrete structures where shown on the Plans. Precast units shall have mortar or bitumastic sealer placed between all joints to make them watertight. Openings or knockouts shall be provided in the structure as detailed on the Plans and as applicable to interface to the respective duct system. Threaded inserts and pulling eyes shall be cast in as shown.

If the Contractor chooses to propose a different structural design, signed and sealed shop drawings, design calculations, and other information requested by the Engineer shall be submitted by the Contractor to allow for a full evaluation by the Engineer.

- A. Electrical Handholes. Each electrical handhole shall be constructed in accordance with the details as shown on the Construction Plans. The handholes shall be provided with extra heavy duty frame and lid suitable for 100,000 pound loading, with spring assist hatch, hinged with hold open safety device, Neenah Foundry Company R-3498-P2S Spring-Assist Hatch, East Jordan Iron Works 8096 Spring-Assist Hatch, or an approved equal. Lids for the handholes containing high voltage airfield lighting cables shall include lettering labeled "**DANGER HIGH VOLTAGE KEEP OUT 5000 VOLTS**" to comply with NEC Article 300.45 "Warning Signs" and NEC Article 314.30(D) "Covers". Lids for the handholes containing low voltage cables (600 Volts and below) shall include lettering labeled "**LOW-VOLTAGE**". Coordinate lettering with manufacturer. Precast electrical handholes shall be manufactured by a concrete electrical handhole producer on the Illinois Department of Transportation approved list of certified precast concrete producers. Electrical handholes will be paid for under Item AR115610 Electrical Handhole per each.

115-2.3 JUNCTION BOXES. Junction structures for Item AR125565 Splice Can shall be FAA Type L-867 (non-load bearing) Class IA, Size D; 16-inch diameter, 24 inches deep, with minimum 3/8-inch thick galvanized steel cover and stainless steel bolts. Refer to the Plans for the number, size, and quantity of conduit hubs for each respective splice/junction can. Covers for splice cans containing high voltage airfield lighting cables shall include minimum 1/2-inch high lettering labeled "DANGER HIGH VOLTAGE KEEP OUT" to comply with National Electrical Code Article 300.45 "Warning Signs" and National Electrical Code Article 314.71(E) "Suitable Covers". This will need to be coordinated with the splice can manufacturer. Lids for splice cans containing low voltage cables (rated 600 Volts and below) will be acceptable to use blank covers.

115-2.4 GROUND RODS. Ground rods for use with junction structures/splice cans shall be minimum 3/4-inch diameter by 10 feet long UL listed copper-clad steel. Ground rod for junction structures/splice cans shall be tested. Where ground resistance exceeds 25 Ohms furnish and install and second ground rod not less than one rod length apart and connect to the first ground rods at the junction structure/splice can.

CONSTRUCTION METHODS

115-3.1. Electrical handholes and manholes shall be constructed in accordance with the details as shown on the Construction Plans. At electrical handholes and manholes, identify and label each cable with respect to its origin and the system or device served. Coordinate conduit and duct interface with the handhole and/or manhole installation. Field cut openings for conduits and ducts according to the respective handhole and/or manhole manufacturer's recommendations. Core drill and/or cut wall of handhole and/or manhole with a tool designed for the material to be cut and suitable for the respective application. Size holes for termination fittings to be used and seal around penetrations after fittings are installed.

115-3.2 UNCLASSIFIED EXCAVATION. It is the Contractor's responsibility to locate existing utilities within the work area prior to excavation. Damage to utility lines, through lack of care in excavating, shall be repaired or replaced to the satisfaction of the Resident Engineer/Resident Technician without additional expense to the Owner.

The Contractor shall perform excavation for structures and structure footings. The excavation shall be of sufficient size to permit the placing of the full width and length of the structure or structure footings shown.

All excavation shall be unclassified and shall be considered incidental to the respective handhole and/or manhole structure pay item of which it is a component part. Dewatering necessary for manhole structure installation, erosion and turbidity control, in accordance with Federal, State, and Local requirements is incidental to its respective pay item. The cost of all excavation regardless of type of material encountered, shall be included in the unit price bid for the respective manhole structure pay item.

Boulders, logs and all other objectionable material encountered in excavation shall be removed. All rock and other hard foundation material shall be cleaned of all loose material and cut to a firm surface either level, stepped or serrated, as directed by the Resident Engineer/Resident Technician. All seams, crevices, disintegrated rock and thin strata shall be removed. When concrete is to rest on a surface other than rock, special care shall be taken not to disturb the bottom of the excavation. Excavation to final grade shall not be made until just before the concrete or reinforcing is to be placed.

The Contractor shall provide all bracing, sheeting and shoring necessary to implement and protect the excavation and the structure as required for safety or conformance to governing laws. The cost of bracing, sheeting and shoring shall be included in the unit price bid for the structure.

Unless otherwise provided, bracing, sheeting and shoring involved in the construction of this item shall be removed by the Contractor after the completion of the structure. Removal shall be effected in a manner that will not disturb or mar finished masonry. The cost of removal shall be included in the unit price bid for the structure.

After each excavation is completed, the Contractor shall notify the Resident Engineer/Resident Technician. Structures shall be placed after the Resident Engineer/Resident Technician has approved the depth of the excavation and the suitability of the foundation material.

Prior to installation the Contractor shall provide a minimum of 6 in of sand or a material approved by the Resident Engineer/Resident Technician as a suitable base to receive the

structure. The base material shall be compacted and graded level and at proper elevation to receive the structure in proper relation to the conduit grade or ground cover requirements, as indicated on the Plans.

115-3.2 CONCRETE STRUCTURES. Concrete structures shall be built on prepared foundations conforming to the dimensions and form indicated on the plans. The concrete and construction methods shall conform to the requirements specified in Item 610. Any reinforcement required shall be placed as indicated on the plans and shall be approved by the Engineer before the concrete is placed.

115-3.3 PRECAST UNIT INSTALLATIONS. Precast units shall be installed plumb and true. Joints shall be made watertight by use of sealant at each tongue-and-groove joint and at roof of manhole. Excess sealant shall be removed and severe surface projections on exterior of neck shall be removed.

115-3.4 PLACEMENT AND TREATMENT OF CASTINGS, FRAMES AND FITTINGS. All castings, frames and fittings shall be placed in the positions indicated on the Plans or as directed by the Resident Engineer/Resident Technician and shall be set true to line and to correct elevation. If frames or fittings are to be set in concrete or cement mortar, all anchors or bolts shall be in place and position before the concrete or mortar is placed. The unit shall not be disturbed until the mortar or concrete has set.

Field connections shall be made with bolts, unless indicated otherwise. Welding will not be permitted unless shown otherwise on the approved shop drawings and written permission is granted by the casting manufacturer. Erection equipment shall be suitable and safe for the workman. Errors in shop fabrication or deformation resulting from handling and transportation that prevent the proper assembly and fitting of parts shall be reported immediately to the Resident Engineer/Resident Technician and approval of the method of correction shall be obtained. Approved corrections shall be made at Contractor's expense.

Anchor bolts and anchors shall be properly located and built into connection work. Bolts and anchors shall be preset by the use of templates or such other methods as may be required to locate the anchors and anchor bolts accurately.

Pulling-in irons shall be located opposite all conduit entrances into structures to provide a strong, convenient attachment for pulling-in blocks when installing cables. Pulling-in irons shall be set directly into the concrete walls of the structure.

115-3.5 INSTALLATION OF LADDERS. [Not used]

115-3.6 REMOVAL OF SHEETING AND BRACING. In general, all sheeting and bracing used to support the sides of trenches or other open excavations shall be withdrawn as the trenches or other open excavations are being refilled. That portion of the sheeting extending below the top of a structure shall be withdrawn, unless otherwise directed, before more than 6 inches (150 mm) of material is placed above the top of the structure and before any bracing is removed. Voids left by the sheeting shall be carefully refilled with selected material and rammed tight with tools especially adapted for the purpose or otherwise as may be approved.

The Resident Engineer/Resident Technician may order the Contractor to delay the removal of sheeting and bracing if, in his judgment, the installed work has not attained the necessary strength to permit placing of backfill.

115-3.7 BACKFILLING. After a structure has been completed, the area around it shall be backfilled in horizontal layers not to exceed 6 inches (150 mm) in thickness. Each layer shall be deposited all around the structure to approximately the same elevation. The top of the fill shall meet the elevation shown on the plans or as directed by the Resident Engineer/Resident Technician.

Backfill shall not be placed against any structure until permission is given by the Resident Engineer/Resident Technician. In the case of concrete, such permission shall not be given until tests made by the laboratory under supervision of the Engineer establish that the concrete has attained sufficient strength to provide a factor of safety against damage or strain in withstanding any pressure created by the backfill or the methods used in placing it.

Where required, the Resident Engineer/Resident Technician may direct the Contractor to add, at his own expense, sufficient water during compaction to assure a complete consolidation of the backfill. The Contractor shall be responsible for all damage or injury done to conduits, duct banks, structures, property or persons due to improper placing or compacting of backfill.

115-3.8 CONNECTION OF DUCT BANKS. To relieve stress of joint between concrete-encased duct banks and structure walls, reinforcement rods shall be placed in the structure wall and shall be formed and tied into duct bank reinforcement at the time the duct bank is installed.

115-3.9 RESTORATION. After the backfill is completed, the Contractor shall dispose of all surplus material, dirt and rubbish from the site. The Contractor shall restore all disturbed areas equivalent to or better than their original condition. All sodding, seeding, mulching grading and restoration shall be considered incidental to the respective pay item and shall be in accordance with Item 901 Seeding and Item 908 Mulching. The Contractor shall grade around structures as required to provide positive drainage away from the structure. Areas with special surface treatment, such as roads, sidewalks, or other paved areas shall have backfill compacted to match surrounding areas, and surfaces shall be repaired using materials comparable to original materials. After all work is completed, the Contractor shall remove all tools and other equipment, leaving the entire site free, clear and in good condition.

115-3.10 LOCATING EXISTING UNDERGROUND UTILITIES AND CABLES. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatsoever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans and shall obtain from the respective utility companies detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract.

All utility cables and lines shall be located by the respective utility. **Contact JULIE (Joint Utility Location Information for Excavators) for utility information, phone: 1-800-892-0123.** Contact the FAA (Federal Aviation Administration) for assistance in locating FAA cables and utilities. Location of FAA power, control, and communication cables shall be coordinated with and/or located by the FAA. Also contact Airport Director/Manager and Airport Personnel for assistance in locating underground Airport cables and/or utilities. Also coordinate work with all aboveground utilities.

Contractor shall locate and mark all existing cables within ten (10) feet of proposed excavating/trenching area. Any cables found interfering with proposed excavation or cable/trenching shall be hand dug and exposed. Any damaged cables shall be immediately repaired to the satisfaction of the Resident Engineer at the Contractor's expense. The Resident Engineer and Owner shall be notified immediately if any cables are damaged.

Due to the quantities of existing utilities and lines in the proposed areas of work, the Contractor will need to carefully excavate to expose and protect these utilities and lines prior to installing manholes, handholes, and/or junction structures and the associated trenches for the proposed conduits, ducts, and raceway system.

Contractor is responsible for the repairs of any utilities, lines, and/or cables damaged as a result of his operations.

Payment for locating and marking underground utilities and cables will not be paid for separately, but shall be considered incidental to the respective duct installation.

115-3.11 SEPARATION OF HIGH-VOLTAGE AND LOW-VOLTAGE WIRING. High-voltage circuit wiring (airfield lighting 5000 Volt series circuits and/or other circuits rated above 600 Volts) and low-voltage circuit wiring (rated 600 Volts and below) shall maintain separation from each other. High-voltage wiring and low-voltage wiring shall not be installed in the same wireway, conduit, duct, raceway, handhole, or junction box.

METHOD OF MEASUREMENT

115-4.1. Electrical manholes, handholes and junction structures shall be measured by each unit completed in place and accepted by the Resident Engineer/Technician. The following additional items are specifically included in each unit.

- All required excavation,
- Sheeting and bracing
- All required backfilling with on-site materials
- Restoration of all surfaces and finished grading, sodding
- All required connections
- Conduits, conduit nipples, conduit couplings, and other conduit fittings included with junction structures, and/or splice cans
- Slack cable required to perform cable splices outside of the respective junction structures, handholes, or manholes.
- Dewatering if required
- Temporary cables and connections
- Ground rods, grounding electrode conductors, connections, and associated grounding work included with junction structures, and/or splice cans
- Ground rod testing

- All coring and labor associated with conduit, duct, cable in unit duct, and/or cable entries
- Locating existing utilities, lines, and cables in the respective areas of work
- All coordination with the respective Airport staff, site personnel, and/or FAA personnel

BASIS OF PAYMENT

115-5.1. Payment will be made at the contract unit price bid for each electrical manhole, handhole, and/or junction structure completed and in place. This price shall be full compensation for furnishing all materials and for all preparation, excavation, backfilling, and placing of the materials; for locating existing utilities, lines, and cables in the respective areas of work; for all coring and labor associated with conduit, duct, cable in unit duct, and/or cable entries; for all coordination with the respective Airport and/or FAA personnel; for furnishing and installation of appurtenances and connections to duct banks and other structures as may be required to complete the item as shown on the plans and for all labor, equipment, tools and incidentals necessary to complete the structure.

Payment will be made under:

Item AR125565 Splice Can - per each

END OF ITEM 115

ITEM 125 INSTALLATION OF AIRPORT LIGHTING SYSTEMS

DESCRIPTION

125-1.1. Add the following:

“This Item of work shall consist of furnishing and installing base- and stake-mounted airfield lights, taxiway lights, taxi guidance signs, and splice cans at the locations shown on the Construction Plans and in accordance with the details shown on the Plans. This Item of work shall also include the removal of base- and stake-mounted runway lights, taxiway lights and/or taxi guidance signs. Also included in this Item will be the testing of the installation and all incidentals necessary to place the lighting systems into operation, completed, and to the satisfaction of the Resident Engineer/Technician.”

125-1.6 REFERENCES. The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. ANSI C80.1 – Rigid Steel Conduit, Zinc Coated.
- B. ANSI C80.4 – Fittings Rigid Metal Conduit and EMT.
- C. FAA AC 150/5340-18, “STANDARDS FOR AIRPORT SIGN SYSTEMS”.
- D. FAA AC 150/5340-26, “MAINTENANCE OF AIRPORT VISUAL AID FACILITIES”.
- E. FAA AC 150/5340-30, “DESIGN AND INSTALLATION DETAILS FOR AIRPORT VISUAL AIDS”.
- F. FAA AC 150/5345-7, “SPECIFICATION FOR L-824 UNDERGROUND ELECTRICAL CABLE FOR AIRPORT LIGHTING CIRCUITS”.
- G. FAA AC 150/5345-26, “SPECIFICATION FOR L-823 PLUG AND RECEPTACLE, CABLE CONNECTORS”.
- H. FAA AC 150/5345-42, “SPECIFICATION FOR AIRPORT LIGHT BASES, TRANSFORMER HOUSINGS, JUNCTION BOXES, AND ACCESSORIES”.
- I. FAA AC 150/5345-47, “SPECIFICATION FOR SERIES TO SERIES ISOLATION TRANSFORMERS FOR AIRPORT LIGHTING SYSTEMS”.
- J. FAA AC No. 150/5345-51 (current issue in effect) “SPECIFICATION FOR DISCHARGE-TYPE FLASHING LIGHT EQUIPMENT”.
- K. FAA AC 150/5345-53, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM” and FAA AC 150/5345-53D, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum”.
- L. FAA AC 150/5370-2, “OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION.

- M. FAA Order 5100.38D Airport Improvement Program Handbook
- N. FAA Order JO 6850.2B Visual Guidance Lighting Systems
- O. FAA STD-019f, Lightning and Surge Protection, Grounding Bonding and Shielding Requirements for Facilities and Electronic Equipment.
- P. NFPA 70 – National Electrical Code (most current issue in force).
- Q. NFPA 70E – Standard for Electrical Safety in the Workplace.
- R. OSHA 29 CFR Part 1910, Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.
- S. UL Standard 6 – Electrical Rigid Metal Conduit – Steel.
- T. UL Standard 514B – Conduit, Tubing and Cable Fittings.

EQUIPMENT AND MATERIALS

125-1.7 SHOP DRAWINGS. The Contractor shall furnish shop drawings for approval before ordering equipment and/or materials. Shop drawings are required for each type of electrical handhole/manhole and junction structure to be used on the project. **Shop drawings shall be clear and legible. Copies that are illegible will be rejected.** The preferred shop drawing submittal format shall be electronic (PDF) copies. Shop drawings shall include the following information:

- A. Certification of compliance with the AIP (Airport Improvement Program) Buy American Preferences for all materials and equipment. Do not submit ARRA (American Recovery and Reinvestment Act) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Do not submit NAFTA (North American Free Trade Agreement) certification as a substitute for certification of compliance with the AIP Buy American Preferences. Shop drawings submitted without certification of compliance with the Airport Improvement Program Buy American Preferences or without certification of manufacture in the United States of America in accordance with the AIP Buy American Requirements will be rejected. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for more information on the AIP Buy American Preferences requirements. FAA approved equipment that is on the FAA Buy American Conformance List or the list of Nationwide Buy American Waivers Issued by the FAA complies with the AIP Buy American Preferences and will not require additional waiver paperwork for AIP projects. See the FAA website at: http://www.faa.gov/airports/aip/buy_american/ for a list of Nationwide Buy American Waivers Issued by the FAA.
- B. In order to expedite the shop drawing review, inspection and/or testing of materials and equipment, the Contractor shall furnish complete statements to the Project Engineer as to the origin and manufacturer of all materials and equipment to be used in the work. Such statements shall be furnished promptly after execution of the contract but, in all cases, prior to delivery of such materials and equipment.

- C. Illinois Department of Transportation Division of Aeronautics requires the following: ***“Under the FAA Buy American Preference, the contractor is required to submit certification that assures only domestic steel, domestic materials and domestic manufactured products are used. The Buy American statement must come from the producer, not the supplier. Producer verification must state that the items are produced in the United States and are made from 100% domestic materials. Statements that solely refer to the “Buy American Act” or “ARRA” or any federal purchasing act other than Title 49 United States Code (USC), Section 50101 will be rejected. Producers may use the Illinois Department of Transportation Domestic Material Compliance Certification Form AER 25 to satisfy this requirement.”***
- D. Cut sheets with part number and specifications for ODALS. Include cut sheets with part numbers and dimensions for base cans, base plates, transformers, and associated components for ODALS.
- E. Cut sheets for conduits associated with the ODALS installation. Include certification that steel conduits are made with 100 percent domestic steel.
- F. Cut sheets for power and control cables associated with the ODALS installation.
- G. Concrete mix design.
- H. Provide cut sheets with manufacturer’s name, catalog number, dimensions, material and UL listing for each type and size ground rod. Include certification of 100% domestic steel for ground rods. Include cut sheets for exothermic weld connections, ground lugs, and ground wire.

EQUIPMENT AND MATERIALS

125-2.1 GENERAL. Add the following to this section:

- “D. The concrete used in the construction of these Items shall be in accordance with Item 610.”

125-2.4 CONDUIT. Add the following to this section:

“Rigid Steel Conduit and fittings shall be hot-dipped, galvanized, UL-listed, produced in accordance with UL Standard 6 – Rigid Metal Conduit and ANSI C80.1 – Rigid Steel Conduit, Zinc Coated. Couplings, connectors, and fittings for rigid steel conduit shall be threaded galvanized steel or galvanized malleable iron specifically designed and manufactured for the purpose. Fittings shall conform to ANSI C80.4 – Fittings Rigid Metal Conduit and EMT. Set screw type fittings are not acceptable. Galvanized rigid steel conduit shall be manufactured in the United States of America produced from 100 percent domestic steel.

Plastic conduits shall conform to the requirements of Item 110 and as detailed on the Plans.”

125-2.7 ISOLATION TRANSFORMERS. Add the following to this section:

“Series circuit isolation transformers for the ODALS, runway edge lights, and/or other airfield Nav aids or lighting devices shall be manufactured to FAA Specification AC 150/5345-47 (current edition in effect) and shall be FAA-approved (ETL-Certified). Series circuit transformer shall be properly sized for the respective runway or taxiway edge lights, and/or other airfield Nav aids or lighting devices and shall be as recommended by the respective ODALS manufacturer, respective Nav aid manufacturer, and/or respective airfield lighting device manufacturer. Confirm proper transformer selection and sizing with the respective equipment manufacturer.”

125-2.8 LIGHT CANS. Add the following to this section:

“Each light base can and/or splice can shall include internal and external ground lugs. Cans shall be the size and depth as detailed on the Plans. L-867 splice cans shall have galvanized steel covers, 3/8 in. thick, with stainless steel bolts. Lids for splice cans containing high voltage airfield lighting cables shall include minimum 1/2-inch high lettering labeled “DANGER HIGH VOLTAGE KEEP OUT” to comply with National Electrical Code Article 300.45 “Warning Signs” and National Electrical Code Article 314.71(E) “Suitable Covers”. This will need to be coordinated with the splice can manufacturer. Lids for splice cans containing low voltage cables (rated 600 Volts and below) will be acceptable to use blank covers. Provide compatible base covers for mounting the respective light fixtures.”

Add the following:

125-2.14 ODALS. ODALS (Omni-Directional Approach Lighting System) shall be FAA approved conforming to FAA AC No. 150/5345-51 (current issue in effect) “SPECIFICATION FOR DISCHARGE-TYPE FLASHING LIGHT EQUIPMENT”, FAA Type L-859V; ODALS powered by Airport Voltage Power Source), Style F; Omni-directional three brightness steps. ODALS shall be FAA approved and listed in FAA AC 150/5345-53D, “AIRPORT LIGHTING EQUIPMENT CERTIFICATION PROGRAM Appendix 3 Addendum. Include surge protectors for each ODALS unit in accordance with the respective ODALS manufacturer recommendations.

125-2.15 POWER AND CONTROL CABLES FOR ODALS. Power and control cables for ODALS shall be in accordance with ITEM 108, as detailed on the Plans, and per the requirements of the respective ODALS manufacturer instructions and recommendations.

125-2.16 ANTI-SEIZE COMPOUND. Prior to installing the proposed airfield lights, the Contractor will apply an oxide-inhibiting, anti-seizing compound to all screws, nuts, breakable coupling, and all places where metal comes into contact with metal.

125-2.17 STAINLESS STEEL BOLTS. All base plate-mounting bolts and stake-mounting bolts shall be stainless steel.

125-2.18 GROUND RODS. Ground rods shall be 3/4-inch diameter by 10-foot long sectional UL listed Copper clad with 10 mils (minimum) Copper coating. **Due to the sandy soil conditions at the project site ground rods for the ODALS units shall be 3/4-inch diameter by 30-foot long (three 3/4-inch by 10 foot long ground rods coupled together to form a ground rod 30 feet in length.** Ground rods shall be manufactured in the United States of

America from 100 percent domestic steel to comply with the requirements of the Airport Improvement Program Buy American Preferences requirements and the Steel Products Procurement Act.

125-2.19 SPARE PARTS. Spare parts for airport visual aids are allowable in accordance with the requirements of FAA Order 5100.38D "Airport Improvement Program Handbook" and the guidelines in FAA AC No. 150/5340-26C "Maintenance of Airport Visual Aid Facilities". Provide the following spare parts for the airport visual aid/airfield lighting system:

1. One Circuit board for the ODALS primary power and control unit timing and control system.
2. One Circuit board for use in each of the secondary ODALS units power and control system.

Spare parts for the airport visual aid/airfield lighting system will be considered incidental to the respective airfield lighting system pay items and no additional compensation will be allowed.

CONSTRUCTION METHODS

125-3.1 GENERAL. Add the following to this section:

"The Contractor shall furnish and install all equipment and electrical materials necessary for complete and operational installation of the airfield lighting systems as shown on the Plans and detailed herein. The complete installation and wiring shall be done in a neat, workmanlike manner. All electrical work shall comply with the requirements of the NFPA 70 - National Electrical Code (NEC) most current issue in force and the applicable Federal Aviation Administration standards, orders, and advisory circulars. Equipment and materials shall be installed in conformance with the respective manufacturer's directions and recommendations for the respective application. Any installations which void the UL listing, Intertek Testing Services verification/ETL listing, (or other third party listing), and/or the manufacturer's warranty of a device will not be permitted.

- A. Keep all work, power outages, and/or shut down of existing systems coordinated with the Airport Director/Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Director/Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- B. Examine the site to determine the extent of the work. Contractor shall field verify existing site conditions.
- C. Verify respective circuits and power sources prior to removing, disconnecting, relocating, installing, connecting, or working on the respective ODALS, airfield lighting, taxi sign, NAVAID, or other device. Identify each respective circuit prior to performing work on that circuit.

- D. Install ODALS and other airfield lighting devices in accordance with the details shown on the Construction Plans.
- E. New power and control cable shall be furnished and installed in conduit and duct for the ODALS. Power wiring shall be installed in conduits separate from control wiring. The feeder circuit from the vault to the ODALS site will be paid from under Item 108. The power and control cables between the ODALS units and associated equipment will be considered incidental to the ODALS
- F. Locate existing underground utilities, cables and lines. The location, size, and type of material of existing underground and/or aboveground utilities indicated on the Plans are not represented as being accurate, sufficient, or complete. Neither the Owner nor the Engineer assumes any responsibility whatsoever in respect to the accuracy, completeness, or sufficiency of the information. There is no guarantee, either expressed or implied, that the locations, size, and type of material of existing underground utilities indicated are representative of those to be encountered in the construction. It shall be the Contractor's responsibility to determine the actual location of all such facilities, including service connections to underground utilities. Prior to construction, the Contractor shall notify the utility companies of his operational plans, and shall obtain, from the respective utility companies, detailed information and assistance relative to the location of their facilities and the working schedule of the companies for removal or adjustment, where required. In the event an unexpected utility interference is encountered during construction, the Contractor shall immediately notify the utility company of jurisdiction. The Owner's Representative and/or the Resident Engineer shall also be immediately notified. Any damage to such mains and services shall be restored to service at once and paid for by the Contractor at no additional cost to the Contract. All utility cables and lines shall be located by the respective utility. Also coordinate work with all aboveground utilities.
- G. Identify, secure, and place any above ground temporary wiring in conduit to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2G, Part 2.18.3 "Lighting and Visual NAVAIDs". All temporary installations shall comply with National Electrical Code Article 590 – "Temporary Installations."
- H. Grounding work and modifications shall not be performed during a thunderstorm or when a thunderstorm is predicted in the area. Grounding for airfield lights and taxi signs shall be as detailed on the Plans and as specified herein.
- I. Homerun cables for a respective circuit that are installed in conduit or duct shall be run together in the same raceway or duct.
- J. The respective personnel performing airfield lighting work, vault work, and/or tests shall be familiar with, and qualified to work on 5000-volt airfield lighting series circuits, constant current regulators and associated airport electrical vault equipment.
- K. FAA requires that every airfield lighting cable splicer shall be qualified in making cable splices and terminations on cables rated at and/or above 5000 Volts AC and shall have a minimum of three (3) years continuous experience in terminating/splicing medium voltage cable.

- L. Obey and comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.
- M. Other construction projects might be in progress on the Airport at the same time as this project. The Contractor will be required to cooperate with all other contractors and the Airport Director/Manager in the coordination of the work.
- N. The Contractor shall comply with the requirements of FAA AC No. 150/5370-2 (current issue in effect) “OPERATIONAL SAFETY ON AIRPORTS DURING CONSTRUCTION”.
- O. In the event a conflict is determined with respect to manufacturer installation instructions, National Electrical Code, and/or the Contract Documents, contact the Project Engineer for further direction.
- P. Slack cable shall be provided at each splice can, junction, structure, handhole, or manhole to accommodate performing splices outside of the respective structure. There shall be no additional payment for cable slack and therefore the quantity of proposed cable slack has not been included in the respective cable pay items.
- Q. Existing ducts and cables associated with Navaid and/or airfield lighting removals shall be removed where accessible and abandoned in place elsewhere unless it conflicts with the installation of the airfield light, sign, duct, cable, handhole, manhole, site work, pavement or other work, then it shall be disconnected, removed, and disposed of off the site at no additional cost to the Contract. Contractor may remove abandoned cables at no additional cost to the Contract and shall have the salvage rights to abandoned cables.
- R. Obtaining the required borrow material from an offsite borrow, placing the borrow material, grading, seeding, and mulching the disturbed areas will be considered as an Incidental Item to the proposed/relocated lights, splice cans, and/or removal/relocation work and no additional compensation will be allowed.
- S. Requirements of FAA AC 150/5340-30J, Paragraph 1.6 it notes “*Do not use the high voltage series lighting circuit to power devices that are not certified per AC 150/5345-53, Airport Lighting Equipment Certification Program, listed in Appendix 3, Addendum. Using non-certified devices can result in a poor system power factor resulting in unexpected constant current regulator (CCR) shutdowns and lighting circuit start-up problems.*”
- T. When a respective runway is closed the runway lighting and Navaids for that runway shall be shut off. Keep respective Navaids active during times when respective runway is open. Navaids receiving maintenance shall be shut off until operating properly. Coordinate with the Airport Director/Manager to issue NOTAMS when airfield lighting and/or Navaids are out of service.
- U. Provisions shall be made for the temporary wiring of the affected circuits to insure that the Airport will maintain all runway and taxiway lighting capabilities for active runways and taxiways. All temporary wiring will be considered incidental to the

associated work for which it is necessary, and no additional compensation will be allowed.”

Add the following:

125-3.4 INSTALLATION OF ODALS.

- A. ODALS shall be installed at the locations shown on the Plans. Installation of ODALS systems shall conform to FAA AC No. 150/5345-51 (current issue in effect) titled “SPECIFICATION FOR DISCHARGE-TYPE FLASHING LIGHT EQUIPMENT”, other applicable FAA advisory circulars and FAA orders, the respective manufacturer’s instructions, as detailed on the Plans, and as specified herein. The Contractor shall install L-867 base/splice cans and construct concrete bases for the ODALS units in accordance with the respective ODALS manufacturer’s recommendations and as detailed on the Plans. Because of the difference in manufacturers’ installations, all required trenching, cable, and ducts between the ODALS units, associated hardware, mounting requirements, etc. shall be installed in accordance with the respective ODALS manufacturer’s recommendations, and shall be considered part of the installation with no additional compensation. ODALS shall be adjusted as detailed on the Plans and in accordance with the respective manufacturer’s instructions.
- B. Conduit Installation for ODALS. Installation of conduit shall conform to Item 110, the respective ODALS manufacturer’s installation instructions and/or recommendations, as detailed on the Plans and as specified herein. Control cables between ODALS units shall be installed in a separate dedicated conduit. Power cables between the ODALS units shall be installed in a conduit separate from the control cables.
- C. Grounding For ODALS. Grounding for ODALS shall conform to the respective ODALS manufacturer’s installation instructions, as detailed on the Plans, and as specified herein. Furnish and install two 3/4-inch diameter by 30-foot long Copper clad ground rods at each ODALS unit. Ground rods shall be spaced not less than one rod length apart (30 feet minimum for ground rods that are 30 feet in length). Bond each ODALS unit housing and the ODALS base can to the respective ground rod in accordance with the manufacturer’s instructions with a #6 AWG bare solid or stranded (per ODALS manufacturer requirements) copper grounding electrode conductor. Top of ground rods shall be buried not less than 12 inches below grade. All connections to ground rods shall be exothermic weld as manufactured by Cadweld by Pentair Erico Products, Inc., Thermoweld by Continental Industries, Inc., Ultraweld by Harger, or approved equal. Connections to ODALS unit frames shall be as recommended by the manufacturer or with a UL listed grounding connector. Provide multi-terminal ground bar or individual ground lugs to terminate each ground wire in each ODALS unit. For each ODALS unit the Contractor shall test the made electrode ground system with an instrument specifically designed for testing ground systems. Test results shall be recorded for each ODALS unit installation. If ground resistance exceeds 25 Ohms, contact the Project Engineer for further direction.
- D. ODALS Operation. ODALS shall be activated by sensing the current level in the respective associated runway lighting series circuit. The brightness level of the ODALS will correspond to the brightness level of the respective runway lights as follows: 10 percent brightness level – on at low level intensity, 30 percent brightness

level – on at medium level intensity, 100 percent brightness level – on at high level intensity. The Contractor shall test and demonstrate proper operation for the Resident Project Representative and the Airport Manager or respective maintenance staff.

- E. ODALS Ground Check. Prior to final acceptance and activation, each completed ODALS will be ground checked by the Resident Project Representative and/or the Project Engineer, and it shall be the Contractor's responsibility to have a representative present to make any necessary adjustments and/or corrections of the respective REIL system installation. The Contractor shall be responsible to provide ODALS that are installed properly and operate properly.
- F. ODALS Flight Check. Prior to final acceptance and activation, each completed ODALS will be flight checked by Federal Aviation Administration and it shall be the Contractor's responsibility to have a representative present to make any necessary adjustments in the aiming of the respective ODALS units. The Contractor shall be responsible to provide ODALS that pass the flight check by Federal Aviation Administration.
- G. Personnel installing airfield lighting systems shall be experienced and qualified to perform the respective work. Personnel performing cable connections shall be qualified in making cable splices and terminations on 5,000 Volt rated cable for use on runway and taxiway series circuits in accordance with the requirements of Item L-108.

125-3.5 INSTRUCTION AND TRAINING OF AIRPORT STAFF. Contractor shall provide instruction and training to airport staff in regard to the operation and maintenance of the ODALS. The Contractor shall arrange for and provide training of the Airport staff by the respective ODALS manufacturer technical support staff. The training shall include, but not be limited to, set up and check out, demonstration of operating procedures, lamp changing procedures, routine maintenance items, troubleshooting procedures and guidelines, and associated items requiring maintenance to keep the system in proper operating condition and to meet the requirements of the FAA. Contractor shall furnish operation and maintenance manuals for ODALS and associated equipment.

METHOD OF MEASUREMENT

125-4.1 Add the following:

“Ground resistance tests for the made electrode ground system at each ODALS unit will be considered incidental to the respective work item for which they are installed and no additional compensation will be allowed.

Testing the airfield lighting systems and the associated constant current regulator tests and cable tests will be considered incidental to the respective work item for which they are installed, and no additional compensation will be allowed.

Spare parts for the airport visual aid/airfield lighting system will be considered incidental to the respective airfield lighting system pay items and no additional compensation will be allowed.

Conduits, conduit nipples, conduit couplings, and other conduit fittings included with splice cans, junction structures, Navaid installations, base mounted airfield light fixtures, airfield signs, and/or other airfield fixtures, will be considered incidental to the respective item for which they are installed, and no additional compensation will be made.

Ground rods, grounding electrode conductors, connections, and associated grounding work included with airfield lighting and/or Nav aids will be considered incidental to the respective item for which they are installed, and no additional compensation will be made.

All temporary wiring will be considered incidental to the associated work for which it is necessary, and no additional compensation will be allowed.

All cable and duct removals associated with airfield lighting removals, relocations, and /or cable or duct replacements will be considered incidental to the associated work and no additional compensation will be allowed.”

Add the following

125-4.2 ODALS Manufacturer Training. The Contractor shall arrange for and provide training of the Airport staff by the respective ODALS manufacturer technical support staff. This item shall include instruction and training to airport staff in regard to the operation and maintenance of the ODALS, set up and check out, demonstration of operating procedures, lamp changing procedures, routine maintenance items, troubleshooting procedures and guidelines, and associated items requiring maintenance. This item shall include all travel and lodging expenses, transportation, tools, equipment, labor, operation and maintenance manuals, instruction, training, demonstration, manufacturer recommendations for maintaining the system in proper operating condition, and incidentals necessary to complete this item of work. Contractor shall furnish operation and maintenance manuals for ODALS and associated equipment.

BASIS OF PAYMENT

125-5.1 Add the following:

“Payment will be made at the contract price for each completed ODALS installed in place by the Contractor and accepted by the Resident Engineer/Resident Technician. This price shall be full compensation for furnishing all materials and for all preparation, assembly, and installation of these materials; and for all excavation, backfilling, and restoration; and for all labor, testing, equipment, tools, and incidentals necessary to complete this item.

Payment will be made under:

Item AR125636	ODALS – per Lump Sum
Item AR800528	ODALS Manufacturer Training – per Lump Sum”

END OF ITEM 125

ITEM 800476 REMOVE AIRFIELD LIGHTING

DESCRIPTION

800476-1.1 This Item of work shall consist of the removal of the ODALS (Omni-Directional Approach Lighting System), including light fixtures, bases, foundations, conduits, cables, transformers, wiring, and associated materials in accordance with the details in the Construction Plans and in accordance with these Special Provisions.

800476-1.2 REFERENCES. Note: where FAA Advisory Circulars are referenced they shall be the current issue or issues in effect.

- A. FAA AC No. 150/5370-2G “Operational Safety on Airports During Construction” (current issue in effect).
- B. NFPA 70E – Standard for Electrical Safety in the Workplace
- C. OSHA 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures.

CONSTRUCTION METHODS

800476-2.1 GENERAL

- A. Contractor shall examine the site to determine the extent of the work.
- B. Contractor shall coordinate work and any power outages with the Airport Director/Manager and the Resident Engineer. Any shutdown of existing systems shall be scheduled with and approved by the Airport Director/Manager prior to shutdown. Once shut down, the circuits shall be labeled as such to prevent accidental energizing of the respective circuits. All personnel shall follow U.S. Department of Labor Occupational Safety & Health Administration (OSHA) 29 CFR Part 1910 Occupational Safety and Health Standards for electrical safety and lockout/tagout procedures including, but not limited to, 29 CFR section 1910.147 The Control of Hazardous Energy (lockout/tagout).
- C. Contractor shall examine the site to determine the extent of the work. Contractor shall field verify existing site conditions. Contractor shall field verify the respective circuits and power sources prior to removing, disconnecting, relocating, working on, or connecting the respective airfield lighting, taxi sign, NAVAID, circuit, Vault equipment, or other device.
- D. Contractor shall comply with the requirements of FAA AC No. 150/5370-2G “Operational Safety on Airports During Construction” (current issue in effect).
- E. Contractor shall comply with the applicable requirements of NFPA 70E – Standard for Electrical Safety in the Workplace.
- F. Power for each respective airfield lighting system and/or electrical junction structure shall be disconnected at the respective power source prior to removal. Contractor shall field verify to

confirm the respective power source for each respective airfield lighting system or other device. The airfield lighting appears to have power from multiple sources.

- G. Where detailed herein and/or to accommodate maintaining operation of the airfield lighting system, the Contractor shall furnish jumper cables and connector kits as required to place the airfield lighting back into operation. All temporary installations shall comply with National Electrical Code Article 590 – “Temporary Installations.” The Contractor shall secure, identify, and place temporary exposed wiring in conduit, duct, or unit duct to prevent electrocution and fire ignition sources in conformance with the requirements of FAA AC 150/5370-2G “Operational Safety on Airports During Construction”, Part 2.18.3 “Lighting and Visual NAVAIDS”.
- H. Existing airfield lighting cables associated with airfield lighting to be removed shall be abandoned in place unless it conflicts with new work and then it shall be removed at no additional cost to the Contact. If the Contractor elects to salvage the cable within the circuit to be removed, shown in the Construction Plans as cable to be abandoned, any cost associated with removal of the cable shall be considered incidental to the Contract and no additional compensation will be allowed.
- I. Every airfield lighting cable splicer shall be qualified in making cable splices and terminations on cables rated at and/or above 5000 Volts AC. The Contractor shall submit to the Project Engineer proof of the qualifications of each proposed cable splicer for the cable type and voltage level to be worked on. Cable splicing/terminating personnel shall have a minimum of three (3) years continuous experience in terminating/splicing medium voltage cable.

800476-2.2 REMOVAL OF ODALS. An ODALS (Omni Directional Approach Lighting System) shall consist of seven omni-directional sequenced flashing lights located in the runway approach area, the power and control units, concrete bases/foundations, associated cables, conduits, junction structures, series circuit transformers, step-up transformers, step-down transformers, boost transformers, and/or other transformers, circuit breakers, and other associated materials.

Power for each respective ODALS shall be disconnected at the respective power source prior to removing the respective ODALS. Power for the existing ODALS located on Runway 27 is understood to be powered from the Airport Electrical Vault. Contractor shall field verify to confirm the respective power source for each ODALS.

The Contractor shall remove the ODALS units when the runway is closed. The Owner shall retain the right of first refusal for the ODALS equipment and materials. Any items not salvaged by the Airport shall be removed and disposed of off the Airport site in a legal manner. The Contractor shall coordinate with and notify the Airport Manager and the Resident Engineer/Resident Technician and provide a schedule for ODALS removals and the new ODALS installation. The Contractor shall remove the existing ODALS bases and foundations and dispose of them off the airport site in a legal manner. The existing electrical cables from the vault shall be disconnected, removed where accessible or where in conflict with new work, and abandoned in place elsewhere. The Contractor may remove abandoned cables and have the salvage rights to those cables schedule for removal and/or discontinued use. The holes left from the removal of the concrete bases/foundation will be filled with earth material. The earth material will be compacted to prevent any future settlement. The earth material will be obtained from off the Airport site. The disturbed area will be restored, graded, and seeded to the

satisfaction of the Engineer, and will be considered as an incidental item to the removal of the ODALS units.

Remove existing ground rods associated with the ODALS to be removed.

800476-2.3 REMOVAL OF ELECTRICAL JUNCTION STRUCTURES. Removal of electrical junction structures shall include L-867 base cans, splice cans, handholes, and manholes. The existing electrical junction structures designated for removal shall be removed in their entirety. Any materials not salvaged by the Airport, shall be disposed of off the airport site, in a legal manner, at the Contractor's own expense. The existing junction structures, bases, foundations, handholes, manholes, and associated materials designated for removal shall be disposed of off the airport site, in a legal manner, at the Contractor's own expense. Earth material will be placed in the hole made from respective removal. The disturbed area shall be restored.

800476-2.4 RESTORATION. All turf areas disturbed by the removal of the ODALS, junction structures, handholes, manholes, splice cans and associated work shall be restored, graded, and seeded in accordance with Item 901 Seeding and Item 908. All areas disturbed by work shall be restored to its original condition. The hole left from the removal of each base/foundation shall be filled with earth material. The earth material shall be compacted to prevent any future settlement. The earth material shall be obtained from off the Airport site. The restoration shall include any necessary topsoiling, fertilizing, liming, seeding, or mulching, as shown on the plans. All such work shall be performed to establish a stand of grass. The Contractor shall be held responsible for maintaining all disturbed surfaces and replacements until final acceptance. Restoration shall be considered incidental to the pay item of which it is a component part.

BASIS OF PAYMENT

800476-3.1 This item of work will be paid for at the contract unit price bid price per lump sum for Remove Airfield Lighting. This price and payment shall constitute full compensation for field verification of existing site conditions and power sources, disconnecting the respective power sources, removing the ODALS, removal of splice cans, removal of junction structures, junction boxes, handholes, manholes, and/or other electrical equipment enclosures, and removal of associated mounting hardware, bases, foundations, cables, ducts, splice cans, transformer cans, and transformers; disconnecting and/or removal of associated transformers and materials located in the Airport Vault, for all excavating and backfilling; for furnishing all earth material; for all restoration work; and for furnishing all coordination, labor, tools, equipment, and incidentals necessary to complete this item of work. Salvageable materials shall be turned over to the Airport. Any materials not salvaged by the Airport shall be legally disposed of off the Airport site by the Contractor at no additional cost to the Contract.

Payment will be made under:

Item AR800476 Remove Airfield Lighting - per lump sum.

END OF ITEM 800476

APPENDIX A

Lawrenceville-Vincennes International Airport (LWV)
Lawrenceville, Illinois

Replace Omni-Directional Approach Lights (ODALs)
on Runway 27

Cable and Constant Current Regulator
Testing Forms

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Prior to beginning excavations, airfield lighting modifications, cable installation, and/or any other work that might possibly affect airfield lighting circuits, all existing series circuit lighting cables shall be Megger tested with an insulation resistance tester and recorded at the respective airport electrical vault. The respective series circuit cable loops shall have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. Each constant current regulator shall be tested with results recorded. The Contractor is responsible to employ the services of personnel qualified, familiar with, and trained to perform the respective tests, and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.

Insulation resistance testing equipment for use with 5,000 Volt series circuit cables shall use an insulation resistance tester capable of testing the cables at 5,000 Volts. Older series circuit cables and/or cables in poor condition may require the test voltage to be performed at a voltage lower than 5,000 Volts (Example 1,000 Volts, 500 Volts, or less than 500 Volts). The respective test voltage shall be recorded for each cable insulation resistance test result.

Insulation resistance testing equipment for use with 600 Volt rated cables shall use a 500 Volt insulation resistance tester. The respective test voltage shall be recorded for each cable insulation resistance test result.

It is recommended to use the same insulation resistance test equipment throughout the project to ensure reliable comparative readings at the beginning of the project and at the completion of the project.

Disconnect the airfield lighting series circuit cables from the constant current regulator when performing cable insulation resistance tests (Megger Tests). Test the cables that go to the airfield for the respective airfield lighting series circuit. Connect the cable insulation resistance tester to one of the airfield lighting series circuit cables and to a good ground in the airport electrical vault such as the airport vault ground bus. Conduct the cable insulation resistance test on each respective cable for not less than 90 seconds. Record the test results at the end of the time duration for the test.

FAA Advisory Circular 150/5340-26C Maintenance of Airport Visual Aid Facilities provides guidance on Insulation Resistance Tests. Also refer to the user manual for the respective cable insulation resistance tester. Reasonably new series circuit cables and transformers with good connections should read 500 Mega-Ohms to 1,000 Mega-Ohms or higher. The readings should decrease with age. The resistance value declines over the service life of the circuit; a 10-20 percent decline per year may be considered

Engineering Firm	<u>Hanson Professional Services Inc.</u>
Airport Name	<u>Lawrenceville-Vincennes International Airport</u>
Project	<u>Replace Omni-Directional Approach Lights (ODALs) on Runway 27</u>
IL Project No.	<u>LWV-5003</u>
Hanson Project Date	<u>21A0161C</u>

TESTING FORMS

normal. A yearly decline of 50 percent (4 percent monthly) or greater indicates the existence of a problem, such as a high resistance ground, serious deterioration of the circuit insulation, lightning damage, bad connections, bad splices, cable insulation damage, or other failure. FAA Advisory Circular 150/5340-26C notes “Generally speaking, any circuit that measures less than 1 megohm is certainly destined for rapid failure.” Airfield lighting series circuits with cable insulation readings of less than 1 megohm are not uncommon for older circuits that are 20 years or more of age.

Based on information in FAA AC No. 150/5340-26C Maintenance of Airport Visual Aid Facilities, the cable insulation resistance value inevitably declines of the service life of the circuit; a 10-20 percent decline per year may be considered normal. In the event that the cable insulation resistance readings have declined more than 2 percent per month it might indicate cable damage due to lightning or damage as a result of Contractor operations. Where the cable insulation resistance readings have declined more than 2 percent per month over the project construction duration as a result of Contractor operations, Contractor will need to investigate, address, and repair the respective cable circuits.

All existing series circuit cable loops shall also have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. The resistance of the series circuit loop with connections using #8 AWG copper conductor should be approximately 0.8 to 1 Ohm per thousand feet of cable length. The resistance of the series circuit loop with connections using #6 AWG copper conductor should be approximately 0.5 to 0.7 Ohm per thousand feet of cable length. The number of series circuit transformers and connections will affect the overall resistance of the series circuit loop and therefore the measurements might be slightly higher than the calculated resistance for the respective length of cable.

Engineering Firm	Hanson Professional Services Inc.
Airport Name	Lawrenceville-Vincennes International Airport
Project	Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No.	LWV-5003
Hanson Project	21A0161C
Date	

___ Record the date for the respective tests.

___ Record the manufacture and model number of the insulation resistance tester used for the Megger tests. Note: it is recommended to use the same insulation resistance tester again after airfield lighting modifications, additions, and/or upgrades have been completed.

___ Record the manufacture and model number of the Ohmmeter used to measure resistance of each series circuit cable loop. Note: it is recommended to use the same Ohmmeter again after airfield lighting modifications, additions, and/or upgrades have been completed.

___ Record the manufacture and model number of the Ammeter used to measure current. Note: it is recommended to use the same Ammeter again after airfield lighting modifications, additions, and/or upgrades have been completed.

___ Record personnel conducting tests.

___ Record personnel observing tests.

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ Conduct cable insulation resistance test (Megger test) and record Runway 9-27 lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
Runway 9-27 series circuit cable			

___ Runway 9-27 lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
Runway 9-27 series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ Conduct cable insulation resistance test (Megger test) and record Runway 18-36 lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
Runway 18-36 series circuit cable			

___ Runway 18-36 lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
Runway 18-36 series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ Conduct cable insulation resistance test (Megger test) and record East-West Taxiway lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
East-West Taxiway lighting series circuit cable			

___ East-West Taxiway lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
East-West Taxiway lighting series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ Conduct cable insulation resistance test (Megger test) and record North-South Taxiway lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
North-South Taxiway lighting series circuit cable			

___ North-South Taxiway lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
North-South Taxiway lighting series circuit cable	

Engineering Firm	<u>Hanson Professional Services Inc.</u>
Airport Name	<u>Lawrenceville-Vincennes International Airport</u>
Project	<u>Replace Omni-Directional Approach Lights (ODALs) on Runway 27</u>
IL Project No.	<u>LWV-5003</u>
Hanson Project	<u>21A0161C</u>
Date	<u></u>

TESTING FORMS

Tests for constant current regulators shall include the following.

1. The respective personnel performing airfield lighting work, vault work, and/or tests shall be familiar with and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.
2. The respective personnel performing tests shall be familiar with the respective test equipment and the use and operation of the test equipment. The Contractor is responsible to employ the services of personnel qualified to perform the respective tests and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.
3. Test each brightness step and measure and record the input current on Phase A, Phase B and/or Phase C for the 240 VAC branch circuit to each CCR. Note: Provide a True RMS Ammeter for current measurements.
4. Test each brightness step and record the CCR output current to the series circuit lighting. Each CCR should be equipped with an output current meter. In the event the output current meter is not working properly or is out of calibration use a True RMS Ammeter for output current measurements and measure the current in the output series circuit conductor.
5. Test each brightness step and record the CCR output voltage for the series circuit lighting. Each CCR should be equipped with an output voltage meter. Where the CCR does not include an output voltage meter, the output voltage measurements are not required. Do not use a 0 to 600 Volt voltmeter to measure voltage across the CCR output terminals due to safety concerns and high voltages at the CCR output.

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ Test Runway 9-27 CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test Runway 9-27 CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ Test Runway 18-36 CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test Runway 18-36 CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ Test East-West Taxiway CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test East-West Taxiway CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ Test North-South Taxiway CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test North-South Taxiway CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

After airfield lighting modifications, additions, and/or upgrades have been completed, series circuit cables shall be Megger tested with an insulation resistance tester and recorded at the vault. All series circuit cable loops shall have the resistance measured with an Ohmmeter and recorded for each circuit at the vault. Each constant current regulator shall be tested with results recorded. Record the date for the respective tests.

___ Record the manufacture and model number of the insulation resistance tester used for the Megger tests.

___ Record the manufacture and model number of the Ohmmeter used to measure resistance of each series circuit cable loop.

___ Record the manufacture and model number of the Ammeter used to measure current. Note: it is recommended to use the same Ammeter again after airfield lighting modifications, additions, and/or upgrades have been completed.

___ Record personnel conducting tests.

___ Record personnel observing tests.

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ After airfield lighting modifications, additions, and/or upgrades have been completed, Conduct cable insulation resistance test (Megger test) and record Runway 9-27 lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
Runway 9-27 series circuit cable			

___ Runway 9-27 lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
Runway 9-27 series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ After airfield lighting modifications, additions, and/or upgrades have been completed, Conduct cable insulation resistance test (Megger test) and record Runway 18-36 lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
Runway 18-36 series circuit cable			

___ Runway 18-36 lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
Runway 18-36 series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ After airfield lighting modifications, additions, and/or upgrades have been completed, Conduct cable insulation resistance test (Megger test) and record East-West Taxiway lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
East-West Taxiway lighting series circuit cable			

___ East-West Taxiway lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
East-West Taxiway lighting series circuit cable	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

___ After airfield lighting modifications, additions, and/or upgrades have been completed, Conduct cable insulation resistance test (Megger test) and record North-South Taxiway lighting series circuit cable loop at the vault. Time duration of test should not be less than 90 seconds.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
North-South Taxiway lighting series circuit cable			

___ After airfield lighting modifications, additions, and/or upgrades have been completed, North-South Taxiway lighting series circuit cable loop shall have the resistance tested and recorded at the vault. Use an Ohmmeter and measure the resistance of the series circuit loop at the Vault.

Cable Under Test	Series Circuit Loop Resistance in Ohms
North-South Taxiway lighting series circuit cable	

Engineering Firm	Hanson Professional Services Inc.
Airport Name	Lawrenceville-Vincennes International Airport
Project	Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No.	LWV-5003
Hanson Project	21A0161C
Date	

TESTING FORMS

Tests for constant current regulators shall include the following.

1. The respective personnel performing airfield lighting work, vault work, and/or tests shall be familiar with and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.
2. The respective personnel performing tests shall be familiar with the respective test equipment and the use and operation of the test equipment. The Contractor is responsible to employ the services of personnel qualified to perform the respective tests and qualified to work on 5000 Volt airfield lighting series circuits, constant current regulators, and associated airport electrical vault equipment.
3. Test each brightness step and measure and record the input current on Phase A, Phase B and/or Phase C for the 240 VAC branch circuit to each CCR. Note: Provide a True RMS Ammeter for current measurements.
4. Test each brightness step and record the CCR output current to the series circuit lighting circuit. Each CCR should be equipped with an output current meter. In the event the output current meter is not working properly or is out of calibration use a True RMS Ammeter for output current measurements and measure the current in the output series circuit conductor.
5. Test each brightness step and record the CCR output voltage for the series circuit lighting circuit. Each CCR should be equipped with an output voltage meter. Where the CCR does not include an output voltage meter, the output voltage measurements are not required. Do not use a 0 to 600 Volt voltmeter to measure voltage across the CCR output terminals due to safety concerns and high voltages at the CCR output.

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ After airfield lighting modifications, additions, and/or upgrades have been completed, Test Runway 9-27 CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test Runway 9-27 CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ After airfield lighting modifications, additions, and/or upgrades have been completed, Test Runway 18-36 CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test Runway 18-36 CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

__ After airfield lighting modifications, additions, and/or upgrades have been completed, Test East-West Taxiway CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

__ Test East-West Taxiway CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

Engineering Firm Hanson Professional Services Inc.
Airport Name Lawrenceville-Vincennes International Airport
Project Replace Omni-Directional Approach Lights (ODALs) on Runway 27
IL Project No. LWV-5003
Hanson Project 21A0161C
Date _____

TESTING FORMS

Note: Provide a True RMS Ammeter for current measurements. Note Output voltage measurements are not required for constant current regulators that do not include an output voltage meter.

___ After airfield lighting modifications, additions, and/or upgrades have been completed, Test North-South Taxiway CCR by Manual Control and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

___ Test North-South Taxiway CCR in remote mode by airfield lighting control system and record input current and output current at each step.

STEP	INPUT CURRENT	OUTPUT CURRENT
B10	Phase A:	
	Phase B:	
B30	Phase A:	
	Phase B:	
B100	Phase A:	
	Phase B:	

APPENDIX B

Lawrenceville-Vincennes International Airport (LWV)
Lawrenceville, Illinois

Replace Omni-Directional Approach Lights (ODALS)
on Runway 27

ODALS
GROUND CHECK LIST

Airport Identifier:	LWV
Airport Name:	Lawrenceville-Vincennes International Airport (LWV)
Location:	Lawrenceville, Illinois
IL Project No.:	LWV-5003
Hanson Project No.:	21A0161C
Date:	
Site Conditions:	

- a. Inspect each ODALS unit to determine that it is installed correctly, at the proper height, at the correct location, level, and properly oriented.

- b. Check all fixture securing screws or bolts to ensure that they have been tightened per manufacturer recommendations. Use an anti-seize compound on bolts made of stainless steel.

- c. Check each ODALS to determine that the lenses are clean and unscratched.

- d. Test ODALS feeder circuit for continuity and insulation resistance to ground. Observe and record megger test for ODALS feeder circuit conductors.

Cable Under Test	Cable Insulation Resistance	Test Voltage	Time Duration
Phase A conductor			
Phase B conductor			

- e. Check fuses and circuit breakers to determine if they are of the proper rating.

- f.** Check ODALS to determine that it is properly oriented with respect to the runway longitudinal sides and the threshold. Check ODALS for proper location.

- g.** Check equipment covered by FAA specifications to determine if the manufacturers have supplied certified equipment. Also check the equipment for general conformance with requirements of the Plans, Specifications, and Special Provisions.

- h.** Inspect all cables, wiring, and splices to obtain assurance that the installation is per FAA Standard Specifications for Construction of Airports, the Special Provision Specifications, the Plans, the National Electrical Code, and local codes. Inspect and test insulation resistance of underground cables before backfilling.

- i.** Check all ducts and duct markers to determine that the installation is per FAA Standard Specifications for Construction of Airports, the Special Provision Specifications, and the Plans. Inspect underground ducts before backfill is made.

- j.** Check the input voltage at the power and control circuits to determine that the voltage is within limits required for proper equipment operation. Select the proper voltage tap on equipment where taps are provided. Circuitry should also be checked per the manufacturer's requirements.

- k.** Check base plates for damage during installation and refinish according to manufacturer's instructions and as acceptable to the Engineer.

- l.** Check and record the size and type of feeder conductor from the vault or power source to the ODALS.

- m.** Check and record the size and type of feeder conductor from the between ODALS units.

- n.** Check and record the size and type of control circuit conductors between ODALS units.

- o. Record nameplate data for each ODALS unit.

ODALS Unit 6A (Primary Unit with Power and Control)	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 6B (Secondary unit at threshold)	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 5 (unit 300 feet from threshold)	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 4	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 3	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 2	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

ODALS Unit 1 (unit furthest from threshold)	
Manufacturer	
FAA Type:	
Part No.:	
Serial No.:	
Power Requirement:	

- p. Test ODALS by respective control system and confirm proper operation. Check to see if ODALS's activate at Step B10 (10% brightness), Step B30 (30% brightness), and B100 (100% brightness) corresponding to the brightness level of the respective runway lighting circuit.

- q. Check to see if the Primary ODALS unit 6A has a ground wire connection from its frame to the ground rod.

- r. Check to see if the Secondary ODALS unit 6B has a ground wire connection from its frame to the ground rod.

- s. Check to see if the ODALS unit 5 has a ground wire connection from its frame to the ground rod.

- t. Check to see if the ODALS unit 4 has a ground wire connection from its frame to the ground rod.

- u. Check to see if the ODALS unit 3 has a ground wire connection from its frame to the ground rod.

- v. Check to see if the ODALS unit 2 has a ground wire connection from its frame to the ground rod.

- w. Check to see if the ODALS unit 1 has a ground wire connection from its frame to the ground rod.

- x. Make sure each ODALS has good ground. Test and record ground resistance of ground rod installation at each ODALS Unit.

ODALS LIGHT HOUSING UNIT	Measured Ground Resistance in Ohms
ODALS Primary Light Unit 6A	
ODALS Light Unit 6B	
ODALS Light Unit 5	
ODALS Light Unit 4	
ODALS Light Unit 3	
ODALS Light Unit 2	
ODALS Light Unit 1 (furthest from threshold)	

y. Confirm Operation and Maintenance Manuals are provided for ODALS.

z. Ground Check test results submitted by:

Name:	
Company:	
Date:	