

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	155	155				
25200110	SODDING, SALT TOLERANT	SQ YD	155	155				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	84	84				
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2234	2234				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	242	242				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5489	5489				
42001300	PROTECTIVE COAT	SQ YD	207	207				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	55447	55447				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	768	768				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	400	400				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	125	125				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	402	402				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005				
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	7	7				
60404950	FRAMES AND GRATES, TYPE 24	EACH	7	7				
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	3	3				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10164	10164				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1076	1076				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27515	27515				

13

FILE NAME :	USER NAME : pvt10pds	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 137 (BUTTERFIELD RD. TO IL 21 (MILWAUKEE AVE.)) SUMMARY OF QUANTITIES	F.A. RTE. :	SECTION :	COUNTY :	TOTAL SHEETS :	SHEET NO. :		
C:\pvt\pvt10pds\pvt10pds00276648\046511-111-111.dgn						DRAWN -	REVISED -	352	2R-1-RS-1	LAKE	24	3
PLOT SCALE * 1000000' / 1" :						CHECKED -	REVISED -	CONTRACT NO. 60P11				
PLOT DATE * 6/9/2014 :						DATE -	REVISED -	SCALE:	SHEET NO. 3 OF 24 SHEETS	STA. :	TO STA. :	FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT