URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8.3	8.3					
25200110	SODDING, SALT TOLERANT	SQ YD	8.3	8.3					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	73	73					
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1969	1969					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	286	286					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4250	4250					
42101300	PROTECTIVE COAT	SQ YD	107	107					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	665	665					
42400800	DETECTABLE WARNINGS	SQ FT	264	264					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	48522	48522					
44000600	SIDEWALK REMOVAL	SQ FT	665	665					
44003100	MEDIAN REMOVAL	SQ FT	261	261					
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SQ YD	463	463					
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SQ YD	365	365					
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SQ YD	500	500					

URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0005					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	380	380					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2					
60618730	CONCRETE MEDIAN, TYPE M-2.06	SQ FT	261	261					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	18794	18794					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	626	626					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19778	19778					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2383	2383					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	239	239					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1707	1707					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	436.5	436.5					