

ADA RAMP SCHEDULE									
STA. TO STA.	SIDEWALK REMOVAL	4" PCC SIDEWALK	COMBO CC&G REMOVAL	CONC CC&G SPECIAL	DETECTABLE WARNING	ISLAND PAVEMENT REMOVAL	PCC ISLAND PAVEMENT	SOD SALT TOLERANT	EARTH EX
	SQ FT	SQ FT	FEET	FEET	SQ FT	SQ YD	SQ FT	SQ YD	CU YD
SHOOTING PARK RD NW QUAD	140.0	140.0	12.0	12.0	40.0	18.2	752.0	9.1	1.5
SHOOTING PARK RD NE QUAD	150.0	160.0	12.0	12.0	40.0	35.4	686.0	8.4	1.4
SHOOTING PARK RD SW QUAD	223.5	225.0	12.0	12.0	40.0	3.4	455.0	11.3	1.9
SHOOTING PARK RD SE QUAD	125.0	125.0	12.0	12.0	40.0	11.6	470.7	7.6	1.3
US 6 AREA "A"	117.0	130.0	12.0	12.0	10.0	0.0	0.0	8.0	1.3
US 6 AREA "B"	70.0	70.0	6.0	6.0	8.0	0.0	0.0	6.2	1.0
US 6 AREA "C"	70.0	70.0	6.0	6.0	8.0	0.0	0.0	6.2	1.0
US 6 AREA "D"	80.0	80.0	16.0	16.0	10.0	0.0	0.0	5.3	0.9
US 6 AREA "E"	117.0	130.0	16.0	16.0	10.0	0.0	0.0	7.6	1.3
US 6 AREA "F" & "G"	189.0	210.0	14.0	14.0	16.0	0.0	0.0	18.7	3.1
US 6 AREA "H"	112.5	125.0	16.0	16.0	10.0	0.0	0.0	6.7	1.1
US 6 AREA "I"	150.0	150.0	30.0	30.0	10.0	0.0	0.0	7.8	1.3
US 6 AREA "J"	60.0	60.0	8.0	8.0	8.0	0.0	0.0	5.3	0.9
US 6 AREA "K"	60.0	60.0	8.0	8.0	8.0	0.0	0.0	5.3	0.9
US 6 AREA "L"	400.0	340.0	44.0	44.0	10.0	0.0	0.0	20.0	3.3
US 6 AREA "M"	140.0	140.0	20.0	20.0	10.0	0.0	0.0	8.0	1.3
US 6 AREA "P"	130.0	130.0	26.0	26.0	10.0	0.0	0.0	7.6	1.3
TOTALS	2334.0	2345.0	270.0	270.0	288.0	68.6	2363.7	149.1	24.9

DECTECTOR LOOPS		
LOCATION	DECTECTOR LOOP, TY 1	DECTECTOR LOOP TEST
	FEET	EACH
UNYTITE DRIVE	1672	1
MAY/ LASALLE RD	986	1
I-80 WB	1032	1
I-80 EB	952	1
38TH ST	1712	1
WENZEL RD	1738	1
MIDWAY RD	1046	1
SHOOTING PARK RD	2164	1
TOTAL	11302	8

TIE POINTS					
ILL RTE. 251		LASALLE COUNTY 0.8 MI N OF I-80 TO S OF US 6 IN PERU			
GPS POINT NUMBER OR INDEX NUMBER	DESCRIPTION	EXISTING MONUMENT TYPE	PROPOSED MONUMENT TYPE	MONUMENT RECORD TO BE RECORDED	RESPONSIBILITY
251311	NE CORNER SECTION 32 T34N R1E 3RD PM	BRASS PLAQUE	TYPE 1	YES	1
251310	E QTR CORNER SECTION 32 T34N R1E 3RD PM	PK NAIL	TYPE 1	YES	1
251304	SW CORNER SECTION 4 T33N R1E 3RD PM	BRASS DISK	TYPE 1	YES	1

THIS NOTE TO BE INCLUDED IN PLANS:
LISTED MONUMENT LOCATIONS HAVE BEEN RECORDED BY GPS. PRE CONSTRUCTION TIES BY THE R.E. ARE NOT REQUIRED.
IF AN UNLISTED MONUMENT IS FOUND, IT MUST BE TIED BY THE R.E. AND BROUGHT TO THE ATTENTION OF THE PLATS AND PLANS MANAGER.
AFTER RESURFACING, THE R.E. IS TO CONTACT THE PLATS AND PLANS MANAGER TO ESTABLISH LOCATIONS FOR PERMANENT SURVEY MARKER CORING.

RESPONSIBILITY:
1) RESIDENT TO RE-ESTABLISH MONUMENT (PAY ITEM REQUIRED. PERMANENT SURVEY MARKER, TYPE 1)
2) PLATS AND PLANS TO RE-ESTABLISH MONUMENT

CONTRACT 66C07
FOLDER 251-12