

100% STATE

100% STATE

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|---|-------|------------------|------------------------|------------|
| CODE NO | ITEM | UNIT | | URBAN 0005 | RURAL 0005 |
| 40600275 | BITUMINOUS MATERIALS (PRIME COAT) | POUND | 413669 | 204865 | 208804 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 5246 | 5246 | |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SO YD | 1021 | | 1021 |
| 40600990 | TEMPORARY RAMP | SO YD | 2156 | 1741 | 415 |
| 40603243 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90 | TON | 45965 | 23000 | 22965 |
| 40603545 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 | TON | 30833 | 15371 | 15462 |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SO YD | 7220 | 2122 | 5098 |
| 44000162 | HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" | SO YD | 7245 | 7245 | |
| 44004250 | PAVED SHOULDER REMOVAL | SO YD | 2313 | 481 | 1832 |
| 44200573 | CLASS A PATCHES, TYPE I, 12 INCH | SO YD | 15 | | 15 |
| 44200577 | CLASS A PATCHES, TYPE II, 12 INCH | SO YD | 4858 | 763 | 4095 |
| 44200581 | CLASS A PATCHES, TYPE III, 12 INCH | SO YD | 798 | 55 | 743 |

| SUMMARY OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE | |
|-----------------------|------------------------------------|-------|------------------|------------------------|------------|
| CODE NO | ITEM | UNIT | | URBAN 0005 | RURAL 0005 |
| 44200583 | CLASS A PATCHES, TYPE IV, 12 INCH | SO YD | 2691 | 107 | 2584 |
| 44201019 | CLASS B PATCHES, TYPE II, 14 INCH | SO YD | 2165 | 1595 | 570 |
| 44201023 | CLASS B PATCHES, TYPE III, 14 INCH | SO YD | 36 | 18 | 18 |
| 44201294 | CLASS B PATCH - EXPANSION JOINT | FOOT | 4265 | 3045 | 1220 |
| 44201299 | DOWEL BARS 1 1/2" | EACH | 7446 | 5318 | 2128 |
| 44213000 | PATCHING REINFORCEMENT | SO YD | 5660 | 924 | 4736 |
| 44213100 | PAVEMENT FABRIC | SO YD | 36 | 18 | 18 |
| 44213200 | SAW CUTS | FOOT | 60411 | 17689 | 42722 |
| 44213208 | TIE BARS 1 1/4" | EACH | 194 | 38 | 156 |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 5160 | 2563 | 2597 |
| 48203042 | HOT-MIX ASPHALT SHOULDERS, 11 1/4" | SO YD | 2074 | 170 | 1904 |
| 48203050 | HOT-MIX ASPHALT SHOULDERS, 13 1/4" | SO YD | 409 | 311 | 98 |
| 48203100 | HOT-MIX ASPHALT SHOULDERS | TON | 48522 | 23534 | 24988 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 156 | 156 | |

| | | | |
|--|-------------------------------------|------------|-----------|
| FILE NAME = | USER NAME = staffennk | DESIGNED - | REVISED - |
| c:\p\work\psd\st\staffennk\02106637\02106637.dwg | 4470-ht-000.dgn | DRAWN - | REVISED - |
| | PLOT SCALE = 1/8" = 100.0000' / in. | CHECKED - | REVISED - |
| Default | PLOT DATE = 6/12/2014 | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

| | | | | |
|--------------------|----------------|--------|---------------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 72 | 158-64, 65RS-1 | MACON | 47 | 4 |
| CONTRACT NO. 74470 | | | ILLINOIS FED. AID PROJECT | |

SCALE: N/A SHEET 1 OF 3 SHEETS STA. TO STA.