

PAVING SCHEDULE

STATION		LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", NSO	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, NSO	HOT MIX ASPHALT SHOULDERS 3 3/4"	SHOULDER RUMBLE STRIPS	AGGREGATE WEDGE SHOULDERS, TYPE B
TO	STATION	FEET	FEET	FEET	SQ YD	POUND	TON	TON	TON	FOOT	TON
321+88.66	TO 325+35.68	347.0	48.0	12.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
325+35.68	TO 327+63.50	227.8	48.0	12.0	1215.0	1366.9	102.1	153.1	63.8	455.6	233.5
327+63.50	TO 329+36.50	173.0	48.0	22.0	922.7	1038.0	77.5	116.3	88.8	346.0	177.3
329+36.50	TO 331+75.10	238.6	48.0	22.0	1272.5	1431.6	106.9	160.3	122.5	715.8	366.8
331+75.10	TO 333+06.30	131.2	48.0	22.0	699.7	787.2	58.8	88.2	67.3	393.6	201.7
333+06.30	TO 340+73.70	767.4	48.0	32.0	4092.8	4604.4	343.8	515.7	573.0	3069.6	1573.2
340+73.70	TO 342+04.80	131.1	48.0	22.0	699.2	786.6	58.7	88.1	67.3	393.3	201.6
342+04.80	TO 344+02.60	197.8	48.0	22.0	1054.9	1186.8	88.6	132.9	101.5	593.4	304.1
344+02.60	TO 346+36.80	234.2	48.0	22.0	1249.1	1405.2	104.9	157.4	120.2	468.4	240.1
346+36.80	TO 350+66.43	429.6	48.0	12.0	2291.4	2577.8	192.5	288.7	120.3	859.3	440.4
350+66.43	TO 352+54.95	188.5	48.0	22.0	1005.4	1131.1	84.5	126.7	96.8	565.6	289.8
352+54.95	TO 368+00.00	1,545.1	48.0	32.0	8240.3	9270.3	692.2	1038.3	1153.6	6140.2	3167.4
368+00.00	TO 382+00.00	1,400.0	48.0	32.0	7466.7	8400.0	627.2	940.8	1045.3	5560.0	2870.0
382+00.00	TO 578+08.00	19,608.0	48.0	32.0	104576.0	117648.0	8784.4	13176.6	14640.6	78352.0	40196.4
578+08.00	TO 578+36.48	28.5	48.0	22.0	151.9	170.9	12.8	19.1	14.6	85.4	43.8
578+36.48	TO 583+63.90	527.4	48.0	12.0	2812.9	3164.5	236.3	354.4	147.7	1054.8	540.6
583+63.90	TO 584+71.90	108.0	48.0	22.0	576.0	648.0	48.4	72.6	55.4	216.0	110.7
584+71.90	TO 589+86.60	514.7	48.0	22.0	2745.1	3088.2	230.6	345.9	264.2	1544.1	791.4
589+86.60	TO 590+43.90	57.3	48.0	22.0	305.6	343.8	25.7	38.5	29.4	171.9	88.1
590+43.90	TO 596+14.74	570.8	48.0	32.0	3044.5	3425.0	255.7	383.6	426.2	2283.4	1170.2
596+14.74	TO 596+59.74	45.0	48.0	32.0	240.0	270.0	20.2	30.2	33.6	180.0	92.3
596+59.74	TO 600+23.69	364.0	48.0	32.0	1941.1	2183.7	81.5	122.3	271.7	1455.8	746.1
600+23.69	TO 600+68.69	45.0	48.0	32.0	240.0	270.0	20.2	30.2	33.6	180.0	92.3
600+68.69	TO 608+14.40	745.7	48.0	32.0	3977.1	4474.3	334.1	501.1	556.8	2982.8	1528.7
608+14.40	TO 609+72.30	157.9	48.0	22.0	842.1	947.4	70.7	106.1	81.1	473.7	242.8
609+72.30	TO 613+85.30	413.0	48.0	22.0	2202.7	2478.0	185.0	277.5	212.0	1239.0	635.0
613+85.30	TO 614+57.60	72.3	48.0	22.0	385.6	433.8	32.4	48.6	37.1	144.6	74.1
614+57.60	TO 620+22.38	564.8	48.0	12.0	3012.2	3388.7	253.0	379.5	158.1	1129.6	578.9
620+22.38	TO 620+51.82	29.4	48.0	22.0	157.0	176.6	13.2	19.8	15.1	88.3	45.3
620+51.82	TO 689+97.47	6,945.7	48.0	32.0	37043.5	41673.9	3111.7	4667.5	5186.1	27782.6	14238.6
689+97.47	TO 690+42.53	45.1	48.0	32.0	240.3	270.4	20.2	30.3	33.6	180.2	92.4
690+42.53	TO 692+94.22	251.7	48.0	32.0	1342.3	1510.1	0.0	0.0	187.9	1006.8	516.0
692+94.22	TO 693+39.21	45.0	48.0	32.0	239.9	269.9	20.2	30.2	33.6	180.0	92.2
693+39.21	TO 701+00.00	760.8	48.0	32.0	4057.5	4564.7	340.8	511.3	568.1	3043.2	1559.6
SHEET TOTALS		36,809			200,343	225,386	16,635	24,952	26,607	143,335	2,724

FILE NAME : c:\pwork\pavido\staf\pavmk\d8106637\07
Default

USER NAME : staf\pavmk
74470-sht-sch.dgn
PLOT SCALE = 100.0000' / 1"
PLOT DATE : 6/13/2014

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 2 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(58-64, 65)RS-1	MACON	47	12
ILLINOIS FED. AID PROJECT				

CONTRACT NO. 74470