

PAVEMENT MARKING SCHEDULE

LOCATION		LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE DASHED)	TEMPORARY PAVEMENT MARKING-LINE 8"	TEMPORARY PAVEMENT MARKING-LINE 12"	TEMPORARY PAVEMENT MARKING-LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PREFORMED PLASTIC PAVEMENT MARKING, TYPEB-INLAID-6"	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (YELLOW)	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (WHITE)	THERMOPLASTIC PAVEMENT MARKING-LINE 4" (WHITE DASHED)	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER (CRYSTAL)	RAISED REFLECTIVE PAVEMENT MARKER (AMBER)
STATION TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
RAMP G																			
500+56.89	TO 503+01.64	244.8	0.0	0.0	244.8	0.0	0.0	0.0	0.0	81.5	0.0	0.0	244.8	0.0	0.0	0.0	0.0	12.0	0.0
503+01.64	TO 506+27.21	325.6	0.0	0.0	325.6	0.0	325.6	0.0	0.0	325.6	0.0	0.0	325.6	0.0	325.6	0.0	0.0	25.0	0.0
506+27.21	TO 521+14.90	1,487.7	0.0	1,487.7	1,487.7	0.0	0.0	0.0	0.0	990.8	0.0	1,487.7	1,487.7	0.0	0.0	0.0	0.0	0.0	14.0
521+14.90	TO 521+99.87	85.0	0.0	0.0	85.0	0.0	385.0	0.0	0.0	543.8	0.0	0.0	1,083.1	0.0	385.0	0.0	0.0	0.0	0.0
521+99.87	TO 531+98.04	998.2	0.0	0.0	998.2	0.0	0.0	0.0	0.0	332.4	0.0	0.0	998.2	0.0	0.0	0.0	0.0	0.0	0.0
LOOP H																			
550+00.00	TO 550+90.15	90.2	0.0	0.0	90.2	0.0	0.0	0.0	0.0	30.0	0.0	0.0	90.2	0.0	0.0	0.0	0.0	7.0	0.0
550+90.15	TO 551+91.41	101.3	0.0	0.0	101.3	0.0	100.8	0.0	0.0	169.3	0.0	0.0	101.3	0.0	100.8	0.0	0.0	10.0	0.0
551+91.41	TO 562+12.00	1,020.6	0.0	1,020.6	1,020.6	0.0	0.0	0.0	0.0	679.7	0.0	1,020.6	1,020.6	0.0	0.0	0.0	0.0	0.0	28.0
IL 48 INTG																			
RAMP A																			
0+36.23	TO 25+97.30	2,561.1	0.0	2,561.1	2,561.1	0.0	0.0	0.0	0.0	1,705.7	0.0	2,561.1	2,561.1	0.0	0.0	0.0	0.0	0.0	0.0
25+97.30	TO 29+77.33	380.0	0.0	0.0	380.0	0.0	380.0	0.0	0.0	635.2	0.0	0.0	380.0	0.0	380.0	0.0	0.0	0.0	0.0
29+77.33	TO 37+75.86	798.5	0.0	0.0	798.5	0.0	0.0	0.0	0.0	265.9	0.0	0.0	798.5	0.0	0.0	0.0	0.0	0.0	0.0
RAMP B																			
401+94.84	TO 403+04.56	109.7	0.0	0.0	109.7	0.0	0.0	0.0	0.0	36.5	0.0	0.0	109.7	0.0	0.0	0.0	0.0	8.0	0.0
403+04.56	TO 406+62.40	357.8	0.0	0.0	357.8	0.0	357.8	0.0	0.0	595.6	0.0	0.0	357.8	0.0	357.8	0.0	0.0	35.0	0.0
406+62.40	TO 430+90.06	2,427.7	0.0	2,427.7	2,427.7	0.0	0.0	157.0	34.0	1,945.2	0.0	2,427.7	2,427.7	0.0	0.0	157.0	34.0	0.0	38.0
RAMP C																			
200+36.57	TO 212+35.32	1,198.8	0.0	1,198.8	1,198.8	0.0	0.0	0.0	0.0	798.4	0.0	1,198.8	1,198.8	0.0	0.0	0.0	0.0	0.0	0.0
212+35.32	TO 216+16.69	381.4	0.0	0.0	381.4	0.0	381.4	0.0	0.0	127.0	0.0	0.0	381.4	0.0	381.4	0.0	0.0	0.0	0.0
216+16.69	TO 219+37.70	321.0	0.0	0.0	321.0	0.0	0.0	0.0	0.0	617.4	0.0	0.0	321.0	0.0	0.0	0.0	0.0	0.0	0.0
219+37.70	TO 222+90.71	353.0	0.0	0.0	353.0	0.0	0.0	0.0	0.0	117.6	0.0	0.0	353.0	0.0	0.0	0.0	0.0	0.0	0.0
RAMP D																			
100+00.00	TO 103+04.00	304.0	0.0	0.0	304.0	0.0	0.0	0.0	0.0	101.2	0.0	0.0	304.0	0.0	0.0	0.0	0.0	17.0	0.0
103+04.00	TO 106+62.39	358.4	0.0	0.0	358.4	0.0	359.5	0.0	0.0	598.2	0.0	0.0	358.4	0.0	359.5	0.0	0.0	29.0	0.0
106+62.39	TO 121+62.72	1,500.3	0.0	1,500.3	1,500.3	0.0	0.0	133.0	34.0	1,303.6	0.0	1,500.3	1,500.3	0.0	0.0	133.0	34.0	0.0	20.0
CH 25 INTG																			
RAMP A																			
100+23.81	TO 119+35.07	1,911.3	0.0	1,911.3	1,911.3	0.0	0.0	0.0	0.0	1,272.9	0.0	1,911.3	1,911.3	0.0	0.0	0.0	0.0	0.0	0.0
119+35.07	TO 123+42.44	407.4	0.0	0.0	407.4	0.0	407.4	0.0	0.0	680.5	0.0	0.0	407.4	0.0	407.4	0.0	0.0	0.0	0.0
123+42.44	TO 131+40.34	797.9	0.0	0.0	797.9	0.0	0.0	0.0	0.0	265.7	0.0	0.0	797.9	0.0	0.0	0.0	0.0	0.0	0.0
SHEET TOTALS		18,521	0	12,107	18,521	0	2,698	290	68	14,220	0	12,107	19,520	0	2,698	290	68	143	100

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\p\id\dot\steffenmk\d0186637\074470-sh-t-sch.dgn	DRAWN -	REVISED -	72						(58-64, 65)RS-1	MACON	47	19	
Default	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -		SCALE: N/A	SHEET 9 OF 10 SHEETS	STA.	TO STA.	CONTRACT NO. 74470				
	PLOT DATE = 6/13/2014	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								