## INDEX OF SHEETS

2. INDEX OF SHEETS LIST OF APPLICABLE GENERAL NOTES	STATE	STANDARDS
---	-------	-----------

## 3-4. SUMMARY OF QUANTITIES

1. TITLE SHEET

- 5. McHENRY COUNTY LOCATION MAP
- 6. LAKE COUNTY LOCATION MAP
- 7. NORTH KANE COUNTY LOCATION MAP
- 8. NORTH DU PAGE COUNTY LOCATION MAP
- 9, NORTH COOK COUNTY LOCATION MAP
- 10. SOUTH COOK COUNTY LOCATION MAP
- 11. SOUTH KANE COUNTY LOCATION MAP
- 12. SOUTH DU PAGE COUNTY LOCATION MAP
- 13. WILL COUNTY LOCATION MAP
- 14. TYPICAL DETAIL TO ANCHOR STEEL PLATE BEAM GUARDRAIL ON CONCRETE (BM-02)
- 15. TYPICAL DETAIL FOR GUARDRAIL ANCHOR BLOCK REPAIR (BM-03)
- 16. TYPICAL DETAILS FOR STEEL PLATE BEAM GUARDRAIL ANCHORAGE REPAIR (BM-04)
- 17. DETAIL FOR CENTER LONGITUDINAL GUARDRAIL JOINT (BM-05)
- 18. DETAIL OF STEEL PLATE BEAM GUARDRAIL SPECIAL (BM-06)
- 19. DETAIL OF GUARDRAIL SUPPORT AND END ANCHORAGE (BM-07)
- 20. DETAIL OF THRIE-BEAM GUARDRAIL WITH MODIFIED OFFSET BLOCK
- 21 STEEL PLATE BEAM GUARDRAIL STEEL BLOCK-OUT DETAIL
- 22. CURB REMOVAL (PARTIAL) AND SHOULDER WIDENING FOR TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL
- 23. STEEL BRIDGE RAIL DETAIL
- 24-26. T6 TERMINAL FOR USE WITH 21" HIGH SPBGR (BM-22)
  - 27. ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)
  - 28. TRAFFIC CONTROL DETAIL FOR SHOULDER CLOSURE AND PARTIAL RAMP CLOSURES (TC-17)
  - 29. SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS (TC-18)

## LIST OF STATE STANDARDS

630301-06 SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS 631006-08 TRAFFIC BARRIER TERMINAL, TYPE 1B 631011-09 TRAFFIC BARRIER TERMINAL, TYPE 2 631026-06 TRAFFIC BARRIER TERMINAL, TYPE 5 631031-14 TRAFFIC BARRIER TERMINAL, TYPE 6 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE 701301-04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS	
631011–09 TRAFFIC BARRIER TERMINAL, TYPE 2 631026–06 TRAFFIC BARRIER TERMINAL, TYPE 5 631031–14 TRAFFIC BARRIER TERMINAL, TYPE 6 701006–05 OFF–RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE	
631026-06 TRAFFIC BARRIER TERMINAL, TYPE 5 631031-14 TRAFFIC BARRIER TERMINAL, TYPE 6 701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE	
631031–14 TRAFFIC BARRIER TERMINAL, TYPE 6 701006–05 OFF–RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE	
701006-05 OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE	
701301–04 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS	
701311–03 LANE CLOSURE, 2L, 2W, MOVING OPERATIONS, DAY ONLY	
701336-06 LANE CLOSURE, 2L, 2W, WORK AREAS IN SERIES, FOR SPEEDS > 45 MPH	
701400-08 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY	
701401–09 LANE CLOSURE, FREEWAY/EXPRESSWAY	
701411-09 LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEED ≥ 45 MP	H
701421-07 LANE CLOSURE, MULTILANE, DAY OPERATIONS ONLY FOR SPEEDS > 45 MPH TO	55 MPH
701427-04 LANE CLOSURE, MULTILANE, INTERMITTANT OR MOVING OPERATIONS < 40 MPH	
701428-O\ TRAFFIC CONTROL SETUP AND REMOVAL FREEWAY/EXPRESSWAY	
701501–06 URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED	
701601-09 URBAN LANE CLOSURE, MULTILANE, IW OR 2W, WITH NONTRAVERSABLE MEDIAN	
701606-10 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN	
701701-10 URBAN LANE CLOSURE, MULTILANE INTERSECTION	
701801-06 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE	
701901-05 TRAFFIC CONTROL DEVICES	
720011-01 METAL POSTS FOR SIGNS, MARKERS & DELINEATORS	

## **GENERAL NOTES**

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 OR "CUAN" AT (312) 744-700 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. 48 HOUR NOTIFICATION IS REQUIRED.

ALL WORK IS TO BE REPLACED IN KIND OR AS INDICATED ON THE CONTRACT QUANTITY SHEET.

GUARDRAIL WORK WILL INCLUDE ALIGNMENT AS NECESSARY TO RESTORE THE RAIL TO THE ORIGINAL CONDITIONS.

REMOVAL OF DAMAGED MATERIALS WILL INCLUDE DISMANTLING, LOADING, HAULING AND DISPOSAL. THE WORK SITE WILL BE LEFT IN A SAFE AND ORDERLY CONDITION.

NO MATERIAL SHOULD BE LEFT ON OR NEAR THE ROADWAY DURING NON-WORKING HOURS.

ANY NECESSARY TRAFFIC CONTROL WILL BE PROVIDED BY THE CONTRACTOR; APPROPRIATE STANDARDS ARE HEREWITH ATTACHED.

THE LIMITS OF THE DAMAGED GUARDRAIL WILL BE MARKED WITH PAINT. THE REPLACEMENT PARTS AND THE QUANTITIES INDICATED ARE WITHIN THESE LIMITS AS MARKED.

REMOVED GUARDRAIL THAT IS NOT REPLACED ON THE SAME DAY MUST BE DELINEATED WITH LIGHTED BARRICADES. NO LOCATIONS WILL BE LEFT WITHOUT EITHER LIGHTED BARRICADES OR RESTORED GUARDRAIL AT ANY TIME

GUARDRAIL MARKERS SHALL NOT BE ATTACHED TO TERMINAL SECTIONS.

THE CONTRACTOR SHALL TELEPHONE THE IDOT BUREAU OF TRAFFIC OPERATIONS, ELECTRICAL MAINTENANCE SECTION AT 708-524-2145 TO REQUEST THE LOCATE FOR INDERGROUND ELECTRICAL AND/OR FIBER CABLE PRIOR TO ANY DIGGING AS PER THE CONTRACT.

REMOVAL OF EXISTING TERMINAL SECTIONS INCLUDED IN COST OF NEW TERMINAL SECTIONS

Δ	REVISED	SHEET	8-30-16
---	---------	-------	---------

FILE NAME :	USER NAME a pyrzariovskirb	DESIGNED -	REVISED -			······································					F.A.	SECTION	COUNTY	TOTAL	SHEET
1	uments\1001 Offices\District 1\Prejects\0144	<del></del>	REVISED -	STATE OF ILLINOIS	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES				VAR.	2016-045GRR	VARIOUS	29	2		
	PLOT SCRLE = 198.9888 1/ 10.	CHECKEO -	HEVISEU -	DEPARTMENT OF TRANSPORTATION							CONTRAC	CT NO. F	52024		
L	PLOT DATE = 7/14/2016	DATE -	REVISEO -		SCALE:	SHEET NO.	OF	SHEET	TS STA.	TO STA.	FED. ROAD	DIST, NO. ILLINOIS FED	. AID PROJECT		