					CONSTRUCTION TYPE CODE								
	SUMMARY OF QUANTITIES			80% FED. 20% STATE		IL. RTE. 22 & TELEGRAPH RD. 80%.FED./ 10%.STATE	IL. RTE. 22 & WAUKEGAN RD. <b>80%. FED. 20%.</b> STATE	IL. RTE. 22 & RIDGE RD./ TENNYSON LN.  80'. FED./10'.STATE 10'. HIGHLAND PARK	IL. RTE. 22 &     RIDGE RD.  801. FEO. 801. FEO. 6.7% HIGHLAND PARK 201. STATE	50% STATE 50% BANNOCKBURN	PARK	100% BANNOCKBURN EMERGENCY	
CODE NO.	ITEM	UNIT	TOTAL QTY.	ROADWAY JOOO-2A	ROADWAY IOOO-2A	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F				PRE-EMPTION Y031-3D		
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	3000-2A	1000-24	1031-17	1031-11	1031 11	1	31 11 10	1031 30	1031 30	
¥ 97700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1						1				
* 87700240	SIEEL WAST ARM ASSEMBLI AND FOLE, 40 FT.	EACH	1						1				
* 87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1					1					
* 87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1					1					
* 87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH				1							
* 87700330	STEEL MAST ARM ASSEMBLY AND POLE, 56 FT.	EACH	1				1						
	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1			1		<del>                                     </del>					
	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.  STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 70 FT. AND 40 FT.	EACH EACH	1				1						
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	36			12	12		12				
* 87800100	CONCRETE FOUNDATION, TIPE A	F001	٥٤			12	1.4		12				
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	16			4	4	4	4		· ·		
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	140			37	16	52	35				
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	90			21	69						
* 87900200	DRILL EXISTING HANDHOLE	EACH	2						2				
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	38			8	16	8	6				
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	8			2	2	2	2				
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5			2		2	1				
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10			2	5	2	1				
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1				1						
* 88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	4				4						
* 88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	1				1						
		EACH	1				1						
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6			4			2				
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	6			1		4	1				
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	48			10	21	10	7				
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	43			8	21	8	6				
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,117					689	428				
* 88700200	LIGHT DETECTOR	EACH	7									7	
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2									2	
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	24			6	6	8	4				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	4			1	1	1	1				
* 89100400	ILLUMINATED SIGN, LED	EACH	2				2		3				
	ITEMS				1							SHEET 7	

USER NAME = \$USER\$ DESIGNED - LP REVISED W:\JLRTE22\ '009 REVISIONS\CADD Sheets\D160860-sht-S00.dgn DRAWN LP REVISED PLOT SCALE = \$SCALE\$
PLOT DATE = 5/15/2010 CHECKED - JP REVISED DATE 05/14/2010 REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 22													
SUMMARY OF QUANTITIES													
SCALE: NTS	SHEET NO. 9 OF 232 SHEETS STA.	TO STA.											

SECTION COUNTY TOTAL SHEET NO.

20R-4 LAKE 232 9

CONTRACT NO. 60860

ILLINOIS FED. AID PROJECT F.A.P RTE. 337 SECTION 20R~4