60260100 INLETS TO BE ADJUSTED

EACH	LOCATION	
1	STA 48+59.36	25.74' LT
1	STA 51+58.15	26.35' RT
2	TOTAL	

60500040 REMOVING MANHOLES

EACH	LOCATION	
1	STA 50+80.37	CENTER
1	TOTAL	

60600605 CONCRETE CURB, TYPE B

FOOT	LOCATION			
9	STA 50+61.66	TO	STA 50+68.62	LT
7	STA 50+87.32	TO	STA 50+86.27	LT
16	TOTAL			

60603800 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12

FOOT	LOCATION			
41	STA 48+22.46	TO	STA 48+60.39	LT
11	STA 49+27.41	TO	STA 49+27.68	RT
33	STA 51+38.10	TO	STA 51+71.05	RT
76	STA 50+94.97	TO	STA 51+71.05	LT
161	TOTAL			

60610400 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24

FOOT	LOCATION			
130	-112.12 LT CENTER PIER	TO	18.04	RT
130	TOTAL			

63300230 REMOVAL AND REINSTALLATION OF EXISTING STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES

FOOT	LOCATION
91	WEST ABUTMENT
91	EAST ABUTMENT
182	TOTAL

63700255 CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT

FOOT	LOCATION				
109	-200 LT CENTER PIER	TO	-91	LT
104	91 RT CENTER PIER	TO	195	RT
213	TOTAL				

63700805 CONCRETE BARRIER TRANSITION

FOOT	LOCATION				
50	-91 LT CENTER PIER	TO	-41	LT
50	41 RT CENTER PIER	TO	91	RT
100	TOTAL				

63700900 CONCRETE BARRIER BASE

FOOT	LOCATION			
159	-200 LT CENTER PIER	TO	-41	LT
154	41 RT CENTER PIER	TO	195	RT
313	TOTAL			

64200105 SHOULDER RUMBLE STRIP

FOOT	LOCATION			
1210.0	STA -840	TO	STA 370	SB
1748.0	STA -888	TO	STA 860	NB
2958.0	TOTAL			

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			
462.5	STA 4878.22	TO	STA 53+45.83	ELSTON STAGE 1
125.0	STA 4882.92	TO	STA 4962.63	RAMP TO I-94
300.0	STA -215.2	TO	STA 72.3	I-94 WEST ABUTMENT
287.5	STA -82.5	TO	STA 217.5	I-94 EAST ABUTMENT
225.0	STA -300	TO	STA 225	I-94 WEST PIER
250.0	STA -204.5	TO	STA 333	I-94 EAST PIER
100.0	STA -300	TO	STA 100	I-94 WEST PIER
287.5	STA -242	TO	STA 333	I-94 EAST ABUTMENT
2037.5	TOTAL			

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION			
300.0	STA -300	TO	STA 225	I-94 WEST PIER
287.5	STA -104.5	TO	STA 333	I-94 EAST PIER
287.5	STA 48+85.03	TO	STA 51+73.96	ELSTON STAGE 2
300.0	STA -215.2	TO	STA 72.3	I-94 WEST ABUTMENT
287.5	STA -82.5	TO	STA 217.5	I-94 EAST ABUTMENT
300.0	STA -300	TO	STA 100	I-94 WEST PIER
287.5	STA -242	TO	STA 333	I-94 EAST PIER
2050.0	TOTAL			

78200530 BARRIER WALL MARKERS, TYPE C

EACH	LOCATION			
38	STA 4878.22	TO	STA 53+45.83	ELSTON STAGE 1
10	STA 4882.92	TO	STA 4962.63	RAMP TO I-94
24	STA -215.2	TO	STA 72.3	I-94 WEST ABUTMENT
24	STA -82.5	TO	STA 217.5	I-94 EAST ABUTMENT
18	STA -300	TO	STA 225	I-94 WEST PIER
20	STA -204.5	TO	STA 333	I-94 EAST PIER
8	STA -300	TO	STA 100	I-94 WEST PIER
24	STA -242	TO	STA 333	I-94 EAST ABUTMENT
166.0	TOTAL			

X0322256 TEMPORARY INFORMATION SIGNING

SQ FT	LOCATION	
12.5	STA 45+37	LT DE SIGN
12.5	STA 46+84	RT DE SIGN
12.5	STA 46+85	LT DE SIGN
12.5	STA 47+58	RT DE SIGN
12.5	STA 53+90	RT DE SIGN
12.5	STA 58+00	RT DE SIGN
12.5	STA 58+00	LT DE SIGN
12.5	STA 54+00	LT DE SIGN
12.5	STA 59+89	LT DE SIGN
51.4	ROAD WORK AHEAD EXPECT DELAYS (TC-22) X 2	
163.9	TOTAL	

X0324345 COMBINED SEWER REMOVAL, 24"

45.0	STA 50+80 RT	TO STA	51+25 RT
59.0	STA 50+81 RT	TO STA	50+69 LT
104.0	TOTAL		

X0325085 TEMPORARY PAVEMENT (INTERSTATE)

SQ YD	LOCATION
49	-52.31 LT CENTER PIER TO 2.279 RT
49	TOTAL

X0326095 PIPE UNDERDRAIN REMOVAL AND REPLACEMENT

FOOT	LOCATION				
318	-200 LT CENTER PIER	TO	-41	LT
308	41 RT CENTER PIER	TO	195	RT
626	TOTAL				

X4022000 TEMPORARY ACCESS (COMMERCIAL ENTRANCE)

EACH	LOCATION	
1	STA 50+77	LT
1	TOTAL	

X6022400 MANHOLES, TYPE A, 3' DIA. (INCLUDING FRAMES AND LIDS)

EACH	LOCATION	
1	STA 51+25	0' RT
1	STA 50+69	31' LT
2	TOTAL	

ADJUST FRAMES AND LIDS

EACH	LOCATION	
1	STA 48+25.57	33.79' LT
1	STA 48+56.64	12.78' LT
1	STA 48+95.72	30.38' RT
1	STA 49+36.44	31.67' RT
4	TOTAL	

60300105 FRAMES AND GRATES TO BE ADJUSTED

EACH	LOCATION
1	195.51' LT OF CENTER OF PR PIER
1	167.30' LT OF CENTER OF PR PIER
1	157.63' LT OF CENTER OF PR PIER
1	72.61' LT OF CENTER OF PR PIER
1	72.03' LT OF CENTER OF PR PIER
1	103.74' RT OF CENTER OF PR PIER
6	TOTAL