

- 5. Cost of installation of side retainers and other steel members required for the elastomeric bearing assembly shall be included in the cost of Erecting
- 6. The structural steel plates and side retainers of the Bearing Assembly shall conform to the requirements of AASHTO M 270 Grade 50.
- 7. Two $l_{\mathcal{B}}$ in. adjusting shims shall be provided for each bearing in addition to



SIDE RETAINER Equivalent rolled angle with stiffeners will be allowed in lieu of welded plates.

Ĵ٩

43,

€ 1¹2" ¢ Hole

4³4"



- 4. Drilled and set anchor bolts shall be installed according to Article 521.06 of the Standard Specifications.
- Elastomeric Bearing Assembly, Type I.
- all other plates or shims and placed as shown on bearing details.

BILL OF MATERIAL

Item	Unit	Total
Erecting Elastomeric Bearing Assembly, Type I	Each	20
Anchor Bolts, 14"	Each	80

BEARING DETAILS STRUCTURE NO. 016-2119

o.s23	F.A.I. RTE.	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.		
	94	1314B-1			СООК	110	59		
HEETS					CONTRACT	NO. 60	F65		
	ILLINOIS FED. AID PROJECT								