

SUMMARY OF QUANTITIES			100% STATE			SUMMARY OF QUANTITIES			100% STATE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X081-2A	CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000	BRIDGE X081-2A
60262700	INLETS TO BE RECONSTRUCTED	EACH	2	1	1	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	46	38	8
60300105	FRAME AND GRATES TO BE ADJUSTED	EACH	4		4	* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	45	45	
60300305	FRAME AND LIDS TO BE ADJUSTED	EACH	2	2		* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" x 12" x 6"	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9		* 81306500	REMOVE EXISTING JUNCTION BOX	EACH	2	2	
67100100	MOBILIZATION	L SUM	1	1		* 81400115	HANDHOLE TO BE ADJUSTED	EACH	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		20030850	TEMPORARY INFORMATION SIGNING	SQ FT	78	78	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		* X0323710	REMOVE CONDUIT ATTACHED TO STRUCTURE	FOOT	45	45	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	364	364		* 20033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	1	1	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	220	220		20012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS 5 INCHES)	SQ FT	8		8
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	131	131		X7030104	WET ^{PAVEMENT MARKING} TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	5626	5626	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2551	2551		X7030106	WET ^{PAVEMENT MARKING} TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	220	220	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	436	436		X7030124	WET ^{PAVEMENT MARKING} TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	81	81	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	52	52		X7030120	WET ^{PAVEMENT MARKING} TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	115	115	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	33	33		X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	184		184
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	507	507		X7240500	RELOCATE EXISTING SIGNS	EACH	1	1	
* 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	46	46		X2800510	INLET FILTER CLEANING	EACH	6	6	
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	13	13		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	38	38		Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8	Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
* 78200500	BARRIER WALL MARKERS	EACH	16	16		X0320863	BRICK SIDEWALK	SQ FT	753	753	
						X0320864	BRICK SIDEWALK REMOVAL	SQ FT	753	753	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	561	561							

* SPECIALTY ITEMS

LONCO, INC.
CONSULTING ENGINEERS
1560 WALL ST., SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY
DRAWN - ST, TSC
CHECKED - MJY, SLV
DATE - 03/26/2010

REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
IL ROUTE 59 OVER FLINT CREEK TRIBUTARY**

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. 98+00 TO STA. 101+60

F.A.P. RTE. 338	SECTION 108 B-1	COUNTY LAKE	TOTAL SHEETS 40	SHEET NO. 4
D-91-289-09		CONTRACT NO. 60F92		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.