



MATERIALS REQUIRED FOR (1) ONE LUG SYSTEM

(Excluding Pavement Concrete and Pavement Reinforcement)

	Bar	Qty.	S	ize		Length			Shape		
7	а	264	No. 8	(No.	25)	14'-0''	(4.25	m)			
	Ь	18	No. 5	(No.	16)	48'-9''	(7.43	m)			
	С	264	No. 5	(No.	16)	20'-0"	(6.10	m)			
	d	56	No. 4	(No.	13)	11'-9''	(3.52	m)			

Concrete, cu. yds. 43.0
Reinforcing Bars, lbs. 16622
Concrete Pad, sq. yds. 304
Improved Subgrade, sq. yds. 323

	USER NAME =	DESIGNED - JDU	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-57 AT I-294 INTERCHANGE PROJECT	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEET
TYLIN INTERNATIONAL	PLOT SCALE =	CHECKED - JPM	REVISED -		CRC PAVEMENT WITH LUG SYSTEM COMPLETE 48'	57	1414.2B	соок	516 66
	PLOT DATE =	DATE - 3/18/201	D REVISED -		SCALE: NTS SHEET NO. 2 OF 2 SHEETS STA. TO STA.	FED, RO	OAD DIST, NO. ILLINOIS F	CONTRACT ED. AID PROJECT	T NO. 60J27
p:\602540(57-294)\road\p1_15	7 br\P1_DTL_LUG_48_02.dgn								J'