STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

1. Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts. Bolts $\frac{7}{8}$ in. ϕ, holes $\frac{15}{16}$ in. ϕ, unless otherwise noted.

2. Calculated weight of Structural Steel =
   Grade 50 = 589,460 lbs.
   Grade 36 = 130,850 lbs.

3. The Organic Zinc Rich Primer/Epoxy/Urethane paint system shall be used for painting of new structural steel except where otherwise noted. The entire system shall be shop applied, with the exception that the exterior surfaces and bottom of the bottom flange of the fascia beams, masked off connection surfaces, and field installed fasteners, all of which shall be touched up and finish coated in the field. The color of the final finish coat for all interior steel surfaces shall be gray, Munsell No. 5B 7/1. The color of the final finish coat for the exterior and bottom flange of the fascia beams shall be Reddish Brown, Munsell No. 2.5YR 3/4. See Special Provision for "Cleaning and Painting New Metal Structures".

4. Materials, fabrication welding, and non-destructive testing for the members identified as Fracture Critical Member and member components (FCM) in the contract plans shall conform to the requirements of Section 12 of the current ANSI/ AASHTO / AWS / D 1.5 Bridge Welding Code.

5. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.

INDEX OF SHEETS

1 GENERAL PLAN AND ELEVATION NORTH APPROACH
2 GEN. NOTES, INDEX OF SHEETS & BILL OF MATER.
3 STAGE I CONSTRUCTION
4 STAGE II CONSTRUCTION
5 TOP OF SLAB ELEVATIONS LAYOUT SPANS 11, 12 & 13
6 TOP OF SLAB ELEVATIONS LAYOUT SPANS 14 & 15
7 TOP OF SLAB ELEVATIONS 1 (New Beams only)
8 TOP OF SLAB ELEVATIONS 2 (New Beams Only)
9 TOP OF SLAB ELEVATIONS 3 (New Beams Only)
10 SUPERSTRUCTURE CROSS SECTION SPANS 11, 12 & 13
11 SUPERSTRUCTURE CROSS SECTION SPANS 14 & 15
12 SUPERSTRUCTURE CROSS SECTION SPAN 16
13 FINGER PLATE PLAN & SECTIONS - EAST
14 FINGER PLATE PLAN & SECTIONS - WEST
15 FINGER PLATE DETAILS 1
16 FINGER PLATE DETAILS 2
17 FRAMING PLAN SPANS 11, 12 & 13
18 FRAMING PLAN SPANS 14 & 15
19 MOMENT & REACTION TABLES
20 GIRDER ELEVATIONS SPANS 11, 12 & 13
21 GIRDER ELEVATIONS SPANS 11, 12 & 13
22 GIRDER ELEVATIONS SPANS 14 & 15
23 DIAPHRAGMS SPAN 11
24 CROSS FRAMES SPANS 11, 12 & 13
25 CROSS FRAMES SPANS 14 & 15
26 FRAMING DETAILS CONNECTIONS
27 FRAMING DETAILS FIELD SPLICES 1 & 2
28 FRAMING DETAILS FIELD SPLICES 3 & 4
29 CAMBER DIAGRAMS
30 ELASTOMERIC BEARINGS TYPE I
31 ELASTOMERIC BEARINGS TYPE II
32 ELASTOMERIC BEARINGS TYPE III
33 BEARING DETAILS

TOTAL BILL OF MATERIAL

	NORTH APPROACH			
ITEM	UNIT	SUPER	SUB	TOTAL
FURNISHING STRUCTURAL STEEL	L SUM	0.11	-	0.11
FURNISHING FINGER PLATE EXPANSION JOINT, 6"	FOOT	116.0	-	116.0
FURNISHING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	46	-	46
FURNISHING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	37	-	37
FURNISHING ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	17	-	17
FIELD MEASUREMENTS	L SUM	0.33	-	0.33
STORAGE OF STRUCTURAL STEEL	CAL DA	60	-	60
STORAGE OF ELASTOMERIC BEARING ASSEMBLIES	CAL DA	60	-	60
STORAGE OF FINGER PLATE EXPANSION JOINTS	CAL DA	60	-	60

GENERAL NOTES, INDEX OF SHEETS & BILL OF MATERIAL
STRUCTURE NO. 016-3240

TYLIN INTERNATIONAL

DESIGNED	DY, LS
CHECKED	AMD, LS
DRAWN	DY, LS
CHECKED	AMD, LS
DATE	08/02/10

REVISIONS	
NAME	DATE

SHEET NO. 2
33 SHEETS

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	0711.2R & 1011.1BR	COOK	200	169
		CONTRACT NO. 60L39		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

p:\01345\beam and bearing fabrication\155c3genot.dgn 1:57:02 PM 8/2/2010