

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
					I000	SFTY-1D
	20101700	SUPPLEMENTAL WATERING	UNIT	1	1	
	25200110	SODDING, SALT TOLERANT	SQ YD	720	720	
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50	
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3916	3916	
	40600300	AGGREGATE (PRIME COAT)	TON	49	49	
	X4067112	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1372	1372	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	228	228	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1727	1727	
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	50	50	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1914	1914	
	42400800	DETECTABLE WARNINGS	SQ FT	80	80	
	44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	19576	19576	
	Z0004544	HOT-MIX ASPHALT DRIVEWAY PAVEMENT REMOVAL	SQ YD	128	128	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50	50	
	44000600	SIDEWALK REMOVAL	SQ FT	1914	1914	
	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	455	455	
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	88	88	
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	139	139	
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	1339	1339	
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	315	315	
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	22	22	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2000	2000	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17600		17600
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	100		100
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	36		36
*	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	16		16
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	250	250	
	X0325912	HOT-MIX ASPHALT SHOULDER REMOVAL AND REPLACEMENT, 6"	SQ YD	62	62	
	Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	128	128	

**GENERAL NOTES**

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ECT. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 00180_01-QUAN-01 - IDOT P01	USER NAME =	DESIGNED -- JPH	REVISED --	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	PRINCE DRIVE RESURFACING 170TH STREET TO WOODLAWN EAST AVENUE SUMMARY OF QUANTITIES AND GENERAL NOTES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		CHECKED -- PKB	REVISED --		94	10-00088-00-RS	COOK	18	2			
	PLOT SCALE =	DRAWN -- RG	REVISED --		SCALE: NA			SHEET NO. 2 OF 18 SHEETS			CONTRACT NO. 63495	
	PLOT DATE = 06-22-10	CHECKED -- AG	REVISED --		STA. TO STA.			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-9003(668)				