THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

	SUMMA	RY OF QUANTITIES	Y031	-1F
	CODE NO.	ITEM	UNIT	TOTAL
l	20200100	EARTH EXCAVATION	CUYD	7
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	23
١	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQFT	300
4	42400800	DETECTABLE WARNINGS	SQFT	56
4	44000600	SIDEWALK REMOVAL	SQFT	100
	67100100	MOBILIZATION	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1
	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	340
	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	826
I	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	882
-	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	2
	88030080	SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	1
	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2
	88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1
	88030320	SIGNAL HEAD, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION BRACKET MOUNTED	EACH	1
	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2
	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1
	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	7
	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4
	89502200	MODIFY EXISTING CONTROLLER	EACH	1
	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
	X8140074	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	6
	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1
	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	535
	X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, LED. 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1
	X8808180	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1
	X8809020	COMBINATION SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION OPTICALLY PROGRAMMED, 1-3 SECTION, BRACKET MOUNTED	EACH	1.
	X8809046	COMBINATION SIGNAL HEAD, LED, 2-FACE, 1-4 SECTION OPTICALLY PROGRAMMED, 1-5 SECTION, BRACKET MOUNTED	EACH	1

<sup>\*</sup> SPECIALTY ITEM

FILE NAME =	USER NAME = GHA	DESIGNED - JRD	REVISED -			SUN	MAR	Y OF C	DUANTITIES	S	FAU. RTE.	SECTION	COUNTY	SHEETS NO.
4270.800-TR1.dwg		DRAWN - ZCW	REVISED -	STATE OF ILLINOIS	AND GENERAL NOTES					1547,2757	10-00038-00-TL	COOK	11 2	
	PLOT SCALE = 1" = .0833'	CHECKED - DPB	REVISED -	DEPARTMENT OF TRANSPORTATION								CONTRACT	T#: 63501	
	PLOT DATE = 4/29/10	<b>DATE</b> - 4/29/10	REVISED -		SCALE: N.A. SHEET NO. OF SHEETS STA.				TO STA.		ILLINOIS FED. A			