

# NO SCALE R CAN NOT BE F

\*IF A 4" COVER CAN NOT BE PROVIDED A PAVED DITCH SHALL BE CONSTRUCTED AS SHOWN IN DETAIL C.

- STORM SEWER, PROTECTED


#### NOTES

PROP DT. 2'

Воттом

\* -4" MIN.

- 1. WIDTH OF CONCRETE SLAB SHALL BE THE SAME AS THE TRENCH WIDTH IN ACCORDANCE WITH SECTION 550 OF THE STD. SPECIFICATIONS, OR 3' MIN.
- 2. CONCRETE FOR SLAB, HEADWALL AND PAVED DITCH SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE PER CUBIC YARD FOR MISCELLANEOUS CONCRETE."
- 3. COST OF FURNISHING AND INSTALLING WIRE MESH SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER CUBIC YARD FOR MISCELLANEOUS CONCRETE. WIRE MESH TO WEIGH NOT LESS THAN 58\* PER 100 SO. FT.



#### DETAIL C


NO SCALE

ALTERNATE MATERIALS FOR WALLS	Т				
PRECAST REINFORCED CONCRETE RISERS					
CONCRETE MASONRY UNIT					
MONOLITHIC CONCRETE	6′′				
BUILDING BRICK, GRADE SW FROM CLAY OR SHALE	8′′				
CONCRETE BUILDING BRICK, GRADE A	8′′				


#### NOTES


- 1. THE CONTRACT UNIT PRICE FOR FIELD TILE JUNCTION VAULT SHALL INCLUDE THE COST OF FURNISHING AND PLACING THE FRAME AND GRATE OR PRECAST CONCRETE LID AND WHEN REQUIRED, THE SAND CUSHION.
- 2. ALL FIELD TILE JUNCTION VAULTS SHALL BE 2'-0"
  IN DIAMETER UNLESS OTHERWISE NOTED ON THE PLANS.

# SECTION B-B



#### FIELD TILE REPLACEMENT







SECTION A-A


#### NOTES

- 1. ANY STORM SEWER OR FIELD TILE OUTLET INTO A DITCH SHALL HAVE A HEADWALL BUILT IN ACCORDANCE WITH THIS DETAIL.
- 2. COST OF FURNISHING AND INSTALLING WIRE
  MESH SHALL BE INCLUDED IN THE CONTRACT
  UNIT PRICE PER CUBIC YARD FOR
  MISCELLANEOUS CONCRETE. WIRE MESH TO WEIGH NOT
  LESS THAN 58# PER 100 SQ. FT.



**END VIEW** 






# 201/2" DIA.



± 145#



SECTION A-A

• FAI 80 & FAS 297 / FAU 392

### FIELD TILE JUNCTION VAULT

## 611–2

FILE NAME =	USER NAME = LUSER_	DESIGNED - CGC	REVISED -
t:@1812@cadd sheets@D366408~sht~details.dgn		DRAWN - CGC	REVISED -
	PLOT SCALE = \$SCALE\$	CHECKED - AKK	REVISED -
	PLOT DATE = 5/19/2010 .	DATE - 5/19/2010	REVISED -

**CLASS SI CONCRETE HEADWALLS** 

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	DISTRICT DETAILS					(32,47-4) HBK-4 & G(N)	GRUNDY	351	158	
						CONTRACT NO. 66408				
	SCALE: AS NOTED	SHEET NO. 158 OF 351 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT					