

SCALE: NTS

NOTE:

US-6 SLOTTED DRAIN PIPE

SEE DISTRICT DETAIL 601-2 SLOTTED DRAIN PIPE FOR ADDITIONAL INFORMATION

I-80

MAINLINE

SHOULDER
GORE AREA

1 3/4" SLOT

VARIES

SLOTTED PAVEMENT
DRAIN 12"0

RAMP C
RAMP C
RAMP C
SHOULDER
GORE AREA

1 3/4" SLOT
VARIES
FROM 6" TO 12"


CLASS SI CONCRETE

I-80 AT RAMP C SLOTTED DRAIN PIPE SCALE: NTS


SEE DISTRICT DETAILS 601-2 SLOTTED DRAIN PIPE, 542546-01 FLUSH INLET BOX FOR MEDIAN, AND 420301-04 EXIT RAMP TERMINAL, FOR ADDITIONAL INFORMATION

NOTE:

STABILIZED CONSTRUCTION ENTRANCE




PLAN VIEW SCALE: NTS



NOTES:

- FILTER FABRIC SHALL MEET THE REQUIREMENTS OF SECTION 282 OF THE STANDARD SPECIFICATIONS AND SHALL BE PLACED OVER THE CLEARED AREA PRIOR TO THE PLACING OF ROCK.
- 2. ROCK OR RECLAIMED CONCRETE SHALL MEET ONE OF THE FOLLOWING IDOT COARSE AGGREGATE GRADATIONS, CA-1, CA-2, CA-3 OR CA-4 AND BE PLACED ACCORDING TO SECTION 351 OF THE STANDARD SPECIFICATIONS.
- 3. ANY DRAINAGE FACILITIES REQUIRED BECAUSE OF WASHING SHALL BE CONSTRUCTED ACCORDING TO MANUFACTURERS SPECIFICATIONS.
- 4. IF WASH RACKS ARE USED THEY SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S SPECIFICATIONS.



NOTES.

- SEE SECTION 204.06 OF THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION.
- 2. SETTLEMENT PLATFORM WILL BE CONSIDERED AS INCLUDED IN THE COST OF FURNISHED EXCAVATION.

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DISTRICT DETAILS					F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
						(32,47-4) HBK-4 & G(N)	GRUNDY	351	166
							CONTRACT	NO. 6	6408
SCALE: AS NOTED	SHEET NO. 166 OF 351	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				