

SCHEDULE OF QUANTITIES			
OQUAWKA COVERED BRIDGE VIDEO SURVEILLANCE SYSTEM			
ITEM	UNIT	QTY.	COMMENTS
ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 1/C NO. 10	FOOT	334.0	
REMOVE EXISTING SURVEILLANCE CAMERA EQUIPMENT	EACH	1.0	
CLOSED CIRCUIT TELEVISION DOME CAMERA	EACH	2.0	
SUPPORT EQUIPMENT AND MAINTENANCE	LSUM	1.0	MATERIAL ONLY
CLOSED CIRCUIT TELEVISION DOME CAMERA (MATERIAL ONLY)	EACH	2.0	MATERIAL ONLY
COMPUTER WORKSTATION	EACH	2.0	MATERIAL ONLY
ETHERNET SWITCH (MATERIAL ONLY)	EACH	4.0	MATERIAL ONLY
REMOTE POWER MANAGEMENT UNIT	EACH	1.0	MATERIAL ONLY
EQUIPMENT CABINET	EACH	1.0	
VIDEO SERVER	EACH	2.0	MATERIAL ONLY
DIGITAL VIDEO DECODER	EACH	4.0	MATERIAL ONLY
CAT 5 ETHERNET CABLE	FOOT	1037.0	
UNINTERRUPTIBLE POWER SUPPLY	EACH	1.0	MATERIAL ONLY

CONSTRUCTION NOTES	
1.	ANY MAINTENANCE OF THE EXISTING VIDEO SURVEILLANCE SYSTEM WILL BE CONSIDERED EXTRA WORK IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
2.	THE LOCATION OF ALL UTILITIES AND PRIVATELY OWNED FACILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO THE INSTALLATION OF ANY COMPONENTS.
3.	THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOCATING EXISTING IDOT ELECTRICAL FACILITIES AT HIS/HER OWN EXPENSE IF REQUIRED. THE CONTRACTOR SHALL ALSO BE LIABLE FOR ANY DAMAGE TO IDOT FACILITIES RESULTING FROM INACCURATE LOCATING.
4.	ELECTRICAL WORK SHALL CONFORM WITH NATIONAL, STATE, AND LOCAL CODES.
5.	THE CONTRACTOR SHALL PROVIDE ELECTRICAL CABLE SLACK IN ACCORDANCE WITH ARTICLE 873.03.
6.	ELECTRICAL CABLE WILL BE MEASURED FOR PAYMENT IN ACCORDANCE WITH ARTICLE 873.04.
7.	ALL SURPLUS MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.