COMMITMENTS

No Commitments have been made for this project

GENERAL NOTES

PLAN ELEVATIONS - U. S. G. S. MEAN SEA LEVEL DATUM All elevations shown on the plans are established from U.S.G.S. mean sea level datum.

UTILITIES - LOCATIONS /INFORMATION ON PLANS

The locations of existing water mains, gas mains, sewers, electric power lines, telephone lines and other utilities as shown on the plans are based on careful field investigation and the best information available, but they are not guaranteed. Unless elevations are shown — all utility locations shown on the cross sections are based on the approximate depth supplied by the utility company. It shall be the Contractor's responsibility to ascertain their exact location from the utility companies and by field inspection.

TREE REMOVAL - UTILITY RELOCATION

Tree removal may be necessary prior to utility companies being able to relocate their facilities outside the construction limits. The Contractor should coordinate any contract tree removal activities with the utility companies to eliminate conflicts and potential delays caused by utility tree removal activities or incomplete utility relocations.

TREE REMOVAL

The District Four Tree Committee should be contacted and prior approval obtained for any tree removal beyond the limits/locations included in the plans.

ORDERING LENGTH CONFIRMATION - DRAINAGE ITEMS

The Contractor shall consult with the Engineer in regard to the exact length of the box/pipe culverts, storm sewers, and/or pipe drains required prior to ordering these items.

ENVIRONMENTAL REVIEWS

Prior to the use of any proposed borrow areas, use areas (temporary access roads, detours, run-arounds, etc.) and/or waste areas, the Contractor shall file the required environmental resource request surveys according to Section 107.22 of the Standard Specifications. These surveys are required in order for the Department to conduct cultural and biological resource surveys for the proposed site.

Prior to any waste materials being removed from the construction site the required environmental resource surveys will need to be obtained and filed by the Contractor. Excess waste products removed from the construction site shall be disposed of as required in Section 202.03 of the Standard Specifications.

Any protruding metal bars shall be removed prior to the disposal of broken concrete at approved disposal sites.

The required environmental resource documentation shall include the following:

- **BDE Form 2289 (Environmental Survey Request)**

- Color photographs depicting the use area
- Borrow Area Entry Agreement form-D4 PI0101

Please note that a minimum of two weeks shall be allowed for the District to obtain therequired environmental clearances.

ENGINEERS FIELD OFFICE

Add the following sentence to the end of paragraph 670.02 (i) and 670.04 (e): All of the telephone lines provided shall have unpublished numbers.

Existing guardrail to be removed shall become the property of Illinois Department of Transportation. Please Contact Dave Cambell at (309) 837-5837.

		IL RTE 41 SL						
	FILE NAME =	USER NAME = crespole	DESIGNED ~	REVISED -	STATE OF ILLINOIS			
	D468974-sht-gennote.dgn		DRAWN -	REVISED -	STATE OF TELEVOID	COMMITMENTS AN		
		PLOT SCALE = 100.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO. OF)F SHE
- ¹		PLDT DATE = 6/15/2010	DATE -	REVISED -				

A location map showing the size limits and location of the use area Signed property owner agreement form-D4 PI0100

JOB SPECIFIC NOTE:

11 SLOPE REPAIR 6 AND GENERAL NOTES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
			574	12I-1	Fulton	31	2	
					CONTRACT	NO. 6	8974	
SHEETS	STA.	TO STA.			ILLINOIS FED. A	D PROJECT		