

# SCHEDULE OF QUANTITIES

SCHEDULE OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SFTY Y031-1F		SCHEDULE OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE SFTY Y031-1F	
CODE NO	ITEM	UNIT		MAIN ST	CLAY ST	CODE NO	ITEM	UNIT		MAIN ST	CLAY ST
72000100	SIGN PANEL - TYPE 1	SQ FT	61.5	32	29.5	87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	4	2	2
72000200	SIGN PANEL - TYPE 2	SQ FT	10	10		87800100	CONCRETE FOUNDATION, TYPE A	FOOT	15	6	9
80300100	LOCATING UNDERGROUND CABLE	FOOT	200	100	100	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	7	3.5	3.5
80500100	SERVICE INSTALLATION, TYPE A	EACH	2	1	1	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	42	13.5	28.5
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	423	216	207	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	83.5	46.5	37
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	774	369	405	88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	196	45	151	88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	12	6	6
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	678	307	371	88040110	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED	EACH	3	3	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	27	11	16	88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	5	3	2
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	13	7	6	88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3	1	2
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2	1	1	88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1842	843	999	88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	2		2
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	1	1	88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	3	1	2
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2	1	1	88102820	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION BRACKET MOUNTED	EACH	6	2	4
85900100	TRANSCEIVER	EACH	1	1		88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	20	10	10
86000100	MASTER CONTROLLER	EACH	1		1	88500100	INDUCTIVE LOOP DETECTOR	EACH	26	13	13
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2629	1178	1451	88600100	DETECTOR LOOP, TYPE I	FOOT	3499	1790	1709
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2768	1178	1590	88800100	PEDESTRIAN PUSH-BUTTON	EACH	12	6	6
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4590	2155	2435	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	120	70	50
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3640	1640	2000	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2	1	1
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5292	2351	2941	89502380	REMOVE EXISTING HANDHOLE	EACH	8	4	4
87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	500	250	250	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	14	7	7
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	95	45	50	X0324896	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 2-SECTION, BRACKET MOUNTED	EACH	3	2	1
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	5	2	3	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2175	1075	1100
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	3	2	1						
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2	1	1						
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1						
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1	1							