

RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	PIATT	62	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
* 08-00255-00-BR				
** FAS 535				

CULVERT SCHEDULE																						
LOCATION	TEMP INLETS TB TIF OLID PRCFST (X0323236)	CLASS D, TYPE 1		END SECTIONS		TRENCH BACKFILL (20800150)	CLASS A, TYPE 1, 30" (542A0235)	CONCRETE COLLAR (54248510)	REINFORCEMENT BARS (50800105)	EXPANSION BOLTS (54002070)												
		18" (542D0223)	18" (TEMP) (5421D018)	18" (54213453)	18" (TEMP) (X0322938)																	
		EACH	FOOT	FOOT	EACH						EACH	CU YD	FOOT	CU YD	POUND	EACH						
STA. 28+50 RT											1											
STA. 30+00 RT																					265	
STA. 31+18 RT	1																				10	
STA. 31+74 RT																						90
STA. 32+31 RT	1																					10
STA. 33+50 RT																						223
STA. 34+57 RT	1																					10
STA. 35+01 RT																						65
STA. 35+45 RT	1																					25
STA. 37+66 RT																						75
STA. 48+98 RT																						
TOTALS	4																					230
																						543
																						6
																						2
																						10
																						17
																						0.5
																						30
																						8

CULVERT REMOVAL SCHEDULE			
LOCATION	PIPE CULVERT REMOVAL (50105220)	CONCRETE HEADWALL REMOVAL (50104400)	REMOVING INLETS (60500060)
	FOOT	EACH	EACH
STA. 31+20, 20' RT	245		1
PE STA. 31+59 RT	57		
PE STA. 31+88 RT	17	2	
PE STA. 35+01 RT	23		
PE STA. 37+66 RT	36	2	
TOTALS	378	4	1

STONE RIPRAP, CLASS A4 SCHEDULE (28100107)	
LOCATION	SQ YD
NORTH ABUTMENT	265
SOUTH ABUTMENT	265
STA. 53+00, RT	17
TOTAL	547

ESCA
CONSULTANTS, INC.

DESIGNED BY:	ELH	01/10
DRAWN BY:	HAS	01/10
CHECKED BY:	ELH	05/10
APPROVED BY:	RDP	05/10

SCHEDULES OF QUANTITIES
FAS 535 (SHADY REST ROAD)
SECTION 08-00255-00-BR
PIATT COUNTY