



EROSION CONTROL NOTES

ALL ITEMS SHALL BE CONSTRUCTED AS SHOWN IN THESE PLANS, ON STANDARD 280001 AND AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL MAINTAIN ALL ROADWAYS ADJOINING THE PROJECT SITE KEEPING THEM SHALL MAINTAIN ALL ROADWAYS ADJUINING THE PROJECT STIE REEPING THEM FREE FROM MUD AND DEBRIS AT ALL TIMES. TEMPORARY EROSION CONTROL SYSTEMS SHALL BE MAINTAINED BY THE CONTRACTOR UNTIL PERMANENT SEEDING IS ESTABLISHED. ALL DISTURBED AREAS SHALL RECEIVE TEMPORARY EROSION CONTROL SEEDING DURING THE CONSTRUCTION PROCESS. THE CONTRACTOR SHALL PERFORM DAILY INSPECTIONS AND MAINTAIN WRITTEN
REPORTS OF THE INSPECTIONS. THE COST OF MAINTENANCE OF TEMPORARY
EROSION CONTROLS SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE EROSION CONTROL ITEM.

SEEDING NOTES

FINAL SEEDING SHALL BE CLASS 2A IN ACCORDANCE WITH SECTION 250 OF THE STANDARD SPECIFICATIONS. APPLICATION RATES FOR THE FERTILIZER NUTRIENTS AND AGRICULTURAL GROUND LIMESTONE ARE AS NOTED ON SHEET 2 IN THE GENERAL NOTES. MULCH SHALL BE METHOD 2 IN ACCORDANCE WITH SECTION 251 OF THE STANDARD SPECIFICATIONS.
EROSION CONTROL BLANKET SHALL BE PLACED ON THE STREAM

SLOPE UPON COMPLETION OF SEED AND MULCH AT THE LOCATION SHOWN ON THE PLANS.

LEGEND

SCE

INLET AND PIPE PROTECTION INLET FILTER PERIMETER EROSION BARRIER STONE RIPRAP, CLASS A3 WITH FILTER FABRIC

EROSION CONTROL BLANKET

STABILIZED CONSTRUCTION ENTRANCE

STA 9+23.64 TO STA 33+94.97 FAU RTE. 8046(MEADOWBROOK ROAD) SECTION 09-00465-00-PV CITY OF SPRINGFIELD 4/19/10 SANGAMON COUNTY Coombe-Bloxdorf P.C.

-civil engineers-structural engineers-land surveyorsPhone: 217/544-4477
Design Firm license No. 184-002703
755 South Grand Ave. W. Springfield, IL. 62704 16

EROSION CONTROL PLAN

100'