STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TIMBER SPACING

	Timber Sizes (in.)							
Beam Spacing (ft.)		4" x 6" with min. Fb=775 psi Fv=135 psi	6" x 6" with min. Fb=575 psi Fv=125 psi					
	Maximum Timber Spacing (in.)							
4.5	16	16	16					
4.75	16	16	16					
5.0	16	16	16					
5.25	16	16	16					
5.5	16	16	16					
5.75	16	16	16					
6.0	16	16	16					
6.25	12	16	16					
6.5	12	16	16					
6,75	12	16	16					
7.0	8	16	16					
7.25	8	16	16					
7.5	8	16	16					
7.75	8	16	16					
8.0	8	12	16					
8.25	8	12	16					
8.5	6	12	12					
8.75	6	12	12					
9.0	6	8	12					





SECTION A-A

DESIGNED - CMV		
CHECKED - SDS	WHKS & co.	7018 KINGSMILL CT., SPRINGFIELD, IL
DRAWN - DLH		(217) 483-9457 DESIGN FIRM #184001036

NOTES

See special provisions for Permanent Protective Shield System. Timber sizes shown are nominal sizes. Rough sawn timber of the dimensions shown will also be considered acceptable. The minimum Fb and Fv values shown are the tabulated design values given in the National Design Specification for Wood Construction for No. 2 Spruce-Pine-Fir without adjustment factors applied. Better grades or other species with equal or higher allowable stresses will also be considered acceptable.

The timber spacings shown have been determined using allowable stresses with all adjustment factors necessary for the anticipated service conditions.

All timber shall be treated.

Plywood shall be 5_{g} " Exterior type plywood. by APA. Plywood shall be placed such that the face grain is perpendicular to the timber supports. When less than a full sheet (4' width) of plywood is used, the width of the strip used shall not be less than 2'. Transverse plywood joints shall be supported by timbers. When 4" x 6" timbers are used, they shall be placed such that the wide face is horizontal and the narrow face is vertical. Design load = 200 psf.

PERMANENT PROTECTIVE SHIELD FAI-80 EB RAMP TO I-294

*Section (95-5-1, ETC, 189-824)RS-1

SHEET NO. 2	F.A.I. RTE,	SECTION			COUNTY	TOTAL SHEETS	SHEET NO.
	80	*			СООК	80	46
2 SHEETS	SN 0	016-2132			CONTRACT	NO. 60	F61
	FED. RC	DAD DIST. NO	ILLINOIS FE	ED. All) PROJECT		
	D_Q1_1/5_0Q						