## STATE STANDARDS

SHEET NO.	<u>TITLE</u>
1	TITLE SHEET
2	GENERAL NOTES, INDEX OF SHEETS
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6	STAGING TYPICAL SECTIONS
7	CONSTRUCTION STAGING PLAN - STAGE 1
8	CONSTRUCTION STAGING PLAN - STAGE 2
9	PLAN AND PROFILE
10	PAVEMENT MARKING PLAN
11	EROSION CONTROL PLAN
12-26	STRUCTURAL PLANS
27	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
28	BUTT JOINT AND HMA TAPER DETAILS
29	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
30	RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
31	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
32	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
33	ARTERIAL ROAD INFORMATION SIGN
	HIGHWAY STANDARDS

SHEET NO.	<u>TITLE</u>
000001 <i>-05</i>	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001 <b>- 02</b>	AREAS OF REINFORCEMENT REBARS
280001 <b>-04</b>	TEMPORARY EROSION CONTROL SYSTEMS
420401 <b>-07</b>	BRIDGE APPROACH PAVEMENT CONNECTOR
442201 <b>-03</b>	CLASS C AND CLASS D PATCHES
515001 <b>-03</b>	NAME PLATE FOR BRIDGE
635006 <b>-03</b>	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011 <b>-02</b>	REFLECTOR MARKER AND MOUNTING DETAILS
701301 <b>-03</b>	LANE CLOSURE 2L, 2W SHORT TIME OPERATIONS
<del>701326 <b>05</b></del>	LANE CLOSURE, ZE, ZW, PAVEMENT WIDENING, FOR SPEEDS 2 45 MITH
701331 <b>- 03</b>	LANE CLOSURE, 2L, 2W, WITH RUN-AROUND FOR SPEEDS ≥ 45 MPH
701331 <b>- 03</b>	
701331 <b>-03</b>	FOR SPEEDS ≥ 45 MPH
<del>701431-<b>05</b></del>	FOR SPEEDS ≥ 45 MPH
<del>701431-<b>05</b></del>	FOR SPEEDS 2 45 MPH  LANE GLOSURE, MULTILANE, UNDIV, WY GROSSOVER,  FOR SPEEDS 2 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES
701901- <b>01</b>	FOR SPEEDS 2 45 MPH  LANE CLOSURE, MULTILANE, UNDIV, W/ CROSSOVER, FOR SPEEDS 2 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES  TEMPORARY CONCRETE BARRIER
701431- <b>03</b> 701901- <b>01</b> 704001- <b>05</b>	FOR SPEEDS \( \) 45 MPH  LANE CLOSURE, MULTILANE, UNDIV. W/ CROSSOVER, FOR SPEEDS \( \) 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES  TEMPORARY CONCRETE BARRIER  SIGN PANEL MOUNTING DETAILS
701431-03 701901-01 704001-05 720001-01	FOR SPEEDS 2 45 MPH  LANE GLOSURE, MULTILANE, UNDIV, WY GROSSOVER,  FOR SPEEDS 2 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES  TEMPORARY CONCRETE BARRIER  SIGN PANEL MOUNTING DETAILS  SIGN PANEL ERECTION DETAILS
701431-03 701901-01 704001-01 720006-02	FOR SPEEDS 2 45 MPH  LANE GLOSURE, MULTILANE, UNDIV, W/ GROSSOVER,  FOR SPEEDS 2 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES  TEMPORARY CONCRETE BARRIER  SIGN PANEL MOUNTING DETAILS  SIGN PANEL ERECTION DETAILS  METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS
701431-03 701901-01 704001-05 720001-01 720006-02	FOR SPEEDS 2 45 MPH  LANE CLOSURE, MULTILANE, UNDIV, W/ CROSSOVER,  TOR SPEEDS 2 45 MPH TO 55 MPH  TRAFFIC CONTROL DEVICES  TEMPORARY CONCRETE BARRIER  SIGN PANEL MOUNTING DETAILS  SIGN PANEL ERECTION DETAILS  METAL POSTS FOR SIGNS, MARKERS AND DELINEATORS  APPLICATION OF TYPES A & B METAL POSTS (FOR SIGN & MARKERS)

## GENERAL NOTES

ALL ELEVATIONS ARE BASED ON UNITED STATES COAST AND GEODETIC SURVEY DATUM.

DIMENSIONS ARE IN ENGLISH UNITS UNLESS OTHERWISE NOTED.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT LISTED IN THE PLANS WITH THE LATEST NUMBERS.

DURING CONSTRUCTION OPERATIONS, LOOSE MATERIAL DEPOSITS
THAT OBSTRUCT THE FLOW OF WATER IN DRAINING THE AREA SHALL
BE REMOVED BEFORE THE END OF EACH WORK DAY, AT THE
CONCLUSION OF CONSTRUCTION OPERATIONS, ALL DRAINAGE
STRUCTURES (NEW AND EXISTING) SHALL BE FREE FROM ALL DIRT
AND DEBRIS. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT
SHALL BE INCLUDED IN THE COST OF COMPOST FUNISH AND PLACE 4".

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING PROPERTIES.

THE CONTRACTOR SHALL NOTIFY THE AREA TRAFFIC FIELD ENGINEER, DON CHIARUGI, AT (847) 741-9857 AT LEAST 72 HOURS PRIOR TO FINAL PAVEMENT MARKING INSTALLATION.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

ALL UNBALLASTED TYPE I AND TYPE II BARRICADES SHALL HAVE TWO (2) SANDBAGS ON THE BOTTOM RAIL.

ALL WORK IS TO BE COMPLETED WITHIN 45 WORKING DAYS.
THE COMPLETION DATE FOR THIS CONTRACT IS SEPTEMBER 3, 2010.

CONSULTING ENGINEERS 1560 WALL ST, SUITE 222	DESIGNED - MJY	REVISED -
	DRAWN - ST	REVISED -
	CHECKED - MJY	REVISED -
NAPERVILLE, ILLINOIS 60563 PH; (630) 577-9100	DATE - 07/08/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL NOTES, INDE IL ROUTE 58 (GOI	
SHEET NO. 2 OF 33 SHEETS	STA. 492+55 TO STA. 498+45

A.U. SECTION COUNTY TOTAL SHEETS NO. 320 S81 8-1 COOK 33 2

D-91-288-09 CONTRACT NO. 60F91

ID. ROAD DIST, NO. | ILLINOIS| FED. AID PROJECT