

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					CODE NO	ITEM	UNIT	TOTAL QUANTITIES				
				1000-2A								1000-2A			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	263	263				44213200	SAW CUTS	FOOT	285	285			
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	20	20				48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	568	568			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1				Δ 55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1				60250200	CATCH BASINS TO BE ADJUSTED	EACH	9	9			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1				60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2			
* 25100630	EROSION CONTROL BLANKET	SQ YD	20	20				60255500	MANHOLES TO BE ADJUSTED	EACH	3	3			
* 25200110	SODDING, SALT TOLERANT	SQ YD	20	20				60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1			
* 25200200	SUPPLEMENTAL WATERING	UNIT	1	1				60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1	1				60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	12	12			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	86	86				60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	40	40			
40600300	AGGREGATE (PRIME COAT)	TON	410	410				60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	428	428			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	154	154				67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				67100100	MOBILIZATION	L SUM	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	148	148				70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	815	815				70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8846	8846				70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
42001300	PROTECTIVE COAT	SQ YD	1865	1865				70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	102246	102246				70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	18	18			
44000300	CURB REMOVAL	FOOT	70	70				70300100	SHORT-TERM PAVEMENT MARKING	FOOT	15165	15165			
44000400	GUTTER REMOVAL	FOOT	70	70				70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	372	372			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5420	5420				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80382	80382			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	428	428				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	695	695			
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	4843	4843				70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2030	2030			
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	100	100				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1731	1731			
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	130	130				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	411	411			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	790	790				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	36475	36475			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	480	480				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	372	372			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	2080	2080				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	80382	80382			
44201774	CLASS D PATCHES, TYPE I, 1 1/4 INCH	SQ YD	6	6											
44201777	CLASS D PATCHES, TYPE II, 1 1/4 INCH	SQ YD	700	700											
44201781	CLASS D PATCHES, TYPE III, 1 1/4 INCH	SQ YD	360	360											
44201783	CLASS D PATCHES, TYPE IV, 1 1/4 INCH	SQ YD	962	962											
44201787	CLASS D PATCHES, TYPE IV, 1 3/4 INCH	SQ YD	85	85											