

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25	25						70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4650	4650					
40600300	AGGREGATE (PRIME COAT)	TON	115	115						70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	634	634					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10						70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12400	12400					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2						70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3600	3600					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	270	270						70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	260	260					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	178.5	178.5						70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	410	410					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2780	2780						70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	540	540					
42001300	PROTECTIVE COAT	SO YD	20	20						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	520	520					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL. 2 1/2"	SO YD	28305	28305						* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	634	634					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100						* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12400	12400					
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SO YD	850	850						* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3600	3600					
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SO YD	425	425						* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	260	260					
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SO YD	170	170						* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	410	410					
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SO YD	255	255						* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	540	540					
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200						* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	160	160					
60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	1	1						78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	120	120					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3						* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1597	1597					
60250400	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1						X0322256	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8					
60260100	INLETS TO BE ADJUSTED	EACH	5	5						X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1120	1120					
60261530	INLETS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	3	3						NP Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15	15															
60404400	FRAMES AND GRATES, TYPE 4	EACH	2	2															
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	6	6															
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1															
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1															
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1															

NP= Non-participating
* = Specialty Items