STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

Threaded or Coil

Splicer Rods (E)

SHEET NO. FARTE SECTION TOTAL SHEETS 2843 3249B-R COOK 64 42 FED.ROAD DIST.NO. ILLINOIS FED. AID PROJECT-

Sheet 18 of 22

Contract No. 62539

NOTES

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length.

All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Officer systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

- Minimum Capacity 1.25 x fy x A_t

 Minimum *Pull-out Strength = 0.66 x fy x A_t


 Tassian in kins) = 0.66 x fy x A_t (Tension in kips)

Where fy = Yield strength of lapped reinforcement bars in ksl.

- A_t = Tensile stress area of lapped reinforcement bars.

 * = 28 day concrete

BAR SPLICER ASSEMBLIES				
		Strength Requirements		
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length		Min. Pull-Out Strength kips - tension	
#4	1'-8''	14.7	7.9	
#5	2'-0"	23.0	12.3	
#6	2'-7''	33.1	17.4	
#7	3′-5″	45.1	23.8	
#8	4'-6''	58.9	31.3	
#9	5′-9′′	75.0	39.6	
#10	7′-3′′	95.0	50.3	
#11	9′-0′′	117.4	61.8	



BAR SPLICER ASSEMBLY ALTERNATIVES

** Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.

ROLLED THREAD DOWEL BAR

** ONE PIECE

WELDED SECTIONS

— Wire Connector

The diameter of this part

of the bar spliced.

is the same as the diameter

INSTALLATION AND SETTING METHODS

6'-0"

-Washer Face

<u>"B"</u>


<u>"A "</u>

Q 🛚

"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nalling to wood forms or cementing to steel forms. (E) : Indicates epoxy coating.


Stage Construction Line

Foam Pluas




FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

	Bai	Splicer f	or #5 bar	
Min.	Capacity	= 23.0 ki	ps - tensio	n
Min.	Pull-out	Strength =	= 12.3 kips	- tensior
No.	Reauired	= 108		



Min.	Capacity	= 23.0	kips -	tension	
Min.	Pull-out	Strength	= 12.3	kips -	tensio



STANDARD

Bar Size	No. Assemblies Required	Location
#5	554	Deck
#6	28	Diaphragm
#5	68	Piers
#7	16	Piers
#9	12	Abutments
#5	6	Abutments

REVISIONS		
NAME	DATE	

BAR SPLICER ASSEMBLY DETAILS

DIXIE HIGHWAY OVER BUTTERFIELD CREEK F.A.U. ROUTE 2843 SECTION 3249B-R STA. 78+55.00 COOK COUNTY STRUCTURE NUMBER 016-7946

SCALE: NOT-TO-SCALE DATE 6-25-09

DRAWN BY BV DESIGNED BY BS CHECKED BY PK

R M E Rubinos & Mesia Engineers, Inc.