
| CONTRACT NO. 62539 | F.A. | SECTION | COUNTY | TOTAL | SHEETS | NO. 2843 | 3249B-R | COOK | 64 | 53 | STA. | TO STA. | FED. ROAD DIST. NO. | ILLINOIS | FED. AID | PROJECT |



SEQUENCE OF CONSTRUCTION:

- 1. CLOSE EXISTING VALVE.
- 2. REMOVE EXISTING HYDRANT.
- 3. INSTALL HYDRANT EXTENSION AND NEW VALVE.
- 4. RELOCATE EXISTING HYDRANT.
- 5. OPEN EXISTING VALVE, REMOVE BOX.
- 6. BACKFILL.
- 7. FLUSH AND TEST FOR CHLORIDE RESIDUAL AND PROVIDE TEST.

ALL WORK TO BE DONE IN ACCORDANCE WITH ARTICLE 564 OF THE STANDARD SPECIFICATIONS. NEW VALVE AND BOX SHALL BE SAME MAKE AND MODEL AS EXISTING.

FIRE HYDRANT TO BE MOVED

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	ILLINOIS DECANTIMENT OF INMISCORTATIO
R. SHAH	09/09/94	F.A.U. 2843 DIXIE HWY over BUTTERFIELD CR
R. SHAH	10/25/94	
		FIRE HYDRANT
		TO BE MOVED
		TO DE MOVED
		VEDT

SCALE: VERT. NONE

DRAWN BY CHECKED BY

.07 0ATE = 3/5/2007 LE NAME = Kindistatahd36.di C) 5CALE = 58.0000 / N.