

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	I000-2A	Y007	Y031-1F	Y030-1E	Y060
				ROADWAY	CULVERT	TRAFFIC SIGNALS	LIGHTING	WATERMAIN
				80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL	80% FEDERAL / 20% LOCAL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	565	565				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	117	117				
20101000	TEMPORARY FENCE	FOOT	3000	3000				
20101100	TREE TRUNK PROTECTION	EACH	75	75				
X 20101200	TREE ROOT PRUNING	EACH	75	75				
X 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7	7				
20200100	EARTH EXCAVATION	CUYD	3322	3322				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CUYD	3230	3230				
20400800	FURNISHED EXCAVATION	CUYD	2688	2688				
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CUYD	139	139				
20800150	TRENCH BACKFILL	CUYD	175	110				65
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQYD	1548	1548				
X 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	11100	11100				
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100				
X 25000300	SEEDING, CLASS 3	ACRE	1.3	1.3				
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	178	178				
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	178	178				
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	178	178				
X 25100630	EROSION CONTROL BLANKET	SQ YD	6470	6470				
X 25200110	SODDING, SALT TOLERANT	SQ YD	4630	4630				
X 25200200	SUPPLEMENTAL WATERING	UNIT	70	70				
X 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	229	229				
28000510	INLET FILTERS	EACH	76	76				
28200200	FILTER FABRIC	SQ YD	45	45				
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	45	45				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	894	894				
35501302	HOT-MIX ASPHALT BASE COURSE, 4 1/2"	SQ YD	2418	2418				
35501306	HOT-MIX ASPHALT BASE COURSE, 5 1/2"	SQ YD	1346	1346				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6101	6101				
40600300	AGGREGATE (PRIME COAT)	TON	42	42				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				

X INDICATES SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN <i>BLG/KRK</i>	REVISED -		ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE			0326	06-00130-00-CH	WILL	116	4
		CHECKED <i>DJK</i>	REVISED -		SCALE:	SHEET NO. 1 OF 8 SHEETS		FED. ROAD DIST. NO. 7 ILLINOIS		CONTRACT NO. 63185		
		DATE <i>5-29-09</i>	REVISED -					FED. AID PROJECT M-8003(654)				