

SCHEDULE OF DRIVEWAYS				
STATION	DRIVEWAY REMOVAL (SQ YD)	PCC DRIVEWAY 6 INCH, SPECIAL (SQ YD)	PCC DRIVEWAY 8 INCH, SPECIAL (SQ YD)	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 4" (SQ YD)
136+87, LT (ESS)	19	24		
137+15, RT (ESS)	14	21		
138+12, RT (ESS)		14		
101+19, LT (HEN)	81		78	
114+49, LT (HEN)	146		99	
116+80, LT (HEN)	119			117
117+47, LT (HEN)	116		135	63

EARTHWORK SCHEDULE			
ITEM	UNIT	STAGE 1	STAGE 2
EARTH EXCAVATION	C.Y.	3312	10
EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	C.Y.	2815	9
EMBANKMENT REQUIRED	C.Y.	2687	1
EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	C.Y.	+128	+8

SHRINKAGE CALCULATED USING 15% SHRINKAGE FACTOR.

A PAY ITEM FOR "FURNISHED EXCAVATION" HAS BEEN INCLUDED ON THE ASSUMPTION THAT, DUE TO LIMITED WORKING SPACE, ALL EMBANKMENT MAY HAVE TO BE BROUGHT IN FROM OUTSIDE THE PROJECT LIMITS.

SCHEDULE OF TREE REMOVAL (ESSINGTON)		
STATION	6 TO 15 UNIT DIAMETER (SQ YD)	OVER 15 UNIT DIAMETER (SQ YD)
137+28, RT		28
137+64, RT	13	
138+26, RT	7	
138+26, RT	9	
138+32, RT	7	
138+55, RT	10	
139+11, RT		35
139+21, LT	10	
140+35, RT	7	
140+65, RT	8	
140+72, RT	11	
140+93, RT	12	
141+24, RT	7	
141+33, RT	11	
141+50, RT	11, 13	
141+58, RT	8	
141+70, RT	8	
141+92, RT	13	
142+18, RT		16
142+24, RT	8	
142+22, RT	8	
142+25, RT		20
142+29, RT	13	
142+42, RT	7	
142+46, RT	8	
142+29, RT		18
142+32, RT	8	
142+32, RT	6	
142+45, RT	7	
142+49, RT	8	
142+51, RT	7	
142+48, RT	6	
142+47, RT	7	
142+47, RT	8	
142+46, LT	7	
142+48, RT	8	
142+51, LT	6	
143+86, RT	11	
144+32, RT	10	

SCHEDULE OF TREE REMOVAL (HENNEPIN)		
STATION	6 TO 15 UNIT DIAMETER (SQ YD)	OVER 15 UNIT DIAMETER (SQ YD)
101+19, RT	6	
102+47, RT	6	
103+80, RT	6	
111+57, RT	6	
111+65, RT	9	
111+68, RT	9	
111+80, RT	7	
111+88, RT	9	
111+97, RT	8	
112+02, RT	9	
112+06, RT	8	
112+18, RT	6	
112+34, RT	13	
112+56, RT	8	
112+65, RT	6	
113+10, RT	11	
113+31, RT	7	
113+35, RT	8	
113+36, RT	6	
113+51, RT	6	
113+64, RT	9	
111+45, LT	6	
111+70, LT	6	
112+78, LT	7	
113+03, LT	6	
113+28, LT	10	
115+26, LT	9	
115+51, LT	8	
115+76, LT	9	
117+26, LT	12	
117+51, LT	9	
117+69, LT	6	
119+91, RT	6	

FILE NAME =	USER NAME =	DESIGNED <i>BLG/KRK</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES ESSINGTON ROAD AT HENNEPIN DRIVE AND MALL LOOP DRIVE		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN <i>BLG/KRK</i>	REVISED -				0326	06-00130-00-CH	WILL	116	15	
		CHECKED <i>DJK</i>	REVISED -		SCALE:		SHEET NO. 1 OF 1 SHEETS		CONTRACT NO. 63185			
		DATE <i>5-29-09</i>	REVISED -				FED. ROAD DIST. NO. 7 ILLINOIS		FED. AID PROJECT M-8003(654)			