SECTION COUNTY TOTAL SHEET NO. FAU RTE FAU 2779 08-00165-00-RS COOK 15 11 SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS ILLINOIS PROJECT ARA-9003(176) F.H.W.A. REG. CONTRACT NO. 63203 WORK ZONE EXIT OPENING - ARROWBOARD TYPE C (FLASHING A BAR OR 4-CORNER) FLAGGER BE PREPARED W20-1101(0)-48 TO STOP 36 x 36 8 CAPS 1000 8' (2.4 m) 5' (1.5 m) MIN. CLEAR HEIGHT FEET BLACK LEGEND ORANGE REFL. BACKGROUND 300' (90 m) MIN. DRUMS @ 50' (15 m) C-C TRAFFIC DIRECTION WORK ZONE ENTRY OPENING LEAVING (W21-I105) 5' (1.5 m) MIN. CLEAR HEIGHT 500' (150 m) [100' (30 m)] 200' (60 m) TRAFFIC DIRECTION - FLAGGER WITH CONTROL SIGN NOTES: 1. The Arrowboard, the Flagger Ahead trailer mounted sign, and the Trucks Leaving Highway sign shall be removed or turned away from traffic and the exit and entry openings shall be closed when the flagging operation ceases. 2. Work Zone Exit Openings should be a minimum of one half mile apart. 3. Exiting the work zone at any place other than at a Work Zone Exit Opening will be prohibited. ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN 4. All vehicles shall enter the work zone at entry openings, using their turn signals to warn motorists ILLINOIS DEPARTMENT OF TRANSPORTATION SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS SCALE: NONE DRAWN BY CADD CHECKED BY SHEET SIGNING FOR FLAGGING 11 0F 15

DATE NAME SCALE NAME PLOT FILE 1 USER

Frank Novotny & Associates, Inc.

CITY OF BERWYN, ILLINOIS EAST AVENUE LAPP RESURFACING MFT SECTION NO. 08-00165-00-RS

	K_	<u>t</u>					<u> </u>	_N_	_ >
NO.	BY	DATE		DESCRIPTION					
		1							

OPERATIONS AT WORK ZONE OPENINGS

PROJECT NO.	SCALE
06077	NONE
DRAWN/DESIGNED JEP/AMS	DATE APRIL, 2009
CHECKED/APPROVED	FIELD BOOK NO.
JFP/JEF	FILE

SHEETS

Civil Engineers/ 825 Midway Drive ♦ Willowbrook, IL ♦ 60527 ♦ Telephone: (630) 887-8640 ♦ Fax: (630) 887-0132

Municipal Consultants

| Illinois Professional Design Firm No. 104 00000