TRAFFIC SIGNAL LEGEND PROPOSED EXISTING CONTROLLER SERVICE INSTALLATION SIGNAL HEAD WITH BACKPLATE SIGNAL HEAD, PEDESTRIAN MAST ARM ASSEMBLY AND POLE, STEEL MAST ARM ASSEMBLY AND POLE, ALUMINUM COMBINATION MAST ARM ASSEMBLY AND POLE, STEEL WITH LUMINAIRE UNIT DUCT COMMON TRENCH HANDHOLE HEAVY DUTY HANDHOLE DOUBLE HANDHOLE G.S. CONDUIT IN TRENCH (T) OR PUSHED (P) PEDESTRIAN PUSHBUTTON DETECTOR CAST IRON JUNCTION BOX EMERGENCY VEHICLE LIGHT DETECTOR CONFIRMATION BEACON SIGNAL HEAD OFTICALLY PROGRAMMED CONDUIT SPLICE WOOD POLE RACEWAY FOR MAGNETIC DETECTOR, TYPE I OR TYPE II VEHICLE DETECTOR, NON COMPENSATED MAGNETIC TYPE RAILROAD CONTROL CABINET 8>8 E TELEPHONE CONNECTION ILLUMINATED SIGN

ILLUMINATED SIGN UNINTERRUPTIBLE POWER SUPPLY GENERAL NOTES

1) CONTRACTOR'S ATTENTION IS DRAWN TO DETECTOR LOOP DIVE HOLES THAT MAYBE WITHIN OR UNDER CURB TO BE REMOVED & REPLACED (ANY DAMAGE CAUSED TO DETECTOR LOOP LEAD-IN CABLE OR RACEWAYS SHALL BE REPAIRED BY CONTRACTOR AT THEIR EXPENSE. NO ADDITIONAL COMPENSATION WILL BE ALLOWED)

SECTION COUNTY RTE. SECTION 379 08-00187-00-BT COOK

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

2) DETECTABLE WARNING PLATES SHALL BE SUPPLIED AT ALL DEPRESSED CURB CUTS AS REQUIRED BY THE VILLAGE OF ARLINGTON HEIGHTS FROM THE MANUFACTURER IDENTIFIED IN THE SPECIAL PROVISIONS. (TYP)

3) ADDED NOTES:

- A. THE CONTRACTOR SHALL INFORM THE CCHD DESIGN ENGINEER AT (312)603-1730
 PRIOR TO THE START OF ANY WORK ON THE CONTRACT. A MINIMUM OF FIVE (5)
 WORKING DAYS ADVANCE NOTICE IS REQUIRED.
 B. THE CONTRACTOR SHALL MARK LOCATIONS OF LOOPS AND CONTACT THE COUNTY
 DESIGN ENGINEER AT (312)603-1730 FOR LOCATION APPROVAL PRIOR TO CUTTING
 OF THE LOOPS. A MINIMUM OF FIVE (5) WORKING DAYS ADVANCE NOTICE IS REQUIRED. C. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE EXISTING TRAFFIC SIGNAL CABLES
- C. IT IS THE CONTRACTOR'S RESPONSIBILITY TO LOCATE EXISTING TRAFFIC SIGNAL CABLE AND CONDUITS.

 D. ALL ELECTRICAL CABLE SHALL HAVE A POLYVINYL CHLORIDE JACKET.

 E. CARE IS TO BE TAKEN AS NOT TO DAMAGE ANY OF THE EXISTING TRAFFIC SIGNAL CONDUIT AND EQUIPMENT IF ANY OF THE TRAFFIC SIGNAL CONDUIT AND EQUIPMENT IS DAMAGED, THE CONTRACTOR SHALL REPAIR AND/OR REPLACE THE CONDUIT AND/OR EQUIPMENT AT NO COST TO THE COUNTY.
- 4) INSTALL (30"X30") W11-1 WITH SUPPLEMENTARY (24"X12") W16-7p BICYCLE CROSSING WARNING SIGNS
- 5) PRIOR TO CONSTRUCTION A MEETING WILL BE HELD AT THE JOB SITE WITH REPRESENTATIVES OF THE COOK COUNTY HIGHWAY DEPARTMENT, TRAFFIC SIGNAL SECTION TO FIELD VERIFY THE THAT THE EXISTING TRAFFIC SIGNAL CONTROLLER IS COMPATIBLE WITH THE PROPOSED EMERGENCY VEHICLE PREEMPTION EQUIPMENT, AND CONFIRM INSTRUCTIONS FOR REWIRING THE
- 6) THE CONTRACTOR WILL BE RESPONSIBLE TO ACQUIRE ALL NECESSARY PERMITS OR BONDS AND TO SATISFY THE REQUIREMENTS OF THE COOK COUNTY HIGHWAY DEPARTMENT AND LAKE COUNTY FOREST PRESERVE DISTRICT.

