CODE NO.	ITEM	UNIT	QUANTITY 100
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQYD	25
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3930
40600300	AGGREGATE (PRIME COAT)	TON	80
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	30
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	850
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	220
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1700
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	25
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	500
42400800	DETECTABLE WARNINGS	SQ FT	10
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	19420
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50
44000600	SIDEWALK REMOVAL	SQFT	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800
44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	50
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQYD	50
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	50
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQYD	50
44201761	CLASS D PATCHES, TYPE I. 10 INCH	SQ YD	150
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	150
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	150
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	150
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	16700
60250200	CATCH BASINS TO BE ADJUSTED	EACH	10700
60250400	CATCH BASIN TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID		
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	. 1
60255500	MANHOLES TO BE ADJUSTED	EACH	2
		EACH	6
60255700	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	3
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	6
60260100	INLETS TO BE ADJUSTED	EACH	1
60262700	INLETS TO BE RECONSTRUCTED	EACH	1
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	7
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4700
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	600
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	110
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15030
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	710
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	760
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	60
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	92
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50
88600600	DETECTOR LOOP REPLACEMENT	FOOT	120
XX007366	HOT-MIX ASPHALT SURFACE REMOVAL AND REPLACEMENT, 3"	SQ YD	120
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1
200 10000			

F.A.	SECTION 09-00103-00-RS		COUNTY		TOTAL	SHEET NO.
2786				СООК	14	3
STA.			TO S	TA.		
FED. R	ILLINOIS		FED. AID PROJECT			

ILLINOIS DEPARTMENT OF TRANSPORTATION	REVISIONS		
ILLINOIS DEPARTMENT OF TRANSPORTATION	DATE	NAME	
VILLAGE OF MORTON GROVE			
LEHIGH AVENUE			
SUMMARY OF QUANTITIES			
SCALE: VERT. DRAWN BY: JFG			
HORIZ.			