

		100% STATE FUNDING							
SP	CODE NO.	ITEM	UNIT	URBAN	ROADWAY J000-2A	HIGHWAY LIGHTING Y030-1E	PEDESTRIAN BRIDGE STR NO 082-0394 X932-2A	RETAINING WALL STR NO 082-W228 Y007	RETAINING WALL STR NO 082-W229 Y007
				TOTAL QUANTITY					
	50300300	PROTECTIVE COAT	SQ YD	1,070				570	500
	50800205	REINFORCEMENT BARS, EPOXY COATED	FOUND	111,040			80,590	15,340	15,110
	50800515	BAR SPLICERS	EACH	36			36		
	50900805	PEDESTRIAN RAILING	FOOT	84					84
	50900810	PEDESTRIAN RAIL (SPECIAL)	FOOT	985				480	505
	51200957	FURNISHING METAL SHELL PILES 12" x 0.250"	FOOT	7,146			7,146		
	51202305	DRIVING PILES	FOOT	6,930			6,930		
	51203200	TEST PILE METAL SHELLS	EACH	2			2		
	51204650	PILE SHOES	EACH	110			110		
	51500100	NAME PLATES	EACH	1			1		
	52000110	PREFORMED JOINT STRIP SEAL	FOOT	113			113		
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2				
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	131	131				
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	7	7				
	550A0490	STORM SEWERS, CLASS A, TYPE 2 54"	FOOT	59	59				
	55100500	STORM SEWER REMOVAL 12"	FOOT	62	62				
	55100900	STORM SEWER REMOVAL 18"	FOOT	6	6				
	55102000	STORM SEWER REMOVAL 54"	FOOT	77	77				
	58700300	CONCRETE SEALER	SQ FT	622			622		
	59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	30	30				
	60107700	PIPE UNDERDRAINS 6"	FOOT	208	208				
	60200105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1	1				
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
	60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4				
	60260100	INLETS TO BE ADJUSTED	EACH	1	1				
	60500040	REMOVING MANHOLES	EACH	1	1				
	60500050	REMOVING CATCH BASINS	EACH	1	1				
	60600605	CONCRETE CURB, TYPE B	FOOT	118	118				
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.12	FOOT	111	111				
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.24	FOOT	56	56				
	63700805	CONCRETE BARRIER TRANSITION	FOOT	20	20				
	63700900	CONCRETE BARRIER BASE	FOOT	90	90				
	64200105	SHOULDER RUMBLE STRIP	FOOT	210	210				
	66400105	CHAIN LINK FENCE, 4'	FOOT	137	137				
	66400505	CHAIN LINK FENCE, 8'	FOOT	46	46				
	* 66A00200	NON-SPECIAL WASTE DISPOSAL	CU YD	3,905	3,905				
	66411900	TEMPORARY FENCE	FOOT	137	137				
	* 66A00210	HAZARDOUS WASTE DISPOSAL	CU YD	910	910				
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
	* 66A00450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1				
	67100100	MOBILIZATION	L SUM	1	1				
	* 66A00530	SOIL DISPOSAL ANALYSIS	EACH	2	2				
	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1				
	70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	5,585	5,585				

*specialty items

FILE NAME = DBTRI-76C47-sht-summa-y-02.dgn	USER NAME = millarda	DESIGNED - DJM	REVISED -					F.A.I. RTE. 64	SECTION 82-1-IHR	COUNTY ST. CLAIR	TOTAL SHEETS 93	SHEET NO. 6
	PLOT SCALE = 47.2222' / IN.	CHECKED - JL	REVISED -					SCALE: NONE		SHEET NO. 2 OF 4 SHEETS	STA.	TO STA.
	PLOT DATE = 6/16/2009	DATE - 05/01/09	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
											CONTRACT NO. 76C47	

Rev.