

# SUMMARY OF QUANTITIES

CONTRACT NO.				
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	06-00233-00-BT	ROCK ISLAND	75	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	80% FEDERAL 20% ROCK ISLAND	80% FEDERAL 20% MOLINE	80% FEDERAL 20% ROCK ISLAND	80% FEDERAL 20% MOLINE
				Y047 P. C. PATH	Y047 P. C. PATH	Y007 MINOR STRUCT.	Y007 MINOR STRUCT.
42400800	DETECTABLE WARNINGS	S. F.	32	16	16		
48100100	AGGREGATE SHOULDERS, TYPE A	TON	13	13			
50800105	REINFORCEMENT BARS	POUND	8,240				8,240
54003000	CONCRETE BOX CULVERTS	C. Y.	65				65
54200463	PIPE CULVERTS, TYPE 1, RCCP 48"	FOOT	206	206			
54200475	PIPE CULVERTS, TYPE 1, RCCP 60"	FOOT	236		236		
54207570	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 15"	FOOT	36	20	16		
54207585	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 30"	FOOT	32	32			
54214920	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 15"	EACH	6	4	2		
54214935	PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 30"	EACH	4	4			
66410200	CHAIN LINK FENCE (SPECIAL)	FOOT	683	227	456		
67100100	MOBILIZATION	L. S.	1	0.25	0.75		
70103700	TRAFFIC CONTROL COMPLETE	L. S.	1	0.25	0.75		
XX003182	BOLLARDS COMPLETE (SET OF 3)	EACH	2	1	1		
*XX004339	BIKE PATH APPROACH GUARDRAIL ADJUSTMENT	FT.	50		50		

\* SPECIALTY ITEM

PLOT DATE \* DATE \*  
FILE NAME \* SCALE \*  
USER NAME \* NUMBER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

SCALE: NTS  
DATE 3/31/09

DRAWN BY PAR  
CHECKED BY BAJ