

SCHEDULE OF QUANTITIES

F.A. RTE.		SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		06-00233-00-BT	ROCK ISLAND	75	11
STA.		TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT		

48100100 AGGREGATE SHOULDERS, TYPE A	TON	66410200 CHAIN LINK FENCE (SPECIAL)	FOOT
ROCK ISLAND SEGMENT		ROCK ISLAND SEGMENT	
LT. STA. 100+20.86 TO 102+68.57 (TRAILHEAD)	13	LT. STA. 4+71 TO 5+75	106
		RT. STA. 4+48 TO 5+53	121
TOTAL	13		
50800105 REINFORCEMENT BARS	LB.	MOLINE SEGMENT	
MOLINE SEGMENT		LT. STA. 1+17 TO 2+14	102
STA. 11+57.63	2,280	RT. STA. 1+17 TO 2+14	116
STA. 24+90.93	5,960	LT. STA. 11+30 TO 11+81	51
		RT. STA. 11+30 TO 11+81	45
TOTAL	8,240	LT. STA. 24+54 TO 25+21	71
		RT. STA. 24+54 TO 25+21	71
		TOTAL	683
54003000 CONCRETE BOX CULVERTS	C. Y.	67100100 MOBILIZATION	L. S.
MOLINE SEGMENT		ROCK ISLAND SEGMENT	0.25
STA. 11+57.63	16.5	MOLINE SEGMENT	0.75
STA. 24+90.93	48.6		
TOTAL	65	TOTAL	1
54200463 PIPE CULVERTS, TYPE 1, RCCP 48"	FOOT	70103700 TRAFFIC CONTROL COMPLETE	L. S.
ROCK ISLAND SEGMENT		ROCK ISLAND SEGMENT	0.25
STA. 4+95.30	48	MOLINE SEGMENT	0.75
STA. 5+02.43	44		
STA. 5+09.50	40	TOTAL	1
STA. 5+16.55	38		
STA. 5+23.57	36	XX003182 BOLLARDS COMPLETE (SET OF 3)	EACH
TOTAL	206	ROCK ISLAND SEGMENT	
		STA. 500+05	1
54200475 PIPE CULVERTS, TYPE 1, RCCP 60"	FOOT	MOLINE SEGMENT	
MOLINE SEGMENT		STA. 27+05	1
STA. 1+50.79	52	TOTAL	2
STA. 1+57.53	49		
STA. 1+64.11	47	XX004339 BIKE PATH APPROACH GUARDRAIL ADJUSTMENT	FT.
STA. 1+70.57	45		
STA. 1+76.99	43	MOLINE SEGMENT	
TOTAL	236	STA. 0+00 TO 0+50	50
		TOTAL	50
54207570 PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 15"	FOOT		
ROCK ISLAND SEGMENT			
STA. 500+20.14	10		
STA. 509+75	10		
MOLINE SEGMENT			
STA. 7+76.20	16		
TOTAL	36		
54207585 PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ARCH, EQUIVALENT ROUND-SIZE 30"	FOOT		
ROCK ISLAND SEGMENT			
STA. 502+66.21	16		
STA. 502+73.80	16		
TOTAL	32		
54214920 PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 15"	EACH		
ROCK ISLAND SEGMENT			
6.3' LT. STA. 500+20.14	1		
15.8' RT. STA. 500+20.14	1		
6.3' LT. STA. 509+75	1		
16.0' RT. STA. 509.75	1		
MOLINE SEGMENT			
8.3' LT. STA. 7+76.20	1		
19.3' RT. STA. 7+76.20	1		
TOTAL	6		
54214935 PRECAST REINFORCED CONCRETE FLARED END SECTIONS-ARCH, EQUIVALENT ROUND-SIZE 30"	EACH		
ROCK ISLAND SEGMENT			
9.2' LT. STA. 502+66.21	1		
18.8' RT. STA. 502+66.21	1		
9.2' LT. STA. 502+73.80	1		
18.8' RT. STA. 502+73.80	1		
TOTAL	4		

EARTHWORK SCHEDULE						
LOCATION	EARTH		CHANNEL	EARTH		EMBANKMENT
	EXCAVATION SUITABLE	EXCAVATION UNSUITABLE	EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE *		
	C. Y.	C. Y.	C. Y.	C. Y.		C. Y.
ROCK ISLAND SEGMENT						
STA. 500+00 TO 512+00 (MAINLINE)	0	530		0	1,300	-1,300
STA. 175+80 TO 176+60 (RAMP)	0	0		0	675	-675
MOLINE SEGMENT						
STA. 0+00 TO 5+50 (RAMP)	41	0		31	2,726	-2,695
STA. 5+50 TO 38+00 (MAINLINE)	1,016	368		762	2,225	-1,463
STA. 377+73 TO 380+78 (FLOOD STORAGE AREA)			946			
TOTAL	1,057	898	946	793	6,926	-6,133
* ADJUSTED FOR SHRINKAGE FACTOR OF 25%						

PLOT DATE * \$DATE\$
 FILE NAME * \$FILEL\$
 PLOT SCALE * \$SCALE\$
 USER NAME * \$USER\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NTS
 DATE 3/31/09

DRAWN BY PAR
 CHECKED BY BAJ